



# Awel y Môr Offshore Wind Farm

## Category 6: Environmental Statement

### Volume 2, Chapter 7: Marine Mammals

Date: May 2022

Revision: C

Application Reference: 6.2.7

Pursuant to: APFP Regulation 5(2)(a)



| REVISION | DATE           | STATUS/<br>REASON<br>FOR ISSUE | AUTHOR:            | CHECKED<br>BY: | APPROVED<br>BY: |
|----------|----------------|--------------------------------|--------------------|----------------|-----------------|
| A        | August<br>2021 | PEIR                           | SMRU<br>Consulting | RWE            | RWE             |
| B        | March<br>2022  | ES                             | SMRU<br>Consulting | RWE            | RWE             |
| C        | May<br>2022    | ES                             | GoBe               | RWE            | RWE             |
|          |                |                                |                    |                |                 |
|          |                |                                |                    |                |                 |

[www.awelymor.cymru](http://www.awelymor.cymru)

RWE Renewables UK Swindon Limited

Windmill Hill Business Park  
Whitehill Way  
Swindon  
Wiltshire SN5 6PB  
T +44 (0)8456 720 090  
[www.rwe.com](http://www.rwe.com)

Registered office:  
RWE Renewables UK Swindon Limited  
Windmill Hill Business Park  
Whitehill Way  
Swindon



# Contents

|          |                                                             |    |
|----------|-------------------------------------------------------------|----|
| <u>7</u> | Marine mammals.....                                         | 18 |
| 7.1      | Introduction.....                                           | 18 |
| 7.2      | Statutory and policy context.....                           | 19 |
| 7.2.1    | Overview of Welsh Planning Policy .....                     | 37 |
|          | Welsh National Marine Plan .....                            | 37 |
|          | Future Wales – The National Plan .....                      | 42 |
| 7.3      | Consultation and scoping .....                              | 42 |
| 7.4      | Scope and methodology.....                                  | 55 |
| 7.4.1    | Study area .....                                            | 55 |
| 7.4.2    | Baseline data sources .....                                 | 58 |
| 7.4.3    | Underwater noise modelling .....                            | 59 |
|          | Piling parameters - WTGs.....                               | 59 |
|          | Piling parameters – OSPs and Met mast.....                  | 61 |
|          | Piling parameters – Cofferdam sheet piles.....              | 61 |
|          | PTS assessment.....                                         | 62 |
|          | Swimming speed.....                                         | 63 |
|          | TTS Assessment .....                                        | 64 |
|          | Disturbance assessment – piling .....                       | 65 |
|          | Disturbance assessment - UXO .....                          | 71 |
|          | Disturbance assessment – other construction activities..... | 75 |
| 7.5      | Assessment criteria and assignment of significance .....    | 75 |
| 7.5.1    | Sensitivity to PTS.....                                     | 80 |
|          | Expert elicitation on PTS sensitivity .....                 | 80 |
|          | Other PTS-onset information .....                           | 89 |
|          | PTS sensitivity conclusions .....                           | 90 |
| 7.5.2    | VHF cetacean sensitivity to pile driving disturbance .....  | 91 |
| 7.5.3    | HF Cetacean sensitivity to pile driving disturbance.....    | 95 |
|          | Bottlenose dolphin .....                                    | 95 |

|                                                                 |     |
|-----------------------------------------------------------------|-----|
| Common dolphin.....                                             | 96  |
| Risso's dolphin .....                                           | 97  |
| 7.5.4 LF cetacean sensitivity to pile driving disturbance ..... | 98  |
| 7.5.5 Seal sensitivity to pile driving disturbance .....        | 98  |
| 7.5.6 Harbour porpoise sensitivity to vessels .....             | 101 |
| 7.5.7 Dolphin sensitivity to vessels .....                      | 103 |
| 7.5.8 Minke whale sensitivity to vessels .....                  | 103 |
| 7.5.9 Grey seal sensitivity to vessels.....                     | 104 |
| 7.5.10 Sensitivity summary .....                                | 104 |
| 7.6 Uncertainty and technical difficulties encountered .....    | 105 |
| 7.7 Existing environment.....                                   | 105 |
| 7.7.1 Evolution of the baseline .....                           | 111 |
| 7.8 Key parameters for assessment .....                         | 113 |
| 7.9 Mitigation measures .....                                   | 123 |
| 7.10 Environmental assessment: construction phase.....          | 125 |
| 7.10.1 PTS from piling .....                                    | 125 |
| Harbour porpoise .....                                          | 125 |
| Bottlenose, common and Risso's dolphin.....                     | 127 |
| Minke whale .....                                               | 128 |
| Grey seal 130                                                   |     |
| Cofferdam sheet piles.....                                      | 131 |
| PTS summary .....                                               | 132 |
| 7.10.2 TTS from piling.....                                     | 133 |
| 7.10.3 Disturbance from piling .....                            | 135 |
| Harbour porpoise .....                                          | 135 |
| Bottlenose dolphin .....                                        | 140 |
| Common dolphin.....                                             | 146 |
| Risso's dolphin .....                                           | 148 |
| Minke whale .....                                               | 150 |
| Grey seal 151                                                   |     |

|                                                                               |     |
|-------------------------------------------------------------------------------|-----|
| Cofferdam sheet piles.....                                                    | 160 |
| Disturbance summary .....                                                     | 162 |
| 7.10.4 Other construction activities .....                                    | 162 |
| PTS from other construction activities.....                                   | 162 |
| Disturbance from other construction activities.....                           | 165 |
| 7.10.5 PTS-onset from UXO.....                                                | 167 |
| 7.10.6 Disturbance from UXO .....                                             | 170 |
| 26 km EDR – High order .....                                                  | 171 |
| 5 km EDR – Low order.....                                                     | 173 |
| Fixed noise threshold: TTS-onset.....                                         | 174 |
| 7.10.7 Collision risk from construction vessels .....                         | 177 |
| 7.10.8 Disturbance from construction vessels .....                            | 182 |
| 7.10.9 Change in water quality from construction activities.....              | 183 |
| 7.10.10 Change in fish abundance/distribution from construction activities... | 184 |
| 7.11 Environmental assessment: operational phase.....                         | 188 |
| 7.11.1 Barrier effects from operation .....                                   | 189 |
| 7.11.2 Collision risk from O&M vessels .....                                  | 190 |
| 7.11.3 Disturbance from O&M vessels .....                                     | 191 |
| 7.11.4 Change in water quality from operation .....                           | 192 |
| 7.11.5 Change in fish abundance/distribution from operation.....              | 192 |
| 7.12 Environmental assessment: decommissioning phase.....                     | 194 |
| 7.12.1 PTS and disturbance from decommissioning.....                          | 194 |
| 7.12.2 Collision risk from decommissioning vessels .....                      | 195 |
| 7.12.3 Disturbance from decommissioning vessels .....                         | 196 |
| 7.12.4 Change in water quality from decommissioning .....                     | 197 |
| 7.12.5 Change in fish abundance/distribution from decommissioning.....        | 198 |
| 7.13 Environmental assessment: cumulative effects .....                       | 199 |
| 7.13.1 Disturbance from underwater noise.....                                 | 205 |
| Harbour porpoise .....                                                        | 213 |
| Bottlenose dolphin .....                                                      | 215 |

|                                              |     |
|----------------------------------------------|-----|
| Risso's dolphin .....                        | 217 |
| Common dolphin.....                          | 218 |
| Minke whale .....                            | 219 |
| Grey seal 223                                |     |
| 7.13.2 Disturbance from vessel activity..... | 224 |
| 7.14 Inter-relationships.....                | 234 |
| 7.15 Transboundary effects.....              | 235 |
| 7.16 Summary of effects .....                | 236 |
| 7.17 References .....                        | 241 |

## Figures

|                                                                                                                                                                                                                                                                                                                                 |    |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----|
| Figure 1: Marine mammal regional scale study area (Management Units). ....                                                                                                                                                                                                                                                      | 56 |
| Figure 2: Marine mammal AyM study area (site-specific survey area).....                                                                                                                                                                                                                                                         | 57 |
| Figure 3: Relationship between the proportion of porpoise responding and the received single strike SEL ( $SEL_{ss}$ ) (Graham et al. 2017a).....                                                                                                                                                                               | 67 |
| Figure 4 The probability of a harbour porpoise response (24 h) in relation to the partial contribution of (a) distance from piling and (b) audiogram-weighted received single-pulse SEL for the first location piled (solid navy line) and the final location piled (dashed blue line). Obtained from Graham et al. (2019)..... | 68 |
| Figure 5: Predicted decrease in seal density as a function of estimated sound exposure level, error bars show 95% CI (from Whyte et al 2020). ....                                                                                                                                                                              | 71 |
| Figure 6: Probability distribution showing the consensus distribution for the effects on fertility of a mature female harbour porpoise as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.....                                                                                                                    | 82 |
| Figure 7: Probability distribution showing the consensus distribution for the effects on survival of a mature female harbour porpoise as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.....                                                                                                                     | 83 |
| Figure 8: Probability distribution showing the consensus distribution for the effects on survival of juvenile or dependent calf harbour porpoise as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band. ....                                                                                                         | 83 |
| Figure 9: Probability distribution showing the consensus distribution for the effects on fertility of mature female bottlenose dolphin as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.....                                                                                                                    | 85 |

|                                                                                                                                                                                                                                                                                                                  |     |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Figure 10: Probability distribution showing the consensus distribution for the effects on survival of mature female bottlenose dolphin as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.....                                                                                                     | 85  |
| Figure 11: Probability distribution showing the consensus distribution for the effects on survival of juvenile or dependent calf bottlenose dolphin as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band. ....                                                                                       | 86  |
| Figure 12: Probability distribution showing the consensus distribution for the effects on fertility of a mature female (harbour or grey) seal as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.....                                                                                              | 87  |
| Figure 13: Probability distribution showing the consensus distribution for the effects on survival of a mature female (harbour or grey) seal as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band. ....                                                                                              | 88  |
| Figure 14: Probability distribution showing the consensus distribution for the effects on survival of juvenile or dependent pup (harbour or grey) seal as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band. ....                                                                                    | 88  |
| Figure 15: Probability distributions showing the consensus of the expert elicitation for harbour porpoise disturbance from piling (Booth et al., 2019). ....                                                                                                                                                     | 93  |
| Figure 16: The probability of harbour porpoise occurrence and buzzing activity per hour during (dashed red line) and out with (blue line) pile-driving hours, in relation to distance from the pile-driving vessel at Beatrice (left) and Moray East (right). Obtained from Benhemma-Le Gall et al. (2021). .... | 94  |
| Figure 17: Probability distributions showing the consensus of the expert elicitation for grey seal disturbance from piling (Booth et al., 2019). ....                                                                                                                                                            | 101 |
| Figure 18: Behavioural disturbance dose-response contours for the installation of a monopile at the NW location. ....                                                                                                                                                                                            | 139 |
| Figure 19: Behavioural disturbance dose-response contours for the installation of a monopile at the NW location, in relation to the bottlenose dolphin higher density area within the 20 m depth contour. ....                                                                                                   | 141 |
| Figure 20: Population trajectory for both the impacted and un-impacted bottlenose dolphin population resulting from 201 days of piling disturbance.....                                                                                                                                                          | 145 |
| Figure 21: Behavioural disturbance dose-response contours for the installation of a monopile at the NW location, in relation to the grey seal at-sea density estimates. ....                                                                                                                                     | 153 |
| Figure 22: Population trajectory for both the impacted and un-impacted grey seal OSPAR Region III MU (left) and the Wales & NW England's MU (right) resulting from 201 days of piling disturbance. ....                                                                                                          | 158 |
| Figure 23: Vessel Types – Winter 2020 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline). ....                                                                                                                                                                                 | 178 |
| Figure 24 Vessel Types – Summer 2021 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline). ....                                                                                                                                                                                  | 178 |

|                                                                                                                                                                         |     |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Figure 25: Unique Vessels Per Day – Winter 2020 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline). .....                             | 179 |
| Figure 26: Unique Vessels Per Day – Summer 2021 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline). .....                             | 179 |
| Figure 27: Vessel Type Distribution – Winter 2020 and Summer 2021 Survey Periods combined (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline). ..... | 180 |
| Figure 28: Projects considered within the marine mammal CEA for disturbance from underwater noise.....                                                                  | 210 |

## Tables

|                                                                                                                                          |     |
|------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Table 1: Summary of NPS EN-1 and EN-3 and Draft Overarching NPS EN-1 and EN-3 policy relevant to marine mammals and AyM.....             | 21  |
| Table 2: WNMP policies of relevance to marine mammals.....                                                                               | 38  |
| Table 3: Summary of consultation relating to marine mammals. ....                                                                        | 43  |
| Table 4: Piling parameters for monopiles. ....                                                                                           | 60  |
| Table 5: Piling parameters for multi-leg pin-piled jackets. ....                                                                         | 60  |
| Table 6: Piling parameters for cofferdam sheet piling.....                                                                               | 61  |
| Table 7: PTS-onset thresholds for impulsive noise (from Southall et al 2019). ....                                                       | 62  |
| Table 8: TTS-onset thresholds for impulsive noise (from Southall et al 2019).....                                                        | 64  |
| Table 9: Impact magnitude definitions. ....                                                                                              | 76  |
| Table 10: Sensitivity/importance of the environment. ....                                                                                | 77  |
| Table 11: Matrix to determine effect significance.....                                                                                   | 79  |
| Table 12: Predicted decline in harbour porpoise vital rates for different percentiles of the elicited probability distribution.....      | 82  |
| Table 13: Predicted decline in bottlenose dolphin vital rates for different percentiles of the elicited probability distribution.....    | 84  |
| Table 14: Predicted decline in harbour and grey seal vital rates for different percentiles of the elicited probability distribution..... | 87  |
| Table 15: Summary of key marine mammal sensitivity assessments. ....                                                                     | 105 |
| Table 16: Marine mammal MU and density estimates (#/km <sup>2</sup> ) taken forward to impact assessment. ....                           | 106 |
| Table 17: Summary of the conservation status of each marine mammal species (FV = Favourable, XX = Unknown, + = Improving). ....          | 112 |
| Table 18: Maximum design scenario.....                                                                                                   | 114 |
| Table 19: Mitigation measures relating to marine mammals.....                                                                            | 123 |

|                                                                                                                                                                                                                                                           |     |
|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Table 20: Impact area, maximum range, number of harbour porpoise predicted to experience PTS-onset from piling. ....                                                                                                                                      | 127 |
| Table 21: Impact area and maximum range for bottlenose, common and Risso's dolphins predicted to experience PTS-onset from piling. ....                                                                                                                   | 128 |
| Table 22: Impact area, maximum range and number of minke whales predicted to experience PTS-onset from piling. ....                                                                                                                                       | 130 |
| Table 23: Impact area, maximum range and number of grey seals predicted to experience PTS-onset from piling. ....                                                                                                                                         | 131 |
| Table 24: Impact area and maximum range for PTS-onset from piling of cofferdam sheet piles. ....                                                                                                                                                          | 132 |
| Table 25: Summary of the assessment for PTS-onset from pile driving for each marine mammal species. ....                                                                                                                                                  | 133 |
| Table 26: TTS-onset impact area (km <sup>2</sup> ) and maximum range (km) for each marine mammal hearing group. ....                                                                                                                                      | 134 |
| Table 27: Impact area and maximum range for TTS-onset from piling of cofferdam sheet piles. ....                                                                                                                                                          | 135 |
| Table 28: Number of harbour porpoise and percentage of the MU predicted to experience potential behavioural disturbance from piling. ....                                                                                                                 | 137 |
| Table 29: Calculation of the number of harbour porpoise predicted to experience behavioural disturbance for the installation of a monopile at the NW location, using the JCP III density estimate and the Graham et al. (2017a) dose-response curve. .... | 138 |
| Table 30: Number of bottlenose dolphins and percentage of the MU predicted to experience potential behavioural disturbance from piling. ....                                                                                                              | 140 |
| Table 31 Bottlenose dolphin population modelling inputs and results. ....                                                                                                                                                                                 | 142 |
| Table 32: Number of common dolphins predicted to experience potential behavioural disturbance from piling. ....                                                                                                                                           | 148 |
| Table 33: Number of Risso's dolphins predicted to experience potential behavioural disturbance from piling. ....                                                                                                                                          | 149 |
| Table 34: Number of minke whales and percentage of the MU predicted to experience potential behavioural disturbance from piling. ....                                                                                                                     | 151 |
| Table 35: Number of grey seals and percentage of the MU predicted to experience potential behavioural disturbance from piling. ....                                                                                                                       | 151 |
| Table 36: Grey seal population modelling inputs and results. ....                                                                                                                                                                                         | 154 |
| Table 37: Number of animals predicted to experience behavioural disturbance from piling of cofferdam sheet piles. ....                                                                                                                                    | 161 |
| Table 38: Summary of the assessment of disturbance from pile driving for each marine mammal species. ....                                                                                                                                                 | 162 |
| Table 39: Summary of the source level (SEL <sub>cum</sub> dB re 1 µPa@1m(RMS)) and impact ranges for the different construction noise sources using the non-impulsive criteria from Southall et al. (2019) ....                                           | 164 |

|                                                                                                                                                                                                                         |     |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Table 40: Summary of the potential for disturbance from dredging on marine mammal species. ....                                                                                                                         | 165 |
| Table 41: PTS-onset impact range for various potential UXO charge sizes. ....                                                                                                                                           | 169 |
| Table 42: Estimated number of marine mammals potentially at risk of disturbance during high-order UXO clearance (assuming an EDR of 26 km, resulting in a 2,123.72 km <sup>2</sup> impact area). ....                   | 171 |
| Table 43: Estimated number of marine mammals potentially at risk of disturbance during low-order UXO clearance (assuming an EDR of 5 km, resulting in a 78.54 km <sup>2</sup> impact area). ....                        | 173 |
| Table 44: TTS-onset impact ranges (SPL <sub>peak</sub> ) for various potential UXO charge sizes. ....                                                                                                                   | 175 |
| Table 45 TTS-onset impact ranges (SEL <sub>ss</sub> ) for various potential UXO charge sizes. ....                                                                                                                      | 176 |
| Table 46: Key prey species of the marine mammal receptors (bold = species present at AyM). ....                                                                                                                         | 186 |
| Table 47: Description of tiers of other developments considered within the marine mammal cumulative effect assessment. ....                                                                                             | 200 |
| Table 48: Cumulative MDS for marine mammals. ....                                                                                                                                                                       | 204 |
| Table 49: Indicative construction schedule for AyM. ....                                                                                                                                                                | 207 |
| Table 50: Projects considered within the marine mammal CEA for disturbance from underwater noise, including relevant species (according to Management Units). ....                                                      | 208 |
| Table 51: OWF projects constructing or decommissioning at the same time as AyM is constructing (± 1 year), in addition to seismic surveys in the Irish Sea and the North Sea. ....                                      | 211 |
| Table 52: Number of harbour porpoise disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing (± 1 year). ....                | 214 |
| Table 53: Number of bottlenose dolphins disturbed (per day of impact) for OWF projects under construction or decommissioning and ongoing seismic surveys at the same time as AyM is under construction (± 1 year). .... | 217 |
| Table 54: Number of Risso's dolphins disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing (± 1 year). ....                | 220 |
| Table 55: Number of common dolphins disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing (± 1 year). ....                 | 220 |
| Table 56: Number of minke whales disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing (± 1 year). ....                    | 221 |
| Table 57: Number of grey seals disturbed (per day of impact) for OWF projects under construction or decommissioning and ongoing seismic surveys at the same time as AyM is under construction (± 1 year). ....          | 224 |



|                                                                                                                                                                  |     |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|
| Table 58: Projects considered within the marine mammal CEA for disturbance from vessel activity.....                                                             | 228 |
| Table 59: Level of vessel activity anticipated for each project included in the marine mammal CEA. ....                                                          | 229 |
| Table 60: Summary of effects (HP = harbour porpoise, BND = bottlenose dolphin, CD = common dolphin, RD = Risso's dolphin, MW = minke whale, GS = grey seal)..... | 237 |

# Glossary of terms

| TERM                            | DEFINITION                                                                                                                                                                                                                                                                                                                                                              |
|---------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Permanent Threshold Shift (PTS) | A total or partial permanent loss of hearing at a particular frequency caused by some kind of acoustic trauma. PTS results in irreversible damage to the sensory hair cells of the ear, and thus a permanent reduction of hearing acuity at that frequency.                                                                                                             |
| Sound Exposure Level (SEL)      | The constant sound level acting for one second, which has the same amount of acoustic energy, as indicated by the square of the sound pressure, as the original sound. It is the time-integrated, sound-pressure-squared level. SEL is typically used to compare transient sound events having different time durations, pressure levels, and temporal characteristics. |
| Sound Pressure Level (SPL)      | The sound pressure level or SPL is an expression of the sound pressure using the decibel (dB) scale and the standard reference pressures of 1 $\mu$ Pa for water.                                                                                                                                                                                                       |
| Temporary Threshold Shift (TTS) | Temporary loss of hearing at a particular frequency as a result of exposure to sound over time. The mechanisms underlying TTS are not well understood, but there may be some temporary damage to the sensory cells. The duration of TTS varies depending on the nature of the stimulus, but there is generally recovery of full hearing over time.                      |
| Threshold                       | The threshold generally represents the lowest signal level an animal will detect in some statistically predetermined percent of presentations of a signal.                                                                                                                                                                                                              |

| TERM                   | DEFINITION                                                                                                                                                                                                                                                                    |
|------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Unweighted sound level | Sound levels which are 'raw' or have not been adjusted in any way, for example to account for the hearing ability of a species.                                                                                                                                               |
| Weighted sound level   | A sound level which has been adjusted with respect to a 'weighting envelope' in the frequency domain, typically to make an unweighted level relevant to a particular species. The overall sound level has been adjusted to account for the hearing ability of marine mammals. |

## Abbreviations and acronyms

| TERM   | DEFINITION                                                              |
|--------|-------------------------------------------------------------------------|
| ADD    | Acoustic Deterrent Device                                               |
| AyM    | Awel y Môr                                                              |
| BEIS   | Department for Business, Energy and Industrial Strategy                 |
| CEA    | Cumulative Effects Assessment                                           |
| DEPONS | Disturbance Effects on the Harbour Porpoise Population in the North Sea |
| EDR    | Effective Deterrence Range                                              |
| EEA    | European Economic Area                                                  |
| EIA    | Environmental Impact Assessment                                         |
| ES     | Environmental Statement                                                 |
| GyM    | Gwynt y Môr                                                             |
| HF     | High Frequency                                                          |
| HRGS   | High-resolution Geophysical site Surveys                                |
| IAMMWG | Inter-Agency Marine Mammal Working Group                                |

| TERM  | DEFINITION                                                                                                                                                             |
|-------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| IPC   | Infrastructure Planning Commission (note: the IPC was abolished in April 2012 and was replaced by the Secretary of State for Business, Energy and Industrial Strategy) |
| iPCoD | Interim Population Consequences of Disturbance                                                                                                                         |
| JCP   | Joint Cetacean Protocol                                                                                                                                                |
| JNCC  | Joint Nature Conservation Committee                                                                                                                                    |
| LF    | Low Frequency                                                                                                                                                          |
| MCZ   | Marine Conservation Zone                                                                                                                                               |
| MMMP  | Marine Mammal Mitigation Protocol                                                                                                                                      |
| MPA   | Marine Protected Area                                                                                                                                                  |
| MU    | Management Unit                                                                                                                                                        |
| MWDW  | Manx Whale and Dolphin Watch                                                                                                                                           |
| NPS   | National Policy Statement                                                                                                                                              |
| NRW   | Natural Resources Wales                                                                                                                                                |
| O&M   | Operation and Maintenance                                                                                                                                              |
| OWF   | Offshore Wind Farm                                                                                                                                                     |
| PAM   | Passive Acoustic Monitoring                                                                                                                                            |
| PEMP  | Project Environment Management Plan                                                                                                                                    |
| PINS  | Planning Inspectorate                                                                                                                                                  |
| PTS   | Permanent Threshold Shift                                                                                                                                              |
| RIAA  | Report to Inform Appropriate Assessment                                                                                                                                |
| SAC   | Special Area of Conservation                                                                                                                                           |

| TERM  | DEFINITION                                                    |
|-------|---------------------------------------------------------------|
| SCANS | Small Cetaceans in European Atlantic waters and the North Sea |
| SCOS  | Special Committee on Seals                                    |
| SEL   | Sound Exposure Level                                          |
| SNCB  | Statutory Nature Conservation Body                            |
| SoS   | Secretary of State                                            |
| SOV   | Service Operation Vessel                                      |
| SPA   | Special Protection Area                                       |
| SPL   | Sound Pressure Level                                          |
| SSSI  | Site of Special Scientific Interest                           |
| SWF   | Sea Watch Foundation                                          |
| TTS   | Temporary Threshold Shift                                     |
| UXO   | Unexploded Ordnance                                           |
| VHF   | Very High Frequency                                           |
| WNMP  | Welsh National Marine Plan                                    |

## Units

| UNIT | DEFINITION               |
|------|--------------------------|
| dB   | Decibel (sound pressure) |
| Hz   | Hertz (frequency)        |
| kHz  | Kilohertz (frequency)    |
| kJ   | Kilojoule (energy)       |

| UNIT            | DEFINITION                |
|-----------------|---------------------------|
| km              | Kilometres (distance)     |
| km <sup>2</sup> | Kilometres squared (area) |
| m               | Metres (distance)         |
| m/s             | Metres per second (speed) |
| μPa             | Micropascal (pressure)    |

# 7 Marine mammals

## 7.1 Introduction

- 1 This chapter of the Environmental Statement (ES) has been prepared by SMRU Consulting and assesses the potential effects on marine mammal ecology from the offshore works (including construction, operation and maintenance (O&M) and decommissioning) associated with Awel y Môr Offshore Wind Farm (hereafter referred to as AyM).
- 2 This chapter has been informed by the following ES chapters:
  - ▲ Volume 2, Chapter 1: Offshore Project Description (application ref: 6.2.1);
  - ▲ Volume 2, Chapter 2: Marine Geology, Oceanography and Physical Processes (application ref: 6.2.2);
  - ▲ Volume 2, Chapter 3: Marine Water and Sediment Quality (application ref: 6.2.3);
  - ▲ Volume 2, Chapter 6: Fish and Shellfish Ecology (application ref: 6.2.6);
  - ▲ Volume 4, Annex 7.1: Marine Mammal Baseline Characterisation Report (application ref: 6.4.7.1);
  - ▲ Volume 4, Annex 7.2: Outline Marine Mammal Mitigation Protocol (application ref: 6.4.7.2);
  - ▲ Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, Limitations and Uncertainties (application ref: 6.4.7.3);
  - ▲ Volume 4, Annex 6.2: Underwater Noise Technical Report (application ref: 6.4.6.2);
  - ▲ Volume 5 Annex 5.1: Report to Inform Appropriate Assessment (application ref: 5.2).

## 7.2 Statutory and policy context

- 3 This section identifies legislation and national and local policy of relevance to marine mammal ecology. The Planning Act 2008, Marine Works (Environmental Impact Assessment; EIA) Regulations 2007 (as amended), the Infrastructure Planning (EIA) Regulations 2017 (collectively referred to as 'the EIA Regulations'), and the Environment Act 1995 are considered along with the legislation relevant to marine mammal ecology.
- 4 The following section provides information regarding the legislative context surrounding the assessment of potential effects in relation to marine mammal ecology. In undertaking the assessment, the following policy and legislation has been considered:
  - The Infrastructure Planning (Environmental Impact Assessment) Regulations 2017;
  - The Conservation of Habitats and Species Regulations 2017;
  - The Environment (Wales) Act 2016;
  - Marine and Coastal Access Act 2009;
  - The Marine Works (Environmental Impact Assessment) Regulations 2007;
  - The Agreement on the Conservation of Small Cetaceans of the Baltic, North East Atlantic, Irish and North Seas (ASCOBANS) 1994;
  - EU Council Directive 92/ 43/ EEC on the conservation of natural habitats and of wild flora and fauna (the 'Habitats Directive');
  - OSPAR Convention 1992;
  - The Wildlife and Countryside Act 1981;
  - Convention on the Conservation of European Wildlife and Natural Habitats (the Bern Convention; 1979);
  - The Convention on the Conservation of Migratory Species of Wild Animals 1979;(the Bonn Convention);
  - Convention of International Trade in Endangered Species (CITES) 1975; and
  - The Conservation of Seals Act 1970.
- 5 Guidance on the issues to be assessed for offshore renewable energy developments has been obtained through reference to:



- The Overarching National Policy Statement (NPS) for Energy (NPS EN-1; Department for Energy and Climate Change (DECC 2011b);
  - The National Policy Statement for Renewable Energy Infrastructure (NPS EN-3; DECC 2011a);
  - The UK Marine Policy Statement (HM Government 2011);
  - The Welsh National Marine Plan (WNMP; Welsh Government 2019); and
  - Future Wales – the National Plan 2040.
- 6 The sections of National Policy Statement for Energy (EN-1) and for Renewable Energy Infrastructure (EN-3) relevant to marine mammals are listed in Table 1. In addition to the current NPS, draft NPSs have been consulted upon. The draft NPSs have been reviewed to determine the emerging expectations and changes from previous iterations of the NPSs. This includes the Draft Overarching NPS EN-1 (DECC, 2021a) and EN-3 (DECC, 2021b).

Table 1: Summary of NPS EN-1 and EN-3 and Draft Overarching NPS EN-1 and EN-3 policy relevant to marine mammals and AyM.

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |
|------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| NPS EN-1               | "Where the development is subject to EIA the applicant should ensure that the Environmental Statement (ES) clearly sets out any effects on internationally, nationally and locally designated sites of ecological or geological conservation importance, on protected species and on habitats and other species identified as being of principal importance for the conservation of biodiversity. The applicant should provide environmental information proportionate to the infrastructure where EIA is not required to help the IPC consider thoroughly the potential effects of a proposed project." (paragraph 5.3.3 in NPS EN-1) | The potential effects of AyM have been assessed in regard to international, national and local sites designated for ecological or geological features of conservation importance (see sections 7.10, 7.11 and 7.12). Direct or indirect effects on features of relevant Special Area of Conservation (SAC) and Special Protection Area (SPA) sites are also considered in the Habitats Regulations Assessment Screening Report and where relevant will be included in the Report to Inform Appropriate Assessment (RIAA). Important protected areas for marine mammals within their respective Management Units (MUs) are detailed in Volume 4: Annex 7.1: Marine Mammal Baseline. |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                          | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                     |
|------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | <p>“Many Sites of Special Scientific Interest (SSSI) are also designated as sites of international importance and will be protected accordingly. Those that are not, or those features of SSSIs not covered by an international designation, should be given a high degree of protection.” (paragraph 5.3.10 in NPS EN-1)</p> <p>“All National Nature Reserves are notified as SSSIs.” (paragraph 5.3.10 in NPS EN-1)</p>               | There are no marine mammal SSSIs which are considered to be at risk of effect from the construction, operation or decommissioning of AyM and as such, no further consideration of SSSIs has been given |
|                        | “Marine Conservation Zones (MCZs) introduced under the Marine and Coastal Access Act 2009 are areas that have been designated for the purpose of conserving marine flora and fauna, marine habitat or features of geological or geomorphological interest. The Secretary of State is bound by the duties in relation to MCZs imposed by Sections 125 and 126 of the Marine and Coastal Access Act 2009.” (paragraph 5.3.12 in NPS EN-1) | There are no marine mammal MCZs which are considered to be at risk of effect from the construction, operation or decommissioning of AyM and as such, no further consideration of MCZs has been given.  |
|                        | “Development proposals provide many opportunities for building-in beneficial biodiversity or geological features as part of good design. When considering                                                                                                                                                                                                                                                                               | Designated measures to be adopted as part of the AyM project are presented in Section 7.9.                                                                                                             |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                   | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                    |
|------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | proposals, the IPC should maximise such opportunities in and around developments, using requirements or planning obligations where appropriate." (paragraph 5.3.15 in NPS EN-1)                                                                                                                                                                                                                  |                                                                                                                                                                                                                       |
|                        | "Many individual wildlife species receive statutory protection under a range of legislative provisions" (paragraph 5.3.16 in NPS EN-1)                                                                                                                                                                                                                                                           | Relevant marine mammal policy and legislation listed in section 7.2.                                                                                                                                                  |
|                        | "Other species and habitats have been identified as being of principal importance for the conservation of biodiversity in England and Wales and thereby requiring conservation action. The Secretary of State should ensure that these species and habitats are protected from the adverse effects of development by using requirements or planning obligations." (paragraph 5.3.17 in NPS EN-1) | All species receptors, including those of principal importance for the conservation of biodiversity in Wales are summarised in section 7.7. Full details are provided in Volume 4: Annex 7.1: Marine Mammal Baseline. |
|                        | "The applicant should include appropriate mitigation measures as an integral part of the proposed development. In particular, the applicant should demonstrate that:                                                                                                                                                                                                                             | Embedded mitigation relevant for marine mammals to be adopted as part of the AyM project are detailed in Section 7.9.                                                                                                 |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                                                                                                                                                                                        |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | <ul style="list-style-type: none"> <li>During construction, they will seek to ensure that activities will be confined to the minimum areas required for the works;</li> <li>During construction and operation best practice will be followed to ensure that risk of disturbance or damage to species or habitats is minimised, including as a consequence of transport access arrangements;</li> <li>Habitats will, where practicable, be restored after construction works have finished."</li> </ul> <p>(paragraph 5.3.18 in NPS EN-1)</p>                                                                                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| Draft NPS EN-1         | <p>"Where the development is subject to EIA the applicant should ensure that the Environmental Statement (ES) clearly sets out any effects on internationally, nationally and locally designated sites of ecological or geological conservation importance, on protected species and on habitats and other species identified as being of principal importance for the conservation of biodiversity. The applicant should provide environmental information proportionate to the infrastructure where EIA is not required to help the IPC consider thoroughly the potential effects of a proposed project." (paragraph 5.4.3 of the Draft NPS EN-1)</p> | <p>The potential effects of AyM have been assessed in regard to international, national and local sites designated for ecological or geological features of conservation importance (see sections 7.10, 7.11 and 7.12). Direct or indirect effects on features of relevant Special Area of Conservation (SAC) and Special Protection Area (SPA) sites are also considered in the Habitats Regulations Assessment Screening Report and</p> |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                               | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                              |
|------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        |                                                                                                                                                                                                                                                                                                                                                                                                                                              | where relevant will be included in the Report to Inform Appropriate Assessment (RIAA). Important protected areas for marine mammals within their respective Management Units (MUs) are detailed in Volume 4: Annex 7.1: Marine Mammal Baseline. |
|                        | <p>"Many Sites of Special Scientific Interest (SSSI) are also designated as sites of international importance and will be protected accordingly. Those that are not, or those features of SSSIs not covered by an international designation, should be given a high degree of protection." (paragraph 5.4.9 of the Draft NPS EN-1)</p> <p>"Most National Nature Reserves are notified as SSSIs." (paragraph 5.4.9 of the Draft NPS EN-1)</p> | There are no marine mammal SSSIs which are considered to be at risk of effect from the construction, operation or decommissioning of AyM and as such, no further consideration of SSSIs has been given                                          |
|                        | "Marine Conservation Zones (MCZs) introduced under the Marine and Coastal Access Act 2009 are areas that have been designated for the purpose of conserving marine flora and fauna, marine habitat or features of geological or geomorphological interest. The Secretary                                                                                                                                                                     | There are no marine mammal MCZs which are considered to be at risk of effect from the construction, operation or decommissioning of AyM and as                                                                                                  |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                      | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                    |
|------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | of State is bound by the duties in relation to MCZs imposed by Sections 125 and 126 of the Marine and Coastal Access Act 2009." (paragraph 5.4.11 of the Draft NPS EN-1)                                                                                                                                                                            | such, no further consideration of MCZs has been given.                                                                                                                                                                |
|                        | "Development proposals provide many opportunities for building-in beneficial biodiversity or geological features as part of good design. When considering proposals, the IPC should maximise such opportunities in and around developments, using requirements or planning obligations where appropriate." (paragraph 5.4.14 of the Draft NPS EN-1) | Designated measures to be adopted as part of the AyM project are presented in Section 7.9.                                                                                                                            |
|                        | "Many individual wildlife species receive statutory protection under a range of legislative provisions" (paragraph 5.4.15 of the Draft NPS EN-1)                                                                                                                                                                                                    | Relevant marine mammal policy and legislation listed in section 7.2.                                                                                                                                                  |
|                        | "Other species and habitats have been identified as being of principal importance for the conservation of biodiversity in England and Wales and thereby requiring conservation action. The Secretary of State should ensure that these species and habitats are protected from the adverse effects of development by using                          | All species receptors, including those of principal importance for the conservation of biodiversity in Wales are summarised in section 7.7. Full details are provided in Volume 4: Annex 7.1: Marine Mammal Baseline. |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | SECTION WHERE COMMENT<br>ADDRESSED                                                                                         |
|------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------|
|                        | requirements or planning obligations." (paragraph 5.4.16 of the Draft NPS EN-1)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                            |
|                        | <p>"The applicant should include appropriate mitigation measures as an integral part of the proposed development. In particular, the applicant should demonstrate that:</p> <ul style="list-style-type: none"> <li>➤ During construction, they will seek to ensure that activities will be confined to the minimum areas required for the works;</li> <li>➤ During construction and operation best practice will be followed to ensure that risk of disturbance or damage to species or habitats is minimised, including as a consequence of transport access arrangements;</li> <li>➤ Habitats will, where practicable, be restored after construction works have finished." <p>(paragraph 5.4.18 of the Draft NPS EN-1)</p> </li></ul> | Mitigation relevant for marine mammals to be adopted as part of the AyM project are detailed in Section 7.9.               |
| NPS EN-3               | "Assessment of offshore ecology and biodiversity should be undertaken by the applicant for all stages of the lifespan of the proposed Offshore Wind Farm (OWF) and in accordance with the appropriate policy for OWF EIAs." (NPS EN-3 Paragraph 2.6.64)                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Construction, operation, maintenance and decommissioning phases of AyM have been assessed in sections 7.10, 7.11 and 7.12. |



| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                          | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                              |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | “Consultation on the assessment methodologies should be undertaken at early stages with the statutory consultees as appropriate.” (NPS EN-3 Paragraph 2.6.65)                                           | Consultations with relevant statutory and non-statutory stakeholders have been conducted throughout AyM (see Table 3 for a summary of consultation with regards to marine mammals).                             |
|                        | ▲ “Any relevant data that has been collected as part of post-construction ecological monitoring from existing, operational OWFs should be referred to where appropriate.” (NPS EN-3 Paragraph 2.6.66)   | Relevant data collected during post construction monitoring from other OWF projects as well as relevant scientific research and literature have informed the assessment of AyM in sections 7.10, 7.11 and 7.12. |
|                        | “The assessment should include the potential of the scheme to have both positive and negative effects on marine ecology and biodiversity.” (NPS EN-3 Paragraph 2.6.67)                                  | Both potential positive and negative effects of AyM on marine mammals have been assessed in section 7.16.236                                                                                                    |
|                        | “The Secretary of State should consider the effects of a proposal on marine ecology and biodiversity taking into account all relevant information made available to it.” (paragraph 2.6.68 of NPS EN-3) | The potential effects on marine mammal ecology are presented within this chapter, with the assessment of effects presented within sections 7.10, 7.11 and 7.12.                                                 |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | SECTION WHERE COMMENT<br>ADDRESSED                                                              |
|------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------|
|                        | “Mitigation may be possible in the form of careful design of the development itself and the construction techniques employed (paragraph 2.6.70 of NPS EN-3)                                                                                                                                                                                                                                                                                                                                                                                                                  | Embedded mitigation relevant for marine mammals is detailed in Section 7.9.                     |
|                        | “Ecological monitoring is likely to be appropriate during the construction and operational phases to identify the actual impact so that, where appropriate, adverse effects can then be mitigated and to enable further useful information to be published relevant to future projects.” (paragraph 2.6.71 of NPS EN-3)                                                                                                                                                                                                                                                      | The requirement for marine mammal monitoring has been assessed in sections 7.10, 7.11 and 7.12. |
|                        | <p>Where necessary, assessment of the effects on marine mammals should include details of:</p> <ul style="list-style-type: none"> <li>➤ likely feeding areas;</li> <li>➤ known birthing areas/haul out sites;</li> <li>➤ nursery grounds;</li> <li>➤ known migration or commuting routes;</li> <li>➤ duration of the potentially disturbing activity including cumulative/in-combination</li> <li>➤ effects with other plans or projects;</li> <li>➤ baseline noise levels;</li> <li>➤ predicted noise levels in relation to mortality, permanent threshold shift</li> </ul> | The effects on marine mammals have been assessed in sections 7.10, 7.11, 7.12 and 7.13.         |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                   | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                                                  |
|------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | <ul style="list-style-type: none"> <li>▶ (PTS) and temporary threshold shift (TTS);</li> <li>▶ soft-start noise levels according to proposed hammer and pile design; and</li> <li>▶ operational noise.”</li> </ul> <p>(paragraph 2.6.92 of NPS EN-3)</p>                                                                                                                         |                                                                                                                                                                                                                                                                                                     |
|                        | <p>“The applicant should discuss any proposed piling activities with the relevant body. Where assessment shows that noise from offshore piling may reach noise levels likely to lead to an offence as described in 2.6.91 above, the applicant should look at possible alternatives or appropriate mitigation before applying for a license.” (paragraph 2.6.93 of NPS EN-3)</p> | <p>The proposed piling activity is discussed in section 7.1. Appropriate embedded general mitigation measures to minimise the potential for an offence, along with those specific to construction, operation and maintenance and decommissioning, are discussed in Sections 7.10,7.11 and 7.12.</p> |
|                        | <p>“The Infrastructure Planning Commission (IPC) should be satisfied that the preferred methods of construction, in particular the construction method needed for the proposed foundations and the preferred foundation type, where known at the time of application, are designed so as to reasonably minimise significant disturbance effects on marine mammals. Unless</p>    | <p>The maximum potential impact associated with construction, operating and decommissioning at AyM are assessed in section 7.8. Mitigation measures to minimise this potential disturbance are discussed in Sections 7.10,7.11 and 7.12.</p>                                                        |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                         | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                                                     |
|------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | suitable noise mitigation measures can be imposed by requirements to any development consent the IPC may refuse the application." (paragraph 2.6.94 of NPS EN-3)                                                                                                                                                       |                                                                                                                                                                                                                                                                                                        |
|                        | "Fixed submerged structures such as foundations are likely to pose little collision risk for marine mammals and the IPC is not likely to have to refuse to grant consent for a development on the grounds that offshore wind farm foundations pose a collision risk to marine mammals." (paragraph 2.6.96 of NPS EN-3) | The potential for collision risk is assessed in sections 7.10,7.11 and 7.12.                                                                                                                                                                                                                           |
|                        | "Monitoring of the surrounding area before and during the piling procedure can be undertaken." (paragraph 2.6.97 of NPS EN-3)                                                                                                                                                                                          | Monitoring conducted prior to development is discussed in section 7.7 and in further detail in Volume 4: Annex 7.1: Marine Mammal Baseline. Monitoring to be conducted during piling procedures is described in Section 7.9 with further detail provided in Volume 4: Annex 4.7.2: Draft Outline MMMP. |
|                        | "During construction, 24-hour working practices may be employed so that the overall construction programme and the potential for impacts to marine mammal                                                                                                                                                              | AyM can confirm that 24 hour working practices will be employed for offshore construction works (Volume 2, Chapter                                                                                                                                                                                     |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                          | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                              |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | communities is reduced in time." (paragraph 2.6.98 of NPS EN-3)                                                                                                                                                                                         | 1: Offshore Project Description). The predicted project time frame is discussed in section 7.1.                                                                                                                 |
|                        | "Soft start procedures during pile driving may be implemented. This enables marine mammals in the area disturbed by the sound levels to move away from the piling before significant adverse impacts are caused." (paragraph 2.6.98 of NPS EN-3)        | Soft start procedures for monopiles and multi-leg pin-pile jackets are detailed in section 7.1.                                                                                                                 |
| Draft NPS EN-3         | "Consultation on the assessment methodologies, baseline data collection, and potential mitigation and compensation options should be undertaken at early stages with the statutory consultees as appropriate." (paragraph 2.24.6 of the Draft NPS EN-3) | Consultations with relevant statutory and non-statutory stakeholders have been conducted throughout AyM (see Table 3 for a summary of consultation with regards to marine mammals).                             |
|                        | "Any relevant data that has been collected as part of post-construction ecological monitoring from existing, operational OWFs should be referred to where appropriate." (paragraph 2.24.7 of the Draft NPS EN-3)                                        | Relevant data collected during post construction monitoring from other OWF projects as well as relevant scientific research and literature have informed the assessment of AyM in sections 7.10, 7.11 and 7.12. |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                     | SECTION WHERE COMMENT<br>ADDRESSED                                                                           |
|------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------|
|                        | "Reference must be made to relevant scientific research and literature." (paragraph 2.24.7 of the Draft NPS EN-3)                                                                                                                                                                                                                                  |                                                                                                              |
|                        | "The assessment should include the potential of the scheme to have both positive and negative effects on marine ecology and biodiversity." (paragraph 2.24.8 of the Draft NPS EN-3)                                                                                                                                                                | Both potential positive and negative effects of AyM on marine mammals have been assessed in section 7.16.236 |
|                        | "Mitigation may be possible in the form of careful design of the development itself and the construction techniques employed (paragraph 2.24.10 of the Draft NPS EN-3)                                                                                                                                                                             | Mitigation relevant for marine mammals is detailed in Section 7.9.                                           |
|                        | "Ecological monitoring will be appropriate during the pre-construction, construction and operational phases to identify the actual impacts caused by the project and compare them to what was predicted in the EIA/HRA... Monitoring should be of sufficient standard to inform future decision making." (paragraph 2.24.11 of the Draft NPS EN-3) | The requirement for marine mammal monitoring has been assessed in sections 7.10, 7.11 and 7.12.              |
|                        | Where necessary, assessment of the effects on marine mammals should include details of:                                                                                                                                                                                                                                                            | The effects on marine mammals have been assessed in sections 7.10, 7.11, 7.12 and 7.13.                      |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | SECTION WHERE COMMENT<br>ADDRESSED                                                                       |
|------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------|
|                        | <ul style="list-style-type: none"> <li>➤ likely feeding areas and impacts on prey species and prey habitat</li> <li>➤ known birthing areas / haul out sites for breeding and pupping</li> <li>➤ migration routes</li> <li>➤ protected areas (e.g. HRA sites and SSSIs)</li> <li>➤ baseline noise levels</li> <li>➤ predicted construction and soft start noise levels in relation to mortality, permanent threshold shift (PTS), temporary threshold shift (TTS) and disturbance</li> <li>➤ operational noise</li> <li>➤ duration and spatial extent of the impacting activities including cumulative/in combination effects with other plans or projects</li> <li>➤ collision risk</li> <li>➤ entanglement risk</li> <li>➤ barrier risk"</li> </ul> <p>(paragraph 2.28.3 of the Draft NPS EN-3)</p> |                                                                                                          |
|                        | <p>"The applicant should discuss any proposed noisy activities with the relevant body and must reference the JNCC underwater noise guidance in relation to</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | <p>The proposed piling activity is discussed in section 7.1. Appropriate embedded general mitigation</p> |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                    |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | noisy activities (alone and in-combination with other plans or projects) within HRA sites. Where assessment shows that noise from construction and UXO clearance may reach noise levels likely to lead to noise thresholds being exceeded (as detailed in the JNCC guidance) or an offence as described in paragraph 2.28.1 above, the applicant should look at possible alternatives or appropriate mitigation (detailed below)." (paragraph 2.28.5 of the Draft NPS EN-3)                                                                       | measures to minimise the potential for an offence, along with those specific to construction, operation and maintenance and decommissioning, are discussed in Sections 7.10,7.11 and 7.12.                                            |
|                        | "The Infrastructure Planning Commission (IPC) should be satisfied that the preferred methods of construction, in particular the construction method needed for the proposed foundations and the preferred foundation type, where known at the time of application, are designed so as to reasonably minimise significant disturbance effects on marine mammals. Unless suitable noise mitigation measures can be imposed by requirements to any development consent the IPC may refuse the application." (paragraph 2.28.9 of the Draft NPS EN-3) | The maximum potential impact associated with construction, operating and decommissioning at AyM are assessed in section 7.8. Mitigation measures to minimise this potential disturbance are discussed in Sections 7.10,7.11 and 7.12. |



| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                 | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                                                            |
|------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | <p>“Monitoring of the surrounding area before and during the piling procedure can be undertaken by various methods including marine mammal observers and passive acoustic monitoring. Active displacement of marine mammals outside potential injury zones can be undertaken using equipment such as acoustic deterrent devices.” (paragraph 2.28.6 of the Draft NPS EN-3)</p> | <p>Monitoring conducted prior to development is discussed in section 7.7 and in further detail in Volume 4: Annex 7.1: Marine Mammal Baseline. Monitoring to be conducted during piling procedures is described in Section 7.9 with further detail provided in Volume 4: Annex 4.7.2: Draft Outline MMMP.</p> |
|                        | <p>“Soft start procedures during pile driving may be implemented. This enables marine mammals in the area disturbed by the sound levels to move away from the piling before significant adverse impacts are caused.” (paragraph 2.28.7 of the Draft NPS EN-3)</p>                                                                                                              | <p>Soft start procedures for monopiles and multi-leg pin-pile jackets are detailed in section 7.1.</p>                                                                                                                                                                                                        |

### 7.2.1 Overview of Welsh Planning Policy

- 7 Planning Policy Wales sets out the land use planning policies of the Welsh Government, forming a strategic framework to guide development. The Planning Policy Wales documentation does not explicitly include a topic on marine mammals with other relevant policy and guidance identified below.

### Welsh National Marine Plan

- 8 The WNMP was published on 12 November 2019 and contains policy across a range of considerations (including nature conservation, sustainable use, seascape, and coastal communities and economic growth). The WNMP includes sector objectives for renewable energy to support decarbonisation of the Welsh economy and the use of marine renewable energy generation (including OWFs), with specific reference to marine mammals in relation to underwater noise production. Table 2 provides a summary of the key provisions of the WNMP of relevance to this assessment.

Table 2: WNMP policies of relevance to marine mammals.

| LEGISLATION/<br>POLICY        | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                       |
|-------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Welsh National<br>Marine Plan | <p>ENV_01: Resilient marine ecosystems.</p> <p>Proposals should demonstrate how potential impacts on marine ecosystems have been taken into consideration and should, in order of preference:</p> <ul style="list-style-type: none"> <li>a. avoid adverse impacts; and/or</li> <li>b. minimise impacts where they cannot be avoided; and/or</li> <li>c. mitigate impacts where they cannot be minimised.</li> </ul> <p>If significant adverse impacts cannot be avoided, minimised or mitigated, proposals must present a clear and convincing case for proceeding.</p> <p>Proposals that contribute to the protection, restoration and/or enhancement of marine ecosystems are encouraged.</p> | The potential impacts on marine mammal ecology have been assessed in sections 7.10, 7.11, 7.12 and 7.13. Consideration of the avoid, minimise and mitigate approach is given within the assessments as appropriate. Mitigation measures are detailed within Section 7.9. |
|                               | <p>ENV_02: Marine Protected Areas.</p> <p>Proposals should demonstrate how they:</p>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Designated sites within the region have been identified as appropriate, and any potential impacts to features                                                                                                                                                            |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                        | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                 |
|------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|
|                        | <ul style="list-style-type: none"> <li>avoid adverse impacts on individual Marine Protected Areas (MPAs) and the coherence of the network as a whole;</li> <li>have regard to the measures to manage MPAs; and</li> <li>avoid adverse impacts on designated sites that are not part of the MPA network.</li> </ul>                    | and the network of sites have been assessed in the RIAA.                                                                           |
|                        | <p>ENV_02: Invasive non-native species.</p> <p>Proposals should demonstrate how they avoid or minimise the risk of introducing and spreading invasive non-native species.</p> <p>Where appropriate, proposals should include biosecurity measures to reduce the risk of introducing and spreading of invasive non-native species.</p> | The introduction of non-native species is not of relevance to marine mammals and as such, no further consideration has been given. |
|                        | <p>ENV_05: Underwater noise.</p> <p>Proposals should demonstrate that they have considered man-made noise impacts on the marine environment and, in order of preference:</p> <ul style="list-style-type: none"> <li>a. avoid adverse impacts; and/or</li> <li>b. minimise impacts where they cannot be avoided;</li> </ul>            | The effects of underwater noise on marine mammals have been assessed in sections 7.10, 7.11, 7.12 and 7.13.                        |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                                                                |
|------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                        | <p>and/or</p> <p>c. mitigate impacts where they cannot be minimised.</p> <p>If significant adverse impacts cannot be avoided, minimised or mitigated, proposals must present a clear and convincing case for proceeding.</p>                                                                                                                                                                                                                                                                                     |                                                                                                                                                                                                                                                                                                                   |
|                        | <p>ENV_07: Fish species and Habitats.</p> <p>Proposals potentially affecting important feeding, breeding (including spawning &amp; nursery) and migration areas or habitats for key fish and shellfish species of commercial or ecological importance should demonstrate how they, in order of preference:</p> <p>a. avoid adverse impacts on those areas; and/or</p> <p>b. minimise adverse impacts where they cannot be avoided; and/or</p> <p>c. mitigate adverse impacts where they cannot be minimised.</p> | <p>The potential effects on fish species and their habitats have been assessed in sections 7.10.10, 7.11.5 and 7.12.5 in the context of how marine mammal prey species may be impacted. The potential effects of AyM on fish and shellfish have been fully assessed in Chapter 6: Fish and Shellfish Ecology.</p> |

| LEGISLATION/<br>POLICY | KEY PROVISIONS                                                                                                                               | SECTION WHERE COMMENT<br>ADDRESSED |
|------------------------|----------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------|
|                        | If significant adverse impacts cannot be avoided, minimised or mitigated, proposals must present a clear and convincing case for proceeding. |                                    |

## Future Wales – The National Plan

- 9 Future Wales – the National Plan 2040 is Wales' national development framework, setting the direction for development in Wales to 2040. Whilst it does not specifically relate to marine mammals, it is a development plan with a strategy for addressing key national priorities through the planning system, including sustaining and developing a vibrant economy, achieving decarbonisation and climate-resilience, developing strong ecosystems and improving the health and well-being of Wales' communities.

### 7.3 Consultation and scoping

- 10 As part of the EIA for AyM, consultation has been undertaken with various statutory and non-statutory bodies, through the agreed Evidence Plan process. A formal Scoping Opinion was sought from the Secretary of State (SoS) following submission of the Scoping Report (innogy, 2020). The Scoping Opinion (the Planning Inspectorate (PINS), 2020) was issued in July 2020 by PINS. A record of key areas of consultation undertaken during the Scoping Opinion and Evidence Plan phases is summarised within Table 3 and will be presented in full within the project consultation report, to be published with the final DCO application.

Table 3: Summary of consultation relating to marine mammals.

| DATE AND CONSULTATION PHASE/ TYPE                                          | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                                                                            | SECTION WHERE COMMENT ADDRESSED                                                                                                                           |
|----------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------|
| Email correspondence<br>27/03/2020, re AyM Marine Mammal Density Estimates | Natural Resources Wales (NRW) agreed that the aerial survey data are not sufficient to inform the impact assessment and agreed with the approach to use both the SCANS III and the Joint Cetacean Protocol (JCP) III density estimates in the quantitative impact assessment. | Both SCANS III and JCP III density estimates have been used in the impact assessment (Table 16).                                                          |
| Email correspondence<br>27/03/2020, re AyM Marine Mammal Density Estimates | NRW recommends data from the Sea Watch Foundation is sourced for bottlenose and Risso's dolphins.                                                                                                                                                                             | Sea Watch Foundation data has been purchased for the north coast of Wales area. This is included in Volume 4: Annex 7.1: Marine mammal baseline.          |
| Email correspondence<br>27/03/2020, re AyM Marine Mammal Density Estimates | NRW agreed that the latest grey seal telemetry data should be used to inform seal density estimates.                                                                                                                                                                          | Assessment uses the Carter et al. (2020) habitat preference maps for grey seal at-sea densities, which incorporates the latest telemetry data (Table 16). |



| DATE AND CONSULTATION PHASE/ TYPE | CONSULTATION AND KEY ISSUES RAISED                                                                                                              | SECTION WHERE COMMENT ADDRESSED                                                                                       |
|-----------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------|
| July 2020 Scoping Opinion         | Density estimates used need a clear justification and the approach should be agreed with relevant statutory nature conservation bodies (SNCBs). | Density estimates selected for impact assessment are outlined in Volume 4: Annex 7.1: Marine mammal baseline.         |
| July 2020 Scoping Opinion         | ES should provide TTS ranges used for the purpose of assessing disturbance.                                                                     | TTS-onset impact ranges have been presented (section 0 TTS from piling)                                               |
| July 2020 Scoping Opinion         | Physical barrier effects on marine mammals should be included.                                                                                  | Potential barrier effects are considered in section 7.11.1.                                                           |
| July 2020 Scoping Opinion         | ES should use updated abundance estimates for the Celtic and Irish Seas MU.                                                                     | ES uses updated MU abundance estimates in the impact assessment (Table 16).                                           |
| July 2020 Scoping Opinion         | ES should consider the Pen Llyn a'r Sarnau SAC for bottlenose dolphins.                                                                         | Baseline characterisation considers connectivity with the SAC. Predicted impacts to the SAC are assessed in the RIAA. |

| DATE AND CONSULTATION PHASE/ TYPE                   | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                                                         | SECTION WHERE COMMENT ADDRESSED                                                                                                               |
|-----------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------|
| July 2020 Scoping Opinion                           | ES should assess impact of disturbance on North Anglesey Marine SAC.                                                                                                                                                                                       | North-west (NW) underwater noise modelling location was selected for proximity to SAC. Predicted impacts to the SAC are assessed in the RIAA. |
| Sep 2020 Marine ecology and marine mammal ETG       | Disturbance assessment will utilise the Graham et al. (2017a) dose response curve for cetaceans. The seal assessment will use the Whyte et al. (2020) dose-response curve. Approach agreed with NRW.                                                       | Dose-response curves are used to assess disturbance from piling – described further in paragraph 27 et seq.                                   |
| Email correspondence 17-22/02/2021, re AyM ADD note | NRW agreed with the proposed approach to incorporation of ADDs into the MMMP.                                                                                                                                                                              | Described further in Volume 4, Annex 7.2: Outline Marine Mammal Mitigation Protocol.                                                          |
| Mar 2021<br>Marine ecology and marine mammal ETG    | Lack of data on bottlenose dolphin density in North Wales. In the absence of Sea Watch data, NRW agreed with the proposed approach: use the wider Cardigan Bay density estimate and assume that bottlenose dolphins are restricted to 6 km from the coast. | Described further in Volume 4: Annex 7.1: Marine mammal baseline.                                                                             |

| DATE AND CONSULTATION PHASE/ TYPE | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                       | SECTION WHERE COMMENT ADDRESSED                                                                                                                                                            |
|-----------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Oct 2021 s42 comments from NRW    | NRW do not agree with the PTS sensitivity score for grey seals and cetaceans.                                                                                            | Definition of sensitivity has been updated to take into consideration the significance of the effect (Table 10). Additional justification is provided in section 7.5.1 Sensitivity to PTS. |
| Oct 2021 s42 comments from NRW    | NRW do not support the use of EDRs.                                                                                                                                      | A range of disturbance thresholds are presented in 7.10.6 Disturbance from UXO (EDRs alongside TTS-onset as a proxy for disturbance).                                                      |
| Oct 2021 s42 comments from NRW    | NRW do not agree with the density surface for bottlenose dolphins. Coastal dolphins should be limited to the 20 m depth contour. Offshore dolphins should be considered. | The density surface has been revised as suggested. Described further in Volume 4: Annex 7.1: Marine mammal baseline.                                                                       |
| Oct 2021 s42 comments from NRW    | NRW do not agree with scoping out common dolphins.                                                                                                                       | Common dolphins are now scoped in - see Volume 4:                                                                                                                                          |

| DATE ANDCONSULTATION<br>PHASE/ TYPE | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                   |
|-------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                     |                                                                                                                                                                                                                   | Annex 7.1: Marine mammal<br>baseline.                                                                                                                                                |
| Oct 2021 s42 comments from<br>NRW   | NRW noted that the number of piling days offer no contingency for delays or practical limitations in achieving the maximum piling capacity per day. Any delays would alter the duration and frequency of impacts. | For the assessment of disturbance, it has been assumed that at a worst case, it could take up to three days to install one monopile, and two days to install a jacket foundation.    |
| Oct 2021 s42 comments from<br>NRW   | NRW commented that it was unclear if or how the accumulation of impacts from piling events over time has been considered when estimating the number of animals potentially exposed to PTS.                        | Assessment text specifies that the numbers presented are the number of animals that are expected to experience PTS-onset on each day of pile driving activities (see section 7.10.1) |
| Oct 2021 s42 comments from<br>NRW   | NRW recommended that if a dose-response methodology is being applied this should be explained in much greater detail to demonstrate                                                                               | Additional information on dose response curves and applicability to other species is                                                                                                 |

| DATE AND CONSULTATION PHASE/ TYPE | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                                                          | SECTION WHERE COMMENT ADDRESSED                                                                                                    |
|-----------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|
|                                   | the suitability of the approach to the specifics of this application.                                                                                                                                                                                       | provided in 7.4.3 Underwater noise modelling (specifically paragraph 27 et seq.).                                                  |
| Oct 2021 s42 comments from NRW    | The outline MMMP currently offers no observer coverage during weather of visibility conditions lower than 'good', within which marine mammal observers can operate. It also does not assess the amount of cover the MMMP can provide within the PTS ranges. | The use of PAM has been included in the MMMP. Described further in Volume 4, Annex 7.2: Outline Marine Mammal Mitigation Protocol. |
| Oct 2021 s42 comments from NRW    | It is unclear if or how the temporal extent of sheet piling activities for the cofferdam has been taken into account.                                                                                                                                       | As stated in Table 18 it is expected to take 81 piling days to install the cofferdam.                                              |
| Oct 2021 s42 comments from NRW    | NRW consider that the combination of piling operations at the NW and SE modelling locations may not represent the worst-case scenario for the maximum impact range of simultaneous piling.                                                                  | The Project Description no longer includes simultaneous piling (with the exception of two pins at the same location).              |

| DATE AND CONSULTATION PHASE/ TYPE | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                                                                         | SECTION WHERE COMMENT ADDRESSED                                                                                                                                             |
|-----------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Oct 2021 s42 comments from NRW    | No evidence is presented to support the numbers of seismic surveys assumed to occur in the cumulative assessment.                                                                                                                                                          | As stated in paragraph 294 "The potential number of seismic surveys that could be undertaken is unknown". Therefore, the inclusion of seismic surveys is illustrative only. |
| Oct 2021 s42 comments from NRW    | Swimming speed data should be clearly presented and evaluated.                                                                                                                                                                                                             | Additional information on swimming speed is presented in paragraph 22.                                                                                                      |
| Oct 2021 s42 comments from TWT    | For 49% of aerial sightings it was unknown whether the sighting was of a porpoise or dolphin and none of the dolphin sightings were identified to species level. This does not provide us with enough evidence as to the marine mammal abundance in the Awel y Môr region. | This is acknowledged in Volume 4: Annex 7.1: Marine mammal baseline. Other data sources have been used to supplement the baseline characterization.                         |
| Oct 2021 s42 comments from TWT    | Seasonality and the associated presence/absence of marine mammal species throughout the year will be key in determining                                                                                                                                                    | Seasonality information has been added to Volume 4:                                                                                                                         |

| DATE AND CONSULTATION PHASE/ TYPE                         | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                          | SECTION WHERE COMMENT ADDRESSED                                                                                                                      |
|-----------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                                           | both the degree of impact and the timing of any future construction and mitigation measures. Therefore, it is important that this information is placed upfront where it can be considered. | Annex 7.1: Marine mammal baseline.                                                                                                                   |
| Oct 2021 s42 comments from TWT                            | The cumulative impact assessment should include projects other than offshore wind farms.                                                                                                    | Details on the screening of projects for the cumulative impact assessment is described in section 7.13 Environmental assessment: cumulative effects. |
| Oct 2021 s42 comments from TWT                            | Baseline data on grey seal haul-outs should be obtained from Cofnod (North Wales Records Centre).                                                                                           | Data obtained and presented in Volume 4: Annex 7.1: Marine mammal baseline.                                                                          |
| Oct 2021 s42 comments from Angel Bay Seal Volunteer Group | Baseline report and impact assessment lacks reference to the Angel Bay seal haul-out.                                                                                                       | This is now included in Volume 4: Annex 7.1: Marine mammal baseline.                                                                                 |
| Oct 2021 s42 comments from Isle of Man Govt               | Isle of Man Marine Nature Reserves for marine mammals need to be considered.                                                                                                                | This is now included in Volume 4: Annex 7.1: Marine mammal baseline.                                                                                 |

| DATE AND CONSULTATION PHASE/ TYPE  | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                                                                                                                                                                                   | SECTION WHERE COMMENT ADDRESSED                                                                                                                                                                                                                                                                                                                                     |
|------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Jan 2022 NRW comments on baseline  | Justification is required for not using the higher, and potentially more precautionary Sea Watch Foundation density estimate for harbour porpoise.                                                                                                                                                                                                                                   | Further detail on the Sea Watch Foundation density estimate is provided in Volume 4: Annex 7.1: Marine mammal baseline. A density estimate of 1 porpoise/km <sup>2</sup> (averaged across the coastal and offshore areas from the SWF report) has been presented in the impact assessment for context, however the caveats associated with this estimate are large. |
| Jan 2022 JNCC comments on baseline | The Sea Watch density estimate (0.5-1.5/km <sup>2</sup> ) is a magnitude higher than that estimated by either SCANS (0.086/km <sup>2</sup> ) or the JCP (0.13/km <sup>2</sup> ) however SMRU consulting still propose to take the SCANS/JCP estimates forward to the impact assessment. Justification is needed as to why the more precautionary density is not being taken forward. |                                                                                                                                                                                                                                                                                                                                                                     |
| Jan 2022 NRW comments on baseline  | NRW welcome the inclusion of common dolphin in the baseline. We note that to fully resolve NRW's concerns regarding common dolphin, they should also be scoped into assessments.                                                                                                                                                                                                     | Common dolphins have been fully considered in the impact assessment.                                                                                                                                                                                                                                                                                                |
| Jan 2022 NRW comments on baseline  | JNCC welcome the inclusion of common dolphins to the baseline and consider sufficient information                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                                                                                                                                                                                     |



| DATE AND CONSULTATION PHASE/ TYPE             | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                                                                                                                                                                                                       | SECTION WHERE COMMENT ADDRESSED                                                                                                                                                                      |
|-----------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                               | is provided to describe the likely occurrence of this species in the development area                                                                                                                                                                                                                                                                                                                    |                                                                                                                                                                                                      |
| Jan 2022 NRW comments on cumulative PTS note  | Without a suitable alternative, use of SELcum remains the appropriate means to assess this impact, particularly given its use in the RIAA and PEIR.                                                                                                                                                                                                                                                      | The limitations of the calculations for cumulative PTS are further detailed in Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, Limitations and Uncertainties. |
| Jan 2022 JNCC comments on cumulative PTS note | While we agree that SEL cumulative calculations provide likely over-precautionary injury ranges for the reasons provided, currently there is no agreed alternative method of considering these factors when predicting injury and no alternative is provided in this document. Therefore, using both the peak SPL and cumulative metrics is still the most precautionary approach in impact assessments. | The impact assessment presents the SELcum impact ranges but the illustration provided in Volume 4, Annex 7.3 highlights the precaution in these estimates.                                           |
| Jan 2022 NRW comments on PTS sensitivity note | We are content with the revised sensitivity definitions. We still consider the appropriate PTS sensitivity score for grey seal to be 'low'. We still                                                                                                                                                                                                                                                     | The definitions of sensitivity have been revised (Table 10). All marine mammals have                                                                                                                 |


| DATE AND CONSULTATION PHASE/ TYPE              | CONSULTATION AND KEY ISSUES RAISED                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | SECTION WHERE COMMENT ADDRESSED                                                                                                                                        |
|------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                                | consider the appropriate PTS sensitivity score for bottlenose dolphin to be 'medium.'                                                                                                                                                                                                                                                                                                                                                                                                                                              | been assessed as having a Low sensitivity to PTS, except dolphin species which have been increased to Medium (Table 15).                                               |
| Jan 2022 JNCC comments on PTS sensitivity note | JNCC are content with the sensitivity assessment for harbour porpoise as low, however we agree with NRW's recommendation that the sensitivity for seals be increased from negligible to low. Given the changes to how sensitivity is defined (Table 8), we also suggest the sensitivity for bottlenose dolphins is increased to medium as their coastal behaviour limits their ability to adapt behaviour in response to anthropogenic noise and a significant effect on individual vital rates cannot be ruled out at this stage. |                                                                                                                                                                        |
| Jan 2022 NRW comments on UXO disturbance note  | A broader review should be undertaken and options either demonstrated to be unsuitable or taken forward into the assessment. other options for assessing disturbance should be considered and presented to complete the intended approach, such as the Lucke <i>et al.</i> (2009) 145 SEL                                                                                                                                                                                                                                          | The potential thresholds for the UXO disturbance assessment are now detailed in Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, |


| DATE ANDCONSULTATION<br>PHASE/ TYPE            | CONSULTATION AND KEY ISSUES RAISED                       | SECTION WHERE COMMENT<br>ADDRESSED                                                                                                                                                                                                                                                                                                                              |
|------------------------------------------------|----------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                                                | disturbance, alongside the Soloway & Dahl (2014) method. | Limitations and Uncertainties. This includes assessment of the following thresholds: EDR, TTS, Lucke et al (2009), Level B harassment; as well as information on noise propagation models (e.g. Soloway & Dahl 2014). Section 7.10.6 Disturbance from UXO assesses disturbance using a 26 km EDR (high order), a 5 km EDR (low order) and TTS-onset thresholds. |
| Jan 2022 JNCC comments on UXO disturbance note | The current EDR for UXO clearance is 26km.               |                                                                                                                                                                                                                                                                                                                                                                 |

## 7.4 Scope and methodology

### 7.4.1 Study area

- 11 The AyM marine mammal study area varies depending on the species, considering individual species ecology and behaviour. The marine mammal species likely to be present in the AyM marine mammal study area include harbour porpoise (*Phocoena phocoena*), grey seal (*Halichoerus grypus*), bottlenose dolphin (*Tursiops truncatus*), common dolphins (*Delphinus delphis*), Risso's dolphin (*Grampus griseus*), and minke whale (*Balaenoptera acutorostrata*).
- 12 The marine mammal study area has been defined at two spatial scales:
  - ▲ Regional scale study area: Provides a wider geographic context in terms of the species present and their estimated densities and abundance, at the appropriate scale for each marine mammal population (Management Unit, MU) Figure 1. The regional study area for harbour porpoise is the Celtic and Irish Sea Management Unit (MU), for grey seals it is the OSPAR region III MU, for bottlenose dolphins it is the Irish Sea MU, and for common dolphins, Risso's dolphins and minke whales it is the Celtic and Greater North Seas MU. This scale defines the appropriate reference population for each species for the assessment.
  - ▲ Awel y Môr Study Area: includes the area covered by site-specific marine mammal surveys which are currently underway for AyM. These provide fine scale spatial and temporal data for marine mammals present in the array area (Figure 2).





## 7.4.2 Baseline data sources

13 The baseline characterisation for marine mammals is described in detail in Volume 4, Annex 7.1: Marine Mammal Baseline Characterisation. The baseline has been identified from the following sources:

- ▲ AyM site-specific surveys (APEM);
- ▲ Gwynt y Môr (GyM) baseline, mitigation and post-construction surveys (CMACS Ltd 2005, 2011, 2013, Goddard et al. 2017, Goddard et al. 2018, Goulding et al. 2019);
- ▲ SCANS surveys (Burt et al. 2006, Hammond et al. 2006, Hammond et al. 2017);
- ▲ Welsh Marine Atlas (Baines and Evans 2012);
- ▲ ObSERVE surveys (Rogan et al. 2018);
- ▲ JCP data (Heinänen and Skov 2015, Paxton et al. 2016);
- ▲ Local surveys around Anglesey (Shucksmith et al. 2009, Gordon et al. 2011);
- ▲ Wylfa Newydd surveys (Jacobs 2018);
- ▲ Morlais MDZ surveys (Royal Haskoning DHV 2019);
- ▲ Bottlenose dolphin photo-ID surveys (Pesante et al. 2008, Baines and Evans 2012, Veneruso and Evans 2012, Feingold and Evans 2014, Evans et al. 2015, Duckett 2018, Lohrengel et al. 2018);
- ▲ Sea Watch Foundation surveys in the north coast of Wales (Evans et al. 2021);
- ▲ COFNOD – North Wales environmental Information Service sightings database;
- ▲ Manx Whale and Dolphin Watch (MWDW) surveys (Felce 2014, 2015, Adams 2017, Howe 2018);
- ▲ Seal haul-out and pupping counts (Strong and Morris 2010, Stringell et al. 2014, Langley et al. 2018, Morgan et al. 2018, Angel Bay Seal Volunteer Group 2021, SCOS 2021);
- ▲ Seal telemetry (data provided by SMRU); and
- ▲ Seal at-sea densities (Carter et al. 2020).



### 7.4.3 Underwater noise modelling

- 14 The noise levels likely to occur as a result of the construction of AyM were predicted by Subacoustech Environmental Ltd using their INSPIRE (Impulse Noise Sound Propagation and Impact Range Estimator) model. A detailed description of the modelling approach is presented in the Volume 4, Annex 6.2: Subsea Noise Technical Report.

### Piling parameters - WTGs

- 15 Two modelling locations were selected: North-west (NW) and South-east (SE) which represent opposite corners of the array area. These modelling locations were selected as the represented locations closest to important marine mammal areas, including the North Anglesey Marine SAC for porpoise and the Dee Estuary for grey seals. Table 4 and Table 5 present the worst-case piling parameters modelled for monopiles and multi-leg pin-piled jackets respectively.
- 16 For the calculation of cumulative PTS and TTS-onset from monopiles, the assumption has been made that two monopiles can be installed in a 24-hour period. Given that the capacity of AyM is for up to 50 turbines (50x monopiles), one met mast (1x monopile) and two OSPs (16x monopiles), this results in a total of 67 monopiles. For the assessment of PTS and TTS-onset the worst case is to assume two monopiles are installed in one day; this results in 34 piling days. For the assessment of disturbance additional contingency has been assumed such that it could take up to three days of pile driving to install a monopile, and therefore the worst-case total number of piling days is 201.
- 17 For the calculation of cumulative PTS and TTS-onset from multi-leg pin-piled jackets, the assumption has been made that four pin-piles can be installed at one location in a 24-hour period. Given that the capacity of AyM is for up to 50 turbines (200x pin piles) and other piled offshore infrastructure (24x pin piles), this results in a total of 224 pin piles. For the assessment of PTS and TTS-onset, the worst case is to assume that four pin piles are installed in one day; this results in 56 piling days. For the assessment of disturbance additional contingency has been assumed such that it could take up to two days of pile driving to a jacket, and therefore the worst-case total number of piling days is 112.



- 18 In the case of monopiles, piling will only occur at one location at a time – there is no possibility of simultaneous or concurrent piling. In the case of pin-piled multi-leg jacket foundations, pin-piles may be installed concurrently, but only on adjacent legs of the same jacket foundation – there is no possibility of simultaneous or concurrent piling at two separate foundation locations.

Table 4: Piling parameters for monopiles.

| MONOPILE                  | SOFT-START | RAMP-UP |       |       |       | MAX   |
|---------------------------|------------|---------|-------|-------|-------|-------|
| Hammer Energy (kJ)        | 750        | 1,000   | 2,000 | 3,000 | 4,000 | 5,000 |
| # Strikes                 | 100        | 100     | 340   | 680   | 1020  | 6528  |
| Duration (min)            | 10         | 10      | 10    | 20    | 30    | 195   |
| Strike rate (strikes/min) | 10         | 10      | 34    | 34    | 34    | 34    |

Table 5: Piling parameters for multi-leg pin-piled jackets.

| MULTI-LEG                 | SOFT-START | RAMP-UP |       |       |       | MAX   |
|---------------------------|------------|---------|-------|-------|-------|-------|
| Hammer Energy (kJ)        | 450        | 600     | 1,200 | 1,800 | 2,400 | 3,000 |
| # Strikes                 | 100        | 100     | 340   | 680   | 1020  | 5100  |
| Duration (min)            | 10         | 10      | 10    | 20    | 30    | 150   |
| Strike rate (strikes/min) | 10         | 10      | 34    | 34    | 34    | 34    |

## Piling parameters – OSPs and Met mast

- 19 Other structures within the array area that may require impact pile driving for installation are the foundations for the OSPs and the met mast. The met mast is expected to be installed using a monopile. The OSPs are expected to be installed using either monopiles or pin-piles. The piling parameters are expected to be the same as those described above for WTG foundation installation (Table 4 and Table 5). For the met mast 1 piling day is required. For the OPS, a maximum of 8 piling days is required (if installing 16 smaller monopiles and assuming 2 piles per day).

## Piling parameters – Cofferdam sheet piles

- 20 The Project Description includes the potential for impact pile driving to install sheet piles for the cofferdam as part of the landfall. The sheet piles are expected to be a maximum of 750 mm in width and a total of 650 sheet piles will be installed. Table 6 presents the worst-case piling parameters modelled for sheet piling. It is assumed that eight sheet piles can be installed in one day, resulting in a total of 81 days piling for the cofferdam.

Table 6: Piling parameters for cofferdam sheet piling.

| SHEET PILES               | SOFT-START | RAMP-UP         | MAX |
|---------------------------|------------|-----------------|-----|
| Hammer Energy (kJ)        | 60         | Gradual ramp up | 300 |
| # Strikes                 | 1,550      | 175             | 875 |
| Duration (min)            | 30         | 5               | 25  |
| Strike rate (strikes/min) | 35         |                 |     |

## PTS assessment

- 21 For marine mammals, the main impact from AyM will be as a result of underwater noise produced during construction. Therefore, a detailed assessment has been provided for this impact pathway. Exposure to loud sounds can lead to a reduction in hearing sensitivity (a shift in hearing threshold), which is generally restricted to particular frequencies. This threshold shift results from physical injury to the auditory system and may be temporary (TTS) or permanent (PTS). The PTS- and TTS-onset thresholds used in this assessment are those presented in Southall et al. (2019) (Table 7). The method used to calculate PTS-onset impact ranges for both 'instantaneous' PTS ( $SPL_{peak}$ ), and 'cumulative' PTS ( $SEL_{cum}$ , over 24 hours) are detailed in Volume 4, Annex 6.2: Subsea Noise Technical Report.

Table 7: PTS-onset thresholds for impulsive noise (from Southall et al 2019).

| HEARING GROUP                      | SPECIES                              | CUMULATIVE PTS ( $SEL_{cum}$ DB RE 1 $\mu PA^2S$ WEIGHTED) | INSTANTANEOUS PTS ( $SPL_{peak}$ DB RE 1 $\mu PA$ UNWEIGHTED) |
|------------------------------------|--------------------------------------|------------------------------------------------------------|---------------------------------------------------------------|
| Very High Frequency (VHF) Cetacean | Harbour porpoise                     | 155                                                        | 202                                                           |
| High Frequency (HF) Cetacean       | Bottlenose, Common & Risso's dolphin | 185                                                        | 230                                                           |
| Low Frequency (LF) Cetacean        | Minke whale                          | 183                                                        | 219                                                           |
| Phocid                             | Grey seal                            | 185                                                        | 218                                                           |

## Swimming speed

- 22 In calculating the received noise level that animals are likely to receive during the whole piling sequence, all animals were assumed to start fleeing at a swim speed of 1.5 m/s once the piling has started (based on reported sustained swimming speeds for harbour porpoises) (Otani et al. 2000), except for minke whales which are assumed to flee at a speed of 3.25 m/s (Blix and Folkow 1995). The calculated PTS and TTS-onset impact ranges therefore represent the minimum starting distances from the piling location for animals to escape and prevent them from receiving a dose higher than the threshold.
- 23 Other marine mammal fleeing swimming speeds have previously been recommended by Scottish Natural Heritage (2016). They recommend that 1.4 m/s is used for harbour porpoise, however this is based on an average descent and ascent speed from tagged porpoise (Westgate et al. 1995), not a fleeing speed. Kastelein et al. (2018) found that swimming speeds of ~7 km/h (1.94 m/s) are sustainable for harbour porpoise (throughout a 30 min test period), thus, the modelling is conservative as it used fleeing speeds lower than this. Scottish Natural Heritage (2016) also recommend a fleeing speed of 2.1 m/s for minke whales based on Williams (2009), however this reference states that the routine speeds for mysticete whales is 2.1 to 2.6 m/s and is thus not representative of fleeing speeds. Scottish Natural Heritage (2016) recommend a swimming speed of 1.8 m/s for grey seals, based on Thompson (2015) which estimated that typical swimming speeds were in the range of 1.8-2.0 m/s. This typical swimming speed is faster than the 1.5 m/s used in the modelling and thus the modelled fleeing speed for grey seals is highly conservative.
- 24 The swimming speeds assumed in this impact assessment are standard swimming speeds that have been assumed in several other recent offshore wind farm impact assessments (including: Hornsea Three, Hornsea Four, Erebus, Rampion 2, Norfolk Boreas, East Anglia Two etc.).

## TTS Assessment

- 25 It is recognised that TTS is a temporary impairment of an animal's hearing ability with potential consequences for the animal's ability to escape predation, forage and/or communicate, supporting the statement of Kastelein et al. (2012c) that *"the magnitude of the consequence is likely to be related to the duration and magnitude of the TTS"*. An assessment of the impact based on the TTS thresholds as currently given in Southall et al. (2019) (or the former NMFS (2016) guidelines and Southall et al. (2007) guidance) would lead to a substantial overestimate of the potential impact of TTS. Furthermore, the prediction of TTS impact ranges, based on the sound exposure level (SEL) thresholds, are subject to the same inherent uncertainties as those for PTS, and in fact the uncertainties may be considered to have a proportionately larger effect on the prediction of TTS. These concepts are explained in detail in Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, Limitations and Uncertainties.
- 26 The ranges that indicate TTS-onset were modelled and are presented in this impact assessment (Table 8). However, as TTS-onset is defined primarily as a means of predicting PTS-onset, there is currently no threshold for TTS-onset that would indicate a biologically significant amount of TTS; therefore it was not possible to carry out a quantitative assessment of the magnitude or significance of the impact of TTS on marine mammals. This approach has been agreed with Natural England, the MMO and CEFAS and, as such, recent projects have not presented an assessment of magnitude, sensitivity or resulting significance for TTS-onset (for example, Hornsea Three EIA, Hornsea Four PEIR, Rampion 2 PEIR). In addition to this, the Scottish SNCBs do not require the assessment of TTS-onset in marine mammal EIAs.

**Table 8: TTS-onset thresholds for impulsive noise (from Southall et al 2019).**

| HEARING GROUP | SPECIES          | CUMULATIVE TTS (SEL <sub>CUM</sub> DB RE 1 $\mu$ PA <sup>2</sup> S WEIGHTED) | INSTANTANEOUS TTS (SPL <sub>PEAK</sub> DB RE 1 $\mu$ PA UNWEIGHTED) |
|---------------|------------------|------------------------------------------------------------------------------|---------------------------------------------------------------------|
| VHF Cetacean  | Harbour porpoise | 140                                                                          | 196                                                                 |



| HEARING GROUP  | SPECIES                                    | CUMULATIVE TTS<br>(SEL <sub>CUM</sub> DB RE 1<br>μPA <sup>2</sup> S WEIGHTED) | INSTANTANEOUS TTS<br>(SPL <sub>PEAK</sub> DB RE 1 μPA<br>UNWEIGHTED) |
|----------------|--------------------------------------------|-------------------------------------------------------------------------------|----------------------------------------------------------------------|
| HF<br>Cetacean | Bottlenose,<br>common &<br>Risso's dolphin | 170                                                                           | 224                                                                  |
| LF<br>Cetacean | Minke whale                                | 168                                                                           | 213                                                                  |
| Phocid         | Grey seal                                  | 170                                                                           | 212                                                                  |

## Disturbance assessment – piling

- 27 The assessment of disturbance from pile driven foundations was based on the current best practice methodology, making use of the best available scientific evidence. This incorporates the application of a species-specific dose-response approach rather than a fixed behavioural threshold approach. Noise contours at 5 dB intervals were generated by noise modelling and were overlain on species density surfaces to predict the number of animals potentially disturbed. This allowed for the quantification of the number of animals that will potentially respond.
- 28 Compared with the EDR and fixed noise threshold approaches, the application of a dose-response curve allows for more realistic assumptions about animal response varying with dose, which is supported by a growing number of studies. A dose-response curve is used to quantify the probability of a response from an animal to a dose of a certain stimulus or stressor (Dunlop et al. 2017) and is based on the assumption that not all animals in an impact zone will respond. The dose can either be determined using the distance from the sound source or the received weighted or unweighted sound level at the receiver (Sinclair et al. 2021).

- 29 Using a species-specific dose-response approach rather than a fixed behavioural threshold to assess disturbance is currently considered to be the best practice methodology and the latest guidance provided in Southall et al. (2019) is that *“Apparent patterns in response as a function of received noise level (sound pressure level) highlighted a number of potential errors in using all-or-nothing “thresholds” to predict whether animals will respond. Tyack and Thomas (2019) subsequently and substantially expanded upon these observations. The clearly evident variability in response is likely attributable to a host of contextual factors, which emphasizes the importance of estimating not only a dose-response function but also characterizing response variability at any dosage”*.
- 30 To estimate the number of porpoise predicted to experience behavioural disturbance as a result of pile driving, this impact assessment uses the porpoise dose-response curve presented in Graham et al. (2017a) (Figure 3).
- 31 The Graham et al. (2017a) dose-response curve was developed using data on harbour porpoise collected during the first six weeks of piling during Phase 1 of the Beatrice Offshore Wind Farm monitoring program. Changes in porpoise occurrence (detection positive hours per day) were estimated using 47 CPODs<sup>i</sup> placed around the wind farm site during piling and compared with baseline data from 12 sites outside of the wind farm area prior to the commencement of operations, to characterise this variation in occurrence. Porpoise were considered to have exhibited a behavioural response to piling when the proportional decrease in occurrence was greater than 0.5. The probability that porpoise occurrence did or did not show a response to piling was modelled along with the received single-pulse sound exposure levels piling source levels based on the received noise levels (Graham et al. 2017a).

---

<sup>i</sup> CPODs monitor the presence and activity of toothed cetaceans by the detection within the CPOD app of the trains of echo-location clicks that they make. See <https://www.chelonia.co.uk/index.html>




Figure 3: Relationship between the proportion of porpoise responding and the received single strike SEL ( $SEL_{ss}$ ) (Graham et al. 2017a).

32 Since the initial development of the dose-response curve in 2017, additional data from the remaining pile driving events at Beatrice Offshore Windfarm have been processed, and are presented in Graham et al. (2019). The passive acoustic monitoring showed a 50% probability of porpoise response (a significant reduction in detection relative to baseline) within 7.4 km at the first location piled, with decreasing response levels over the construction period to a 50% probability of response within 1.3 km by the final piling location (Figure 4)(Graham et al., 2019). Therefore, using the dose-response curve derived from the initial piling events for all piling events in the impact assessment is precautionary, as evidence shows that porpoise response is likely to diminish over the construction period.






Figure 4 The probability of a harbour porpoise response (24 h) in relation to the partial contribution of (a) distance from piling and (b) audiogram-weighted received single-pulse SEL for the first location piled (solid navy line) and the final location piled (dashed blue line). Obtained from Graham et al. (2019).

Predicted assuming the number of AIS vessel locations within 1 km  $\geq 0$ ; confidence intervals (shaded areas) estimated for uncertainty in fixed effects only. Harbour porpoise occurrence was considered to have responded to piling when the proportional decrease in occurrence (DPH) exceeded a threshold of 0.5. Points show actual response data for the first location piled (filled navy circles) and the final location piled (open blue circles).

- 33 In the absence of species-specific data on bottlenose dolphins, common dolphins, Risso's dolphins or minke whales, this dose-response curve has been adopted for all cetaceans, however it is considered that the application of the porpoise dose-response curve to other cetacean species is highly over precautionary. Porpoise are considered to be particularly responsive to anthropogenic disturbance, with playback experiments showing avoidance reactions to very low levels of sound (Tyack 2009) and multiple studies showing that porpoise respond (avoidance and reduced vocalisation) to a variety of anthropogenic noise sources to distances of multiple kilometres (e.g., Brandt et al. 2013, Thompson et al. 2013, Tougaard et al. 2013, Brandt et al. 2018, Sarnocinska et al. 2019, Thompson et al. 2020, Benhemma-Le Gall et al. 2021).

- 34 Various studies have shown that other cetacean species show comparatively less of a disturbance response from underwater noise compared with harbour porpoise. For example, through an analysis of 16 years of marine mammal observer data from seismic survey vessels, Stone et al. (2017) found a significant reduction in porpoise detection rates when large seismic airgun arrays were actively firing, but not for bottlenose dolphins. While the strength and significance of responses varied between porpoise and other dolphin species for different measures of effect, the study emphasised the sensitivity of the harbour porpoise (Stone et al. 2017). In the Moray Firth, bottlenose dolphins have been shown to remain in the impacted area during both seismic activities and pile installation activities (Fernandez-Betelu et al. 2021) which highlights a lack of complete displacement response. Likewise, other high-frequency cetacean species, such as striped and common dolphins, have been shown to display less of a response to underwater noise signals and construction-related activities compared with harbour porpoise (e.g. Kastelein et al. 2006, Culloch et al. 2016).
- 35 There is no disturbance threshold (effective disturbance range or dose-response curve) for any other cetacean species included in this assessment. Therefore, in the complete absence of an alternative, the assessment for all cetacean species has used the porpoise dose-response curve. This is considered highly precautionary and as such the number of animals predicted to experience behavioural disturbance is considered to be an over-estimate and should be interpreted with a large degree of caution.
- 36 For grey seals, the dose-response curve adopted was based on the data presented in Whyte et al. (2020) (Figure 5). The Whyte et al. (2020) study updates the initial dose-response information presented in Russell et al. (2016b) and Russell and Hastie (2017), where the percentage change in harbour seal density was predicted at the Lincs offshore windfarm. The original study used telemetry data from 25 harbour seals tagged in the Wash between 2003 and 2006, in addition to a further 24 harbour seals tagged in 2012, to estimate levels of seal usage in the area in order to assess how seal usage changed in relation to the pile driving activities at the Lincs Offshore Wind farm in 2011-2012.

- 37 In the Whyte et al. (2020) dose-response curve it has been assumed that all seals are displaced at sound exposure levels above 180 dB re 1  $\mu\text{Pa}^2\text{s}$ . This is a conservative assumption since there were no data presented in the study for harbour seal responses at this level. It is also important to note that the percentage decrease in response in the categories  $170 \leq 175$  and  $175 \leq 180$  dB re 1  $\mu\text{Pa}^2\text{s}$  is slightly anomalous (higher response at a lower sound exposure level) due to the small number of spatial cells included in the analysis for these categories ( $n=2$  and  $3$  respectively). Given the large confidence intervals on the data, this assessment presents the mean number of seals predicted to be disturbed alongside the 95% Confidence intervals, for context.
- 38 There are no corresponding data for grey seals and, as such, the harbour seal curve is applied to the grey seal disturbance assessment. This is considered to be an appropriate proxy for grey seals, since both species are categorised within the same functional hearing group. However, it is likely that this over estimates the grey seal response, since grey seals are considered to be less sensitive to behavioural disturbance than harbour seals and could tolerate more days of disturbance before there is likely to be an effect on vital rates (Booth et al. 2019). Recent studies of tagged grey seals have shown that there is vast individual variation in responses to pile driving, with some animals not showing any evidence of a behavioural response (Aarts et al. 2018). Likewise, if the impacted area is considered to be a high quality foraging patch, it is likely that some grey seals may show no behavioural response at all, given their motivation to remain in the area for foraging (Hastie et al. 2021). Therefore, the adoption of the harbour seal dose-response curve for grey seals is considered to be precautionary as it will likely over-estimate the potential for impact on grey seals.




Figure 5: Predicted decrease in seal density as a function of estimated sound exposure level, error bars show 95% CI (from Whyte et al 2020).

## Disturbance assessment - UXO

- 39 While there are empirically-derived dose-response relationships for pile driving; these are not directly applicable to the assessment of UXO detonation due to the very different nature of the sound emission. While both sound sources (piling and explosives) are categorised as “impulsive” sound sources, they differ drastically in the number of pulses and the overall duration of the noise emission, both of which will ultimately drive the behavioural response. While one UXO-detonation is anticipated to result in a one-off startle-response or aversive behaviour, the series of pulses emitted during pile driving will more or less continuously drive animals out of the impacted area, giving rise to a measurable and quantifiable dose-response relationship. For UXO clearance, there are no dose-response functions available that describe the magnitude and transient nature of the behavioural impact of UXO detonation on marine mammals.
- 40 Since there is no dose-response function available that appropriately reflects the behavioural disturbance from UXO detonation, other behavioural disturbance thresholds have been considered instead. These alternatives are summarised in the sections below.



## EDR - 26 km for high order UXO clearance

41 There is guidance available on the EDR that should be applied to assess the significance of noise disturbance against Conservation Objectives of harbour porpoise SACs in England, Wales & Northern Ireland (JNCC et al. 2020). This guidance advises that an effective deterrence range of 26 km around the source location is used to determine the impact area from high order UXO detonation with respect to disturbance of harbour porpoise in SACs.

42 However, the guidance itself acknowledges that this EDR is based on the EDR recommended for pile driving of monopiles (without noise abatement measures), since there is no equivalent data for explosives.

*“The 26 km EDR is also to be used for the high order detonation of unexploded ordnance (UXOs) despite there being no empirical evidence of harbour porpoise avoidance.” (JNCC et al. 2020)*

43 The guidance also acknowledges that the disturbance resulting from a single explosive detonation would likely not cause the more wide-spread prolonged displacement that has been observed in response to pile driving activities:

*“... a one-off explosion would probably only elicit a startle response and would not cause widespread and prolonged displacement...” (JNCC et al. 2020).*

44 While NRW have expressed concerns regarding the use of the EDR approach to assess disturbance, they do remain the only published threshold currently advised by a regulator in UK waters to assess behavioral disturbance from high-order UXO detonations. While the Applicant acknowledges that NRW do not agree with the 26 km EDR for UXO detonation, the Applicant will present the 26 km EDR for comparison to the alternative fixed noise threshold described below.

## EDR - 5 km for low order UXO clearance

- 45 There is no guidance available on which thresholds should be used to assess disturbance from low-order UXO clearance. Current risk assessments conducted to support UXO Marine Licence Applications that are including deflagration as the preferred method, are assuming an EDR of 5 km (e.g. Sofia offshore wind farm<sup>ii</sup>). As a consequence, due to the absence of formal guidance, this approach has been adopted here for the assessment of disturbance from low-order detonation of UXOs at the Project.

## Fixed noise threshold – TTS-onset

- 46 Some recent assessments of UXO clearance activities have used the TTS-onset threshold to indicate the level at which a 'fleeing' response may be expected to occur in marine mammals (e.g. Seagreen and Neart na Goithe). This is a result of discussion in Southall et al. (2007) which states that in the absence of empirical data on responses, the use of the TTS-onset threshold may be appropriate for single pulses (like UXO detonation):

*"Even strong behavioral responses to single pulses, other than those that may secondarily result in injury or death (e.g., stampeding), are expected to dissipate rapidly enough as to have limited long-term consequence. Consequently, upon exposure to a single pulse, the onset of significant behavioral disturbance is proposed to occur at the lowest level of noise exposure that has a measurable transient effect on hearing (i.e., TTS-onset). We recognize that this is not a behavioral effect per se, but we use this auditory effect as a de facto behavioral threshold until better measures are identified. Lesser exposures to a single pulse are not expected to cause significant disturbance, whereas any compromise, even temporarily, to hearing functions has the potential to affect vital rates through altered behavior." (Southall et al., 2007)."*

*"Due to the transient nature of a single pulse, the most severe behavioral reactions will usually be temporary responses, such as startle, rather than prolonged effects, such as modified habitat utilization. A transient behavioral response to a single pulse is unlikely to result in demonstrable*

---

<sup>ii</sup> Sofia Offshore Wind Farm UXO Clearance Marine License Application (GoBe 2021)MLA/2020/00489

*effects on individual growth, survival, or reproduction. Consequently, for the unique condition of a single pulse, an auditory effect is used as a de facto disturbance criterion. It is assumed that significant behavioral disturbance might occur if noise exposure is sufficient to have a measurable transient effect on hearing (i.e., TTS-onset). Although TTS is not a behavioral effect per se, this approach is used because any compromise, even temporarily, to hearing functions has the potential to affect vital rates by interfering with essential communication and/or detection capabilities. This approach is expected to be precautionary because TTS at onset levels is unlikely to last a full diel cycle or to have serious biological consequences during the time TTS persists." (Southall et al., 2007).*

- 47 Therefore, an estimation of the extent of behavioural disturbance can be based on the sound levels at which the onset of TTS is predicted to occur from impulsive sounds. Marine Scotland and NatureScot currently recommend that TTS-onset as a proxy for disturbance from UXO detonation is the most appropriate threshold to use given the lack of empirical data. TTS-onset thresholds are taken as those proposed for different functional hearing groups by Southall et al. (2019).

## Summary

- 48 In the absence of agreed thresholds to assess the potential for behaviour disturbance in marine mammals from UXO detonations, the AyM impact assessment presents results for each of the following behavioural disturbance thresholds:
- ▲ 26 km EDR for high-order detonations;
  - ▲ 5 km EDR for low-order detonations; and
  - ▲ TTS-onset thresholds for high-order detonations.
- 49 While the Applicant acknowledges that there is no empirical data to validate these thresholds as appropriate for behavioural disturbance from UXO detonations, these thresholds do cover our understanding of the range of potential behavioural responses from impulsive sound sources, and as such, provide the best indication as to the potential level of impact.

- 50 It is important for the impact assessment to acknowledge that our understanding of the effect of disturbance from UXO detonation is very limited, and as such the assessment can only provide an indication of the number of animals potentially at risk of disturbance given the limited evidence available.

## Disturbance assessment – other construction activities

- 51 There is currently no guidance on the thresholds to be used to assess disturbance of marine mammals from drilling, dredging or vessel activity. Therefore, this impact assessment provides a qualitative assessment for these impacts. The assessment is based on the limited evidence that is available in the existing literature for that impact pathway and species combination, where available.

## 7.5 Assessment criteria and assignment of significance

- 52 Determining the significance of effects is a two-stage process that involves defining the sensitivity of the receptors and the magnitude of the impacts. This section describes the criteria applied in this chapter to assign values to the sensitivity of receptors and the magnitude of potential impacts (see Volume 1, Chapter 3: Environmental Impact Assessment Methodology).
- 53 Information about the project and the project activities for all stages of the project life cycle (construction, O&M and decommissioning) have been combined with information about the environmental baseline to identify the potential interactions between the project and the environment. These potential interactions are known as potential impacts, the potential impacts are then assessed to give a level of significance of effect upon the receiving environment/ receptors.
- 54 The outcome of the assessment is to determine the significance of these effects against predetermined criteria.
- 55 The magnitude of potential impacts is defined by a series of factors including the spatial extent of any interaction, the likelihood, duration, frequency and reversibility of a potential impact. The definitions of the levels of magnitude used in the assessment as shown in Table 9.



- 56 The sensitivities of marine mammal receptors are defined by both their potential vulnerability to an impact from the proposed development, their recoverability, and the value or importance of the receptor. The definitions of terms relating to the sensitivity of marine mammal ecology chapters are detailed in Table 10.

**Table 9: Impact magnitude definitions.**

| MAGNITUDE | DEFINITION                                                                                                                                                                                                                                                                                                                                                                                                                          |
|-----------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| High      | The impact would affect the behaviour and distribution of sufficient numbers of individuals, with sufficient severity, to affect the favourable conservation status and/or the long-term viability of the population at a generational scale adverse.                                                                                                                                                                               |
|           | Long-term, large-scale increase in the population trajectory at a generational scale (beneficial).                                                                                                                                                                                                                                                                                                                                  |
| Medium    | Temporary changes in behaviour and/or distribution of individuals at a scale that would result in potential reductions to lifetime reproductive success to some individuals although not enough to affect the population trajectory over a generational scale. Permanent effects on individuals that may influence individual survival but not at a level that would alter population trajectory over a generational scale adverse. |
|           | Benefit to the habitat influencing foraging efficiency resulting in increased reproductive potential and increased population health and size (beneficial).                                                                                                                                                                                                                                                                         |
| Low       | Short-term and/or intermittent and temporary behavioural effects in a small proportion of the population. Reproductive rates of individuals may be impacted in the short term (over a limited number of breeding cycles). Survival and reproductive rates very unlikely to be impacted to the extent that the population trajectory would be altered adverse.                                                                       |

| MAGNITUDE  | DEFINITION                                                                                                                                                                                                                                                                    |
|------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|            | Short term (over a limited number of breeding cycles) benefit to the habitat influencing foraging efficiency resulting in increased reproductive potential (beneficial).                                                                                                      |
| Negligible | Very short term, recoverable effect on the behaviour and/or distribution in a very small proportion of the population. No potential for the any changes in the individual reproductive success or survival therefore no changes to the population size or trajectory adverse. |
|            | Very minor benefit to the habitat influencing foraging efficiency of a limited number of individuals (beneficial).                                                                                                                                                            |

Table 10: Sensitivity/importance of the environment.

| RECEPTOR SENSITIVITY/ IMPORTANCE | DESCRIPTION/ REASON                                                                                                                                                                                                                                                                                                                                                               |
|----------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| High                             | <p>No ability to adapt behaviour so that individual vital rates (survival and reproduction) are highly likely to be significantly affected.</p> <p>No tolerance – effect will cause a significant change in individual vital rates (survival and reproduction).</p> <p>No ability for the animal to recover from any impact on vital rates (reproduction and survival rates).</p> |
| Medium                           | <p>Limited ability to adapt behaviour so that individual vital rates (survival and reproduction) may be significantly affected.</p> <p>Limited tolerance – effect may cause a significant change in individual vital rates (survival and reproduction).</p> <p>Limited ability for the animal to recover from any impact on vital rates (reproduction and survival rates).</p>    |

| RECEPTOR SENSITIVITY/ IMPORTANCE | DESCRIPTION/ REASON                                                                                                                                                                                                                                                                                                                                           |
|----------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Low                              | <p>Ability to adapt behaviour so that individual vital rates (survival and reproduction) may be affected, but not at a significant level.</p> <p>Some tolerance – no significant change in individual vital rates (survival and reproduction).</p> <p>Ability for the animal to recover from any impact on vital rates (reproduction and survival rates).</p> |
| Negligible                       | <p>Receptor is able to adapt behaviour so that individual vital rates (survival and reproduction) are not affected.</p> <p>Receptor is able to tolerate the effect without any impact on individual vital rates (survival and reproduction).</p> <p>Receptor is able to return to previous behavioural states/activities once the impact has ceased.</p>      |

- 57 The matrix used for the assessment of the significance of potential effects is described in Table 11. The magnitude of the impact is correlated against the sensitivity of the receptor to provide a level of significance.
- 58 For the purpose of this assessment any effect that is moderate or major is considered to be significant in EIA terms. Any effect that is minor or below is not significant with respect to the EIA Regulations.

Table 11: Matrix to determine effect significance.

|                         |            | SENSITIVITY |          |            |            |
|-------------------------|------------|-------------|----------|------------|------------|
|                         |            | HIGH        | MEDIUM   | LOW        | NEGLIGIBLE |
| ADVERSE<br>MAGNITUDE    | HIGH       | Major       | Major    | Moderate   | Minor      |
|                         | MEDIUM     | Major       | Moderate | Minor      | Negligible |
|                         | LOW        | Moderate    | Minor    | Minor      | Negligible |
|                         | NEGLIGIBLE | Minor       | Minor    | Negligible | Negligible |
| BENEFICIAL<br>MAGNITUDE | NEGLIGIBLE | Minor       | Minor    | Negligible | Negligible |
|                         | LOW        | Moderate    | Minor    | Minor      | Negligible |
|                         | MEDIUM     | Major       | Moderate | Minor      | Negligible |
|                         | HIGH       | Major       | Major    | Moderate   | Minor      |

Note: Effects of 'moderate' significance or greater are defined as significant with regards to the EIA Regulations.

### 7.5.1 Sensitivity to PTS

#### Expert elicitation on PTS sensitivity

- 59 The ecological consequences of PTS for marine mammals are uncertain. At a Department for Business, Energy & Industrial Strategy (BEIS) funded expert elicitation workshop held at the University of St Andrews (March 2018), experts in marine mammal hearing discussed the nature, extent and potential consequence of PTS to UK marine mammal species (Booth and Heinis 2018). This workshop outlined and collated the best and most recent empirical data available on the effects of PTS on marine mammals. A number of general points came out in discussions as part of the elicitation. These included that PTS did not mean animals were deaf, that the limitations of the ambient noise environment should be considered and that the magnitude and frequency band in which PTS occurs are critical to assessing the effect on vital rates.
- 60 Southall et al. (2007) defined the onset of TTS as “*being a temporary elevation of a hearing threshold by 6 dB*” (in which the reference pressure for the dB is 1µPa). Although 6 dB of TTS is a somewhat arbitrary definition of onset, it has been adopted largely because 6 dB is a measurable quantity that is typically outside the variability of repeated thresholds measurements. The onset of PTS was defined as a non-recoverable elevation of the hearing threshold of 6 dB, for similar reasons. Based upon TTS growth rates obtained from the scientific literature, it has been assumed that the onset of PTS occurs after TTS has grown to 40 dB. The growth rate of TTS is dependent on the frequency of exposure, but is nevertheless assumed to occur as a function of an exposure that results in 40 dB of TTS, i.e. 40 dB of TTS is assumed to equate to 6 dB of PTS.

- 61 For piling noise, most energy is between ~30 - 500 Hz, with a peak usually between 100 – 300 Hz and energy extending above 2 kHz (Kastelein et al. 2015, Kastelein et al. 2016). Studies have shown that exposure to impulsive pile driving noise induces TTS in a relatively narrow frequency band in harbour porpoise and harbour seals (reviewed in Finneran 2015), with statistically significant TTS occurring at 4 and 8 kHz (Kastelein et al. 2016) and centred at 4 kHz (Kastelein et al. 2012a, Kastelein et al. 2012b, Kastelein et al. 2013, Kastelein et al. 2017). Therefore, during the expert elicitation, the experts agreed that any threshold shifts as a result of pile driving would manifest themselves in the 2 - 10 kHz range (Kastelein et al. 2017) and that a PTS 'notch' of 6 – 18 dB in a narrow frequency band in the 2 - 10 kHz region is unlikely to significantly affect the fitness of individuals (ability to survive and reproduce). The expert elicitation concluded that:

*... the effects of a 6 dB PTS in the 2-10 kHz band was unlikely to have a large effect on survival or fertility of the species of interest.*

*... for all species experts indicated that the most likely predicted effect on survival or fertility as a result of 6 dB PTS was likely to be very small (i.e. <5 % reduction in survival or fertility).*

*... the defined PTS was likely to have a slightly larger effect on calves/pups and juveniles than on mature females survival or fertility.*

- 62 For harbour porpoise, the predicted decline in vital rates from the impact of a 6 dB PTS in the 2-10 kHz band for different percentiles of the elicited probability distribution are provided in Table 12. The data provided in Table 12 should be interpreted as:

- ▲ Experts estimated that the median decline in an individual mature female harbour porpoise's survival was 0.01% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).
- ▲ Experts estimated that the median decline in an individual mature female harbour porpoise's fertility was 0.09% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).
- ▲ Experts estimated that the median decline in an individual harbour porpoise juvenile or dependent calf survival was 0.18% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).

Table 12: Predicted decline in harbour porpoise vital rates for different percentiles of the elicited probability distribution.

|                        | PERCENTILES OF THE ELICITED PROBABILITY DISTRIBUTION |     |      |      |      |      |      |     |      |
|------------------------|------------------------------------------------------|-----|------|------|------|------|------|-----|------|
|                        | 10%                                                  | 20% | 30%  | 40%  | 50%  | 60%  | 70%  | 80% | 90%  |
| Adult survival         | 0                                                    | 0   | 0    | 0.01 | 0.01 | 0.03 | 0.05 | 0.1 | 0.23 |
| Fertility              | 0                                                    | 0   | 0.02 | 0.05 | 0.09 | 0.16 | 0.3  | 0.7 | 1.35 |
| Calf/Juvenile survival | 0                                                    | 0   | 0.02 | 0.09 | 0.18 | 0.31 | 0.49 | 0.8 | 1.46 |




Figure 6: Probability distribution showing the consensus distribution for the effects on fertility of a mature female harbour porpoise as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.






Figure 7: Probability distribution showing the consensus distribution for the effects on survival of a mature female harbour porpoise as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.




Figure 8: Probability distribution showing the consensus distribution for the effects on survival of juvenile or dependent calf harbour porpoise.

porpoise as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.

63 The predicted decline in bottlenose dolphin vital rates from the impact of a 6 dB PTS in the 2-10 kHz band for different percentiles of the elicited probability distribution are provided in Table 13. The data provided in Table 13 should be interpreted as:

- ▲ Experts estimated that the median decline in an individual mature female bottlenose dolphin's survival was 1.6% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).
- ▲ Experts estimated that the median decline in an individual mature female bottlenose dolphin's fertility was 0.43% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).
- ▲ Experts estimated that the median decline in an individual bottlenose dolphin juvenile survival was 1.32% (due to a 6 dB PTS (a notch a few kHz wide and 6dB high) occurring somewhere in the hearing between 2-10 kHz).
- ▲ Experts estimated that the median decline in an individual bottlenose dolphin dependent calf survival was 2.96% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).

**Table 13: Predicted decline in bottlenose dolphin vital rates for different percentiles of the elicited probability distribution.**

|                   | PERCENTILES OF THE ELICITED PROBABILITY DISTRIBUTION |      |      |      |      |      |      |       |       |
|-------------------|------------------------------------------------------|------|------|------|------|------|------|-------|-------|
|                   | 10%                                                  | 20%  | 30%  | 40%  | 50%  | 60%  | 70%  | 80%   | 90%   |
| Adult survival    | 0                                                    | 0.18 | 0.57 | 1.04 | 1.6  | 2.34 | 3.39 | 5.18  | 10.99 |
| Fertility         | 0                                                    | 0.04 | 0.13 | 0.26 | 0.43 | 0.85 | 1.66 | 3.49  | 6.22  |
| Juvenile survival | 0.01                                                 | 0.11 | 0.35 | 0.75 | 1.32 | 2.14 | 3.3  | 5.19  | 11.24 |
| Calf survival     | 0                                                    | 0.29 | 0.93 | 1.77 | 2.96 | 4.96 | 7.81 | 10.69 | 14.79 |




Figure 9: Probability distribution showing the consensus distribution for the effects on fertility of mature female bottlenose dolphin as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.




Figure 10: Probability distribution showing the consensus distribution for the effects on survival of mature female bottlenose dolphin as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.




Figure 11: Probability distribution showing the consensus distribution for the effects on survival of juvenile or dependent calf bottlenose dolphin as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.

64 The predicted decline in harbour and grey seals vital rates from the impact of a 6 dB PTS in the 2-10 kHz band for different percentiles of the elicited probability distribution are provided in Table 14. The data provided in Table 14 should be interpreted as:

- ▲ Experts estimated that the median decline in an individual mature female seal's survival was 0.39% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).
- ▲ Experts estimated that the median decline in an individual mature female seal's fertility was 0.27% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).
- ▲ Experts estimated that the median decline in an individual seal pup/juvenile survival was 0.52% (due to a 6 dB PTS (a notch a few kHz wide and 6 dB high) occurring somewhere in the hearing between 2-10 kHz).

Table 14: Predicted decline in harbour and grey seal vital rates for different percentiles of the elicited probability distribution.

|                | PERCENTILES OF THE ELICITED PROBABILITY DISTRIBUTION |      |      |      |      |      |      |      |      |
|----------------|------------------------------------------------------|------|------|------|------|------|------|------|------|
|                | 10%                                                  | 20%  | 30%  | 40%  | 50%  | 60%  | 70%  | 80%  | 90%  |
| Adult survival | 0.02                                                 | 0.1  | 0.18 | 0.27 | 0.39 | 0.55 | 0.78 | 1.14 | 1.89 |
| Fertility      | 0.01                                                 | 0.02 | 0.05 | 0.14 | 0.27 | 0.48 | 0.88 | 1.48 | 4.34 |
| Calf survival  | 0                                                    | 0.04 | 0.15 | 0.32 | 0.52 | 0.8  | 1.21 | 1.88 | 3    |




Figure 12: Probability distribution showing the consensus distribution for the effects on fertility of a mature female (harbour or grey) seal as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.




Figure 13: Probability distribution showing the consensus distribution for the effects on survival of a mature female (harbour or grey) seal as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.




Figure 14: Probability distribution showing the consensus distribution for the effects on survival of juvenile or dependent pup (harbour or grey) seal as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.

grey) seal as a consequence of a maximum 6 dB of PTS within a 2-10 kHz band.

## Other PTS-onset information

- 65 The low frequency noise produced during piling may be more likely to overlap with the hearing range of low frequency cetacean species such as minke whales. For minke whales, Tubelli et al. (2012) estimated the most sensitive hearing range (the region with thresholds within 40 dB of best sensitivity) to extend from 30 to 100 Hz up to 7.5 to 25 kHz, depending on the specific model used. Therefore a 2-10 kHz notch of 6 dB will only affect a small region of minke whale hearing. In addition, minke whale communication signals have been demonstrated to be below 2 kHz (Edds-Walton 2000, Mellinger et al. 2000, Gedamke et al. 2001, Risch et al. 2013, Risch et al. 2014). Like other mysticete whales, minke whales are also thought to be capable of hearing sounds through their skull bones (Cranford and Krysl 2015).
- 66 Data collected during wind farm construction have demonstrated that porpoise detections around the pile driving site decline several hours prior to the start of pile driving, and it is assumed that this is due to the increase in other construction related activities and vessel presence in advance of the actual pile driving (Brandt et al. 2018, Graham et al. 2019, Benhemma-Le Gall et al. 2020). Therefore, the presence of construction related vessels prior to the start of piling can act as a local scale deterrent for harbour porpoise and therefore reduce the risk of auditory injury. Assumptions that harbour porpoise are present in the vicinity of the pile driving at the start of the soft start are therefore likely to be overly conservative.
- 67 Seals are less dependent on hearing for foraging than cetaceans, but rely on sound for communication and predator avoidance (Deecke et al. 2002). Seals have very well developed tactile sensory systems that are used for foraging (Dehnhardt et al. 2001) and Hastie et al. (2015) reported that, based on calculations of SEL of tagged seals during the Lincs Offshore Windfarm construction, at least half of the tagged seals would have received a dose of sound greater than published thresholds for PTS.



- 68 A recent update of this analysis using the revised Southall et al. (2019) thresholds and weighting reduced this proportion to 25% of the seals (Russell and Hastie 2017). Based on the extent of the offshore wind farm construction in the Wash over the last ten years and the degree of overlap with the foraging ranges of harbour seals in the region (Russell et al. 2016a), it would not be unreasonable to suggest that a large number of individuals of the Wash population may have experienced levels of sound with the potential to cause hearing loss.
- 69 The Wash harbour seal population has been increasing over this period which may provide an indication that either: a) seals are not developing PTS despite predictions of exposure that would indicate that they should; or b) that the survival and fitness of individual seals are not affected by PTS. Point a) would indicate that methods for predicting PTS are perhaps unreliable and/ or over precautionary, and b) would suggest a lack of sensitivity to the effects of PTS.

## PTS sensitivity conclusions

- 70 In conclusion, given the results of the expert elicitation, which combined best available knowledge on the effects of PTS-onset on marine mammals, the sensitivity of all marine mammal species (except dolphins) to PTS-onset is considered to be **Low**, whereby individual vital rates (survival and reproduction) may be affected, but not at a significant level. Given that there was greater uncertainty in the estimates for bottlenose dolphins, all dolphin species have precautionarily been assessed as having a **Medium** sensitivity to PTS, whereby there is the potential for reductions to vital rates to some individuals.


### 7.5.2 VHF cetacean sensitivity to pile driving disturbance

- 71 Previous studies have shown that harbour porpoises are displaced from the vicinity of piling events. For example, studies at wind farms in the German North Sea have recorded large declines in porpoise detections close to the piling (>90% decline at noise levels above 170 dB) with decreasing effect with increasing distance from the pile (25% decline at noise levels between 145 and 150 dB) (Brandt et al. 2016). The detection rates revealed that porpoise were only displaced from the piling area in the short term (1 to 3 days) (Brandt et al. 2011, Dähne et al. 2013, Brandt et al. 2016, Brandt et al. 2018). Harbour porpoise are small cetaceans which makes them vulnerable to heat loss and requires them to maintain a high metabolic rate with little energy remaining for fat storage (e.g. Rojano-Doñate et al. 2018). This makes them vulnerable to starvation if they are unable to obtain sufficient levels of prey intake.
- 72 Studies using Digital Acoustic Recording Tags (DTAGs) have shown that porpoise tagged after capture in pound nets foraged on small prey nearly continuously during both the day and the night on their release (Wisniewska et al. 2016). However, Hoekendijk et al. (2018) point out that this could be an extreme short-term response to capture in nets, and may not reflect natural harbour porpoise behaviour. Nevertheless, if the foraging efficiency of harbour porpoise is disturbed or if they are displaced from a high-quality foraging ground, and are unable to find suitable alternative feeding grounds, they could potentially be at risk of changes to their overall fitness if they are not able to compensate and obtain sufficient food intake in order to meet their metabolic demands.
- 73 The results from Wisniewska et al. (2016) could also suggest that porpoises have an ability to respond to short term reductions in food intake, implying a resilience to disturbance. As Hoekendijk et al. (2018) argue, this could help explain why porpoises are such an abundant and successful species. It is important to note that the studies providing evidence for the responsiveness of harbour porpoises to piling noise have not provided any evidence for subsequent individual consequences. In this way, responsiveness to disturbance cannot reliably be equated to sensitivity to disturbance and porpoises may well be able to compensate by moving quickly to alternative areas to feed, while at the same time increasing their feeding rates.

- 74 Monitoring of harbour porpoise activity at the Beatrice Offshore Wind Farm during pile driving activity has indicated that porpoises were displaced from the immediate vicinity of the pile driving activity – with a 50% probability of response occurring at approximately 7 km (Graham et al. 2019). This monitoring also indicated that the response diminished over the construction period, so that eight months into the construction phase, the range at which there was a 50% probability of response was only 1.3 km. In addition, the study indicated that porpoise activity recovered between pile driving events.
- 75 A study of tagged harbour porpoises has shown large variability between individual responses to an airgun stimulus (van Beest et al. 2018). Of the five porpoises tagged and exposed to airgun pulses at ranges of 420–690 m (SEL 135–147 dB re 1  $\mu\text{Pa}^2\text{s}$ ), one individual showed rapid and directed movements away from the source. Two individuals displayed shorter and shallower dives immediately after exposure and the remaining two animals did not show any quantifiable response. Therefore, there is expected to be a high level of variability in responses from individual harbour porpoises exposed to low frequency broadband pulsed noise (including both airguns and pile-driving).
- 76 At a BEIS-funded expert elicitation workshop held in Amsterdam in June 2018, experts in marine mammal physiology, behaviour and energetics discussed the nature, extent and potential consequences of disturbance to harbour porpoise from exposure to low frequency broadband pulsed noise (e.g. pile-driving, airgun pulses) (Booth et al. 2019). Experts were asked to estimate the potential consequences of a six-hour period of zero energy intake, assuming that disturbance from a pile driving event resulted in missed foraging opportunities for this duration. A Dynamic Energy Budget model for harbour porpoise (based on the DEB model in Hin et al. (2019)) was used to aid discussions regarding the potential effects of missed foraging opportunities on survival and reproduction. The model described the way in which the life history processes (growth, reproduction and survival) of a female and her calf depend on the way in which assimilated energy is allocated between different processes and was used during the elicitation to model the effects of energy intake and reserves following simulated disturbance.



77 The experts agreed that first year calf survival (post-weaning) and fertility were the most likely vital rates to be affected by disturbance, but that juvenile and adult survival were unlikely to be significantly affected as these life-stages were considered to be more robust. Experts agreed that the final third of the year was the most critical for harbour porpoises as they reach the end of the current lactation period and the start of new pregnancies, therefore it was thought that significant impacts on fertility would only occur when animals received repeated exposure throughout the whole year. Experts agreed it would likely take high levels of repeated disturbance to an individual before there was any effect on that individual's fertility (Figure 15 left), and that it was very unlikely an animal would terminate a pregnancy early. The experts agreed that calf survival could be reduced by only a few days of repeated disturbance to a mother/calf pair during early lactation (Figure 15 right); however, it is highly unlikely that the same mother-calf pair would repeatedly return to the area in order to receive these levels of repeated disturbance.



**Figure 15: Probability distributions showing the consensus of the expert elicitation for harbour porpoise disturbance from piling (Booth et al., 2019).**

Left: the number of days of disturbance (i.e. days on which an animal does not feed for six hours) a pregnant female could 'tolerate' before it has any effect on fertility. Right: the number of days of disturbance (of six hours zero energy intake) a mother/calf pair could 'tolerate' before it has any effect on survival.

- 78 A recent study by Benhemma-Le Gall et al. (2021) provided two key findings in relation to harbour porpoise response to pile driving. Porpoise were not completely displaced from the piling site: detections of clicks (echolocation) and buzzing (associated with prey capture) in the short-range (2 km) did not cease in response to pile driving, and porpoise appeared to compensate: detections of both clicks (echolocation) and buzzing (associated with prey capture) increased above baseline levels with increasing distance from the pile, which suggests that those porpoise that are displaced from the near-field, compensate by increasing foraging activities beyond the impact range (Figure 16). Therefore, porpoise that experience displacement are expected to be able to compensate for the lost foraging opportunities and increased energy expenditure of fleeing.




Figure 16: The probability of harbour porpoise occurrence and buzzing activity per hour during (dashed red line) and out with (blue line) pile-driving hours, in relation to distance from the pile-

driving vessel at Beatrice (left) and Moray East (right). Obtained from Benhemma-Le Gall et al. (2021).

- 79 While much of the evidence base included within this section is from studies of animals in the North Sea, it is expected that harbour porpoise in the Irish sea would respond in a similar way, and therefore the data are considered to be applicable.
- 80 Due to observed responsiveness to piling, their income breeder life history, and the low numbers of days of disturbance expected to effect calf survival, harbour porpoises have been assessed here as having a **low** sensitivity to disturbance and resulting displacement from foraging grounds.

### 7.5.3 HF Cetacean sensitivity to pile driving disturbance

#### Bottlenose dolphin

- 81 Bottlenose dolphins have been shown to be displaced from an area as a result of the noise produced by offshore construction activities; for example, avoidance behaviour in bottlenose dolphins has been shown in relation to dredging activities (Pirotta et al. 2013). In a recent study on bottlenose dolphins in the Moray Firth (in relation to the construction of the Nigg Energy Park in the Cromarty Firth), small effects of pile driving on dolphin presence have been observed, however, dolphins were not excluded from the vicinity of the piling activities (Graham et al. 2017b). In this study, the median peak-to-peak source levels recorded during impact piling were estimated to be 240 dB re 1µPa (range 8 dB) with a single pulse source level of 198 dB re 1 µPa<sup>2</sup>s. The pile driving resulted in a slight reduction of the presence, detection positive hours and the encounter duration for dolphins within the Cromarty Firth, however, this response was only significant for the encounter durations. Encounter durations decreased within the Cromarty Firth (though only by a few minutes) and increased outside of the Cromarty Firth on days of piling activity. These data highlight a small spatial and temporal scale disturbance to bottlenose dolphins as a result of impact piling activities.

- 82 According to the opinions of the experts involved in the expert elicitation for iPCoD (the interim Population Consequences of Disturbance framework), which forms our best available knowledge on the topic, disturbance would be most likely to affect bottlenose dolphin calf survival, where: *“Experts felt that disturbance could affect calf survival if it exceeded 30-50 days, because it could result in mothers becoming separated from their calves and this could affect the amount of milk transferred from the mother to her calf”* (Harwood et al. 2014).
- 83 There is the potential for behavioural disturbance and displacement to result in disruption in foraging and resting activities and an increase in travel and energetic costs. However, it has been previously shown that bottlenose dolphins have the ability to compensate for behavioural responses as a result of increased commercial vessel activity (New et al. 2013). Therefore, while there remains the potential for disturbance and displacement to affect individual behaviour and therefore vital rates and population level changes, bottlenose dolphins do have some capability to adapt their behaviour and tolerate certain levels of temporary disturbance. Therefore, since bottlenose dolphins are expected to be able to adapt their behaviour, with the impact most likely to result in potential changes in calf survival (but not expected to affect adult survival or future reproductive rates) bottlenose dolphins are considered to have a **low** sensitivity to behavioural disturbance from piling.

## Common dolphin

- 84 The hearing range of common dolphins is currently estimated from their sound production, and has been labelled medium-high frequency, spanning between 150 Hz to 160 kHz (Finneran 2016, Houser et al. 2017). There are few studies investigating the effects of pile driving on common dolphins, which could relate to their occupation of deeper waters, contrasting with the shallower habitat in which offshore construction frequently occurs.



- 85 However, an analysis of pile driving activity in Broadhaven Bay, Ireland, found construction activity to be associated with a reduction in the presence of minke whales and harbour porpoise, but not with common dolphins (Culloch et al. 2016). Conversely, increased vessel presence during the construction period was associated with a decrease of common dolphins in the surrounding area. While there is little information on the Impacts of pile driving on common dolphins, there are a few studies documenting the impacts of seismic activity. Although the noise produced by airguns differs in its duration and cumulative acoustic energy levels, it may be similar in its frequency range to the low-frequency noise produced by pile driving. In general, there is contrasting evidence for the response of common dolphins to seismic surveys. While some research indicates no change in the occurrence or sighting density of common dolphins when exposed to seismic activity (Stone et al. 2017, Kavanagh et al. 2019), Goold (1996) found a reduction in common dolphin presence within 1 km of ongoing seismic surveys near Pembrokeshire.
- 86 The sparse information available for the impacts of construction, seismic activity and vessel noise on common dolphins makes it difficult to assess the risk for this species. While there is some evidence of disturbance of animals by seismic activity, and reduced presence in increasingly noisy habitat, this species may adjust its whistle characteristics to account for masking, suggesting some flexibility or tolerance.
- 87 Given that they are grouped as high-frequency cetaceans alongside bottlenose dolphins, and are therefore likely to have similar hearing abilities, common dolphins are also considered to have a **Low** sensitivity to behavioural disturbance from piling.

### Risso's dolphin

- 88 In the absence of any species-specific data, given that they are both grouped as high-frequency cetaceans, and are therefore likely to have similar hearing abilities, Risso's dolphins are also considered to have a **Low** sensitivity to behavioural disturbance from piling.

#### 7.5.4 LF cetacean sensitivity to pile driving disturbance

- 89 There is little information available on the behavioural responses of minke whales to underwater noise. Minke whales have been shown to change their diving patterns and behavioural state in response to disturbance from whale watching vessels; and it was suggested that a reduction in foraging activity at feeding grounds could result in reduced reproductive success in this capital breeding species (Christiansen et al. 2013). There is only one study showing minke whale reactions to sonar signals (Sivle et al. 2015) with severity scores above 4 for a received SPL of 146 dB re 1  $\mu$ Pa (score 7) and a received SPL of 158 dB re 1  $\mu$ Pa (score 8). There is a study detailing minke whale responses to the Lofitech device which has a source level of 204 dB re 1  $\mu$ Pa @1m, which showed minke whales within 500 m and 1,000 m of the source exhibiting a behavioural response. The estimated received level at 1,000 m was 136.1 dB re 1  $\mu$ Pa (McGarry et al. 2017).
- 90 Since minke whales are known to forage in UK waters in the summer months, there is the potential for displacement to impact on reproductive rates. However, due to their large size and capacity for energy storage, it is expected that minke whales will be able to tolerate temporary displacement from foraging areas much better than harbour porpoise and individuals are expected to be able to recover from any impact on vital rates. Therefore, minke whales have been assessed as having a **Low** sensitivity to disturbance from pile driving.

#### 7.5.5 Seal sensitivity to pile driving disturbance

- 91 There are still limited data on grey seal behavioural responses to pile driving. The key dataset on this topic is presented in Aarts et al. (2018) where 20 grey seals were tagged in the Wadden Sea to record their responses to pile driving at two offshore wind farms: Luchterduinen in 2014 and Gemini in 2015. The grey seals showed varying responses to the pile driving, including no response, altered surfacing and diving behaviour, and changes in swimming direction. The most common reaction was a decline in descent speed and a reduction in bottom time, which suggests a change in behaviour from foraging to horizontal movement.

- 92 The distances at which seals responded varied significantly; in one instance a grey seal showed responses at 45 km from the pile location, while other grey seals showed no response when within 12 km. Differences in responses could be attributed to differences in hearing sensitivity between individuals, differences in sound transmission with environmental conditions or the behaviour and motivation for the seal to be in the area. The telemetry data also showed that seals returned to the pile driving area after pile driving ceased. While this evidence base is from studies of grey seals tagged in the Wadden Sea, it is expected that grey seals in the Irish Sea would respond in a similar way, and therefore the data are considered to be applicable.
- 93 The expert elicitation workshop in Amsterdam in 2018 (Booth et al. 2019) concluded that grey seals were considered to have a reasonable ability to compensate for lost foraging opportunities due to their generalist diet, mobility, life history and adequate fat stores and that the survival of 'weaned of the year' animals and fertility were determined to be the most sensitive parameters to disturbance (i.e. reduced energy intake). However, in general, experts agreed that grey seals would be much more robust than harbour seals to the effects of disturbance due to their larger energy stores and more generalist and adaptable foraging strategies. It was agreed that grey seals would require moderate-high levels of repeated disturbance before there was any effect on fertility rates to reduce fertility (Figure 17 left). The 'weaned of the year' were considered to be most vulnerable following the post-weaning fast, and that during this time it might take ~60 days of repeated disturbance before there was expected to be any effect on weaned-of-the-year survival (Figure 17 right), however there was a lot of uncertainty surrounding this estimate.



- 94 Grey seals are capital breeders and store energy in a thick layer of blubber, which means that, in combination with their large body size, they are tolerant of periods of fasting as part of their normal life history. Grey seals are also highly adaptable to a changing environment and are capable of adjusting their metabolic rate and foraging tactics, to compensate for different periods of energy demand and supply (Beck et al. 2003, Sparling et al. 2006). Grey seals are also very wide ranging and are capable of moving large distances between different haul out and foraging regions (Russell et al. 2013). Therefore, they are unlikely to be particularly sensitive to displacement from foraging grounds during periods of active piling.
- 95 Hastie et al. (2021) found that grey seal avoidance rates in response to pile driving sounds were dependent on the quality of the prey patch, with grey seals continuing to forage at high density prey patches when exposed to pile driving sounds but showing reduced foraging success at low density prey patches when exposed to pile driving sounds. Additionally, the seals showed an initial aversive response to the pile driving playbacks (lower proportion of dives spent foraging) but this diminished during each trial. Therefore, the likelihood of grey seal response is expected to be linked to the quality of the prey patch. The quality of the AyM array area as a prey patch is unknown, and the importance of this area to grey seals specifically for foraging has not been quantitatively assessed. However, some inference can be made from movement and distribution data. Habitat preference data do not appear to indicate that the AyM array area itself is an important foraging location, though there are higher densities predicted to occur in the Dee estuary.
- 96 Due to observed responsiveness to piling, and their life-history characteristics, grey seals have been assessed as having **negligible** sensitivity to disturbance and resulting displacement from foraging grounds during pile-driving events.




Figure 17: Probability distributions showing the consensus of the expert elicitation for grey seal disturbance from piling (Booth et al., 2019).

Left: the number of days of disturbance (i.e. days on which an animal does not feed for six hours) a pregnant female could 'tolerate' before it has any effect on fertility. Right: the number of days of disturbance (of six hours zero energy intake) a 'weaned of the year' grey seal could 'tolerate' before it has any effect on survival.

### 7.5.6 Harbour porpoise sensitivity to vessels

97 Given their high-frequency hearing range, it has been suggested that porpoise are more likely to be sensitive to vessels that produce medium to high frequency noise components (Hermannsen et al. 2014). However, harbour porpoise are known to avoid vessels and behavioural responses have been shown in porpoise exposed to vessel noise that contains low levels of high-frequency components (Dyndo et al. 2015). Thomsen et al. (2006) estimated that porpoise will respond to both small (~2 kHz) and large (~0.25 kHz) vessels at approximately 400 m. Wisniewska et al. (2018) presented data that suggested that porpoises may respond to very close-range vessel passes with an interruption in foraging. However, observed responses were short lived, porpoises were observed to resume foraging ten minutes after a very close-range vessel encounter, and tagged porpoises remained in areas where shipping levels were high. Overall, despite animals remaining in heavily trafficked areas, the incidence of responses to vessels was low, indicating little fitness cost to exposure to vessel noise and any local scale responses taken to avoid vessels. It is likely that porpoise may become habituated where vessel movements are regular and predictable whereas they may be expected to show more of a local behavioural response to novel vessel activities related to construction activities.

- 98 Data collected during windfarm construction have demonstrated that porpoise detections around the pile driving site decline several hours prior to the start of pile driving, and it is assumed that this is due to the increase in other construction related activities and vessel presence in advance of the actual pile driving (Brandt et al. 2018, Benhemma-Le Gall et al. 2021). Therefore, because the dose-response relationships relating displacement to piling are based on data collected over periods including such vessel activity, these local responses to novel activity such as pile driving vessels have effectively already been included in the assessment of underwater noise related to pile driving above.
- 99 Land-based surveys in Swansea Bay, Wales, found a significant correlation between porpoise sightings and the number of vessels present, with 26% of the interactions considered to be negative (moving away or prolonged dives), occurring within distances of up to 1 km between the animal and the vessel. The type of vessel was relevant, as smaller motorised boats (jet-ski, speed boat, small fishing vessels), were associated with more negative behaviours than larger ships (Oakley et al. 2017).
- 100 Heinänen and Skov (2015) suggested that harbour porpoise density was significantly lower in areas with vessel transit rates of greater than 20,000 ships/year (80 per day). Vessel traffic in the AyM area will be below this figure (see Volume 2, Chapter 1: Offshore Project Description and Table 18) as it is anticipated that the peak number of vessels on-site simultaneously will be 35 vessels during construction and 22 vessels during O&M. This level of activity is the anticipated peak, and therefore it is expected that average daily levels will be lower and will not lead to significant changes in porpoise density in the area. Therefore, harbour porpoise are assessed as having a **low** sensitivity to disturbance from vessels.



### 7.5.7 Dolphin sensitivity to vessels

- 101 Pirotta et al. (2015) found that transit of vessels in the Moray Firth resulted in a reduction (by almost half) of the likelihood of recording bottlenose dolphin prey capture buzzes. They also suggest that vessel presence, not just vessel noise, resulted in disturbance. There is however likely to be rapid recovery from disturbance from vessel presence and vessel noise, as they recorded little pre-emptive disturbance or recovery time following disturbance. There is evidence of bottlenose dolphin habituation to boat traffic, particularly in relation to larger vessel types (Sini et al. 2005). Lusseau et al. (2011) undertook a modelling study which predicted that increased vessel movements associated with offshore wind development in the Moray Firth did not have a negative effect on the local population of bottlenose dolphin. They hypothesise that this was because most of the vessels were commercial ones, which have more predictable patterns of movement than the recreational vessels and are thus less likely to disrupt the feeding behaviour of dolphins than recreational or tourist activity. Therefore, bottlenose dolphins have been assumed as having a **low** sensitivity to disturbance from vessels.
- 102 In the absence of any species-specific data, given that they are both grouped as high-frequency cetaceans, and are therefore likely to have similar hearing abilities, Risso's dolphins are also considered to have a **low** sensitivity to behavioural disturbance from vessels.

### 7.5.8 Minke whale sensitivity to vessels

- 103 There is limited information available on the responses of minke whales to vessels. Whale watching vessels that specifically target minke whales have been shown to cause behavioural responses in minke whales and repeated exposure can result in a decrease in foraging activity (Christiansen et al. 2013). However, these are vessels which specifically target and follow minke whales, so it is unknown whether minke whales respond to more general ship traffic.



104 A conservative approach is assumed that vessel disturbance could result in temporary displacement of minke whales from the immediate area, however there is no evidence that the AyM area is an important foraging habitat for minke whales, and given their generalist and varied diet, it is not expected that any temporary displacement resulting from vessel activity in relation to the AyM will lead to any significant effect on individual energy budgets and subsequently fitness. The sensitivity of minke whales to vessel disturbance is therefore assessed as **low**.

#### 7.5.9 Grey seal sensitivity to vessels

105 Jones et al. (2017) presents an analysis of the predicted co-occurrence of ships and seals at sea which demonstrates that UK wide there is a large degree of predicted co-occurrence, particularly within 50 km of the coast close to seal haul-outs. There is no evidence relating decreasing seal populations with high levels of co-occurrence between ships and animals. In fact, in areas where seal populations are showing high levels of growth (e.g. southeast England) ship co-occurrences are highest (Jones et al. 2017). Thomsen et al. (2006) estimated that both harbour and grey seals will respond to both small (~2 kHz) and large (~0.25 kHz) vessels at approximately 400 m. The sensitivity of grey seals to disturbance from vessels is therefore assessed as **negligible**.

#### 7.5.10 Sensitivity summary

106 Through the use of literature reviews on the potential impacts of underwater noise on marine mammals, the sensitivity of each species to PTS-onset and behavioural disturbance from pile driving has been assessed. While much of the evidence base included within this section is from studies of animals in the North Sea, it is expected that marine mammals in the Irish Sea would respond in a similar way, and therefore the data are considered to be applicable. Given the definitions of marine mammal sensitivity provided in Table 10, all marine mammals have been assessed as having either a low or negligible sensitivity to PTS-onset and behavioural disturbance from pile driving and vessel activity (Table 15), with the exception of dolphin species which have been precautionarily assessed as having a medium sensitivity to PTS.

Table 15: Summary of key marine mammal sensitivity assessments.

| SPECIES            | PTS FROM PILING | PILING DISTURBANCE | VESSEL DISTURBANCE |
|--------------------|-----------------|--------------------|--------------------|
| Harbour porpoise   | Low             | Low                | Low                |
| Bottlenose dolphin | Medium          | Low                | Low                |
| Common dolphin     | Medium          | Low                | Low                |
| Risso's dolphin    | Medium          | Low                | Low                |
| Minke whale        | Low             | Low                | Low                |
| Grey seal          | Low             | Negligible         | Negligible         |

## 7.6 Uncertainty and technical difficulties encountered

107 There are uncertainties relating to the underwater noise modelling and impact assessment for AyM. Broadly, these relate to predicting exposure of animals to underwater noise, predicting the response of animals to underwater noise and predicting potential population consequences of disturbance from underwater noise. Further detail of such uncertainty is presented in Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, Limitations and Uncertainties.

## 7.7 Existing environment

108 The existing environment for marine mammals is detailed in Volume 4: Annex 7.1: Marine Mammal Baseline Characterisation, with a summary provided here. This PEIR chapter should therefore be read alongside the detailed Marine Mammal Baseline Characterisation annex which assesses the range of species and the abundance and density of marine mammals that could potentially be impacted by the AyM offshore wind farm, informed by data collected across previous offshore wind farm projects and surveys covering the marine mammal MUs that include the AyM array area.

109 The data available (see section 7.4.2 for details of data sources) have confirmed the likely presence of harbour porpoise, bottlenose dolphins, common dolphins, Risso's dolphin, minke whale and grey seal in the vicinity of AyM and, therefore, these species should be considered within the quantitative impact assessment. The most robust and relevant density estimates within each MU were determined for each species, with harbour porpoise estimated to have the highest density within its respective MU (Table 16).

**Table 16: Marine mammal MU and density estimates (#/km<sup>2</sup>) taken forward to impact assessment.**

| SPECIES            | MU                            | MU SIZE | MU REF        | DENSITY                                           | DENSITY REF                                                                           |
|--------------------|-------------------------------|---------|---------------|---------------------------------------------------|---------------------------------------------------------------------------------------|
| Harbour porpoise   | Celtic and Irish Seas         | 62,517  | IAMMWG (2021) | 0.13                                              | JCP Tool                                                                              |
|                    |                               |         |               | 1.0                                               | Averaged across costal and offshore estimates from Evans et al. (2021) <sup>iii</sup> |
| Bottlenose dolphin | Irish Sea                     | 293     | IAMMWG (2021) | 0.035 within the 20 m depth contour, 0.008 beyond | Lohrengel et al. (2018) and SCANS III (Hammond et al. 2017, Hammond et al. 2021)      |
| Common dolphin     | Celtic and Greater North Seas | 102,656 | IAMMWG (2021) | 0.0081                                            | SCANS II (Hammond et al. 2006)                                                        |

<sup>iii</sup> Please see Volume 4: Annex 7.1: Marine Mammal Baseline Characterisation for details as to why this estimate is considered to be highly precautionary.

| SPECIES         | MU                            | MU SIZE | MU REF                            | DENSITY            | DENSITY REF                                          |
|-----------------|-------------------------------|---------|-----------------------------------|--------------------|------------------------------------------------------|
| Risso's dolphin | Celtic and Greater North Seas | 12,262  | IAMMWG (2021)                     | 0.031              | SCANS III (Hammond et al. 2017, Hammond et al. 2021) |
| Minke whale     | Celtic and Greater North Seas | 20,118  | IAMMWG (2021)                     | 0.017              | SCANS III (Hammond et al. 2017, Hammond et al. 2021) |
| Grey seal       | OSPAR region III              | 66,100  | Derived from Carter et al. (2020) | Grid cell specific | Carter et al. (2020)                                 |
|                 | Wales and NW England MUs      | 5,000   | Derived from (SCOS 2021)          |                    |                                                      |

110 Harbour porpoise within the 'Celtic and Irish Seas' MU have an estimated abundance of 62,517 (95% CI: 48,324 – 80,877, CV: 0.13) (estimated using data from SCANS III and ObSERVE) (IAMMWG 2021). Whilst they are listed as Least Concern on the IUCN red, the 2021 abundance estimate was a significant decrease from the previous estimate using the SCANS II and CODA data which was 104,695 porpoise (95% CI: 56,774 – 193,065, CV: 0.32)(IAMMWG 2015).

- 111 Harbour porpoise were found to have a widespread distribution within the MU and were observed at the AyM site year-round during the 24 months of site-specific surveys. The high proportion of unidentified sightings during the site-specific surveys meant that the data were unsuitable for baseline characterisation. Instead, the JCP Phase III Tool density estimate for the AyM area (0.13 porpoise/km<sup>2</sup>) was identified as the most suitable to take forward to impact assessment, alongside the precautionary density estimate obtained from the Sea Watch Foundation (SWF) report (1.0 porpoise/km<sup>2</sup>, averaged across coastal and offshore areas) (Evans et al. 2021) (Table 16).
- 112 Bottlenose dolphin within the 'Irish Sea' MU have an estimated abundance of 293 dolphins (95% CI: 108 – 793, CV: 0.54) (estimated using data from SCANS III and ObSERVE) (IAMMWG 2021). No bottlenose dolphins were identified during the 24 months of site-specific surveys although there were several sightings of dolphins which could not be identified to species level. They have, however, been recorded year-round in the wider region during the GyM surveys and around Anglesey (Evans et al. 2021). There is evidence of large home ranges and connectivity of bottlenose dolphins within the MU with photo-identification from boat-based and land-based surveys identifying the same individuals in both North Wales and Cardigan Bay SAC (Feingold and Evans 2014). Therefore, density estimates in North Wales are estimated to be similar to that of Cardigan Bay (Lohrengel et al. 2018). The population is known to have a large home range (Pesante et al. 2008) and therefore, the impacts of the development of the AyM offshore wind farm could potentially impact other populations, although the extent of this impact is largely unknown.



- 113 Common dolphins in the UK are all part of the Celtic and Greater North Seas' MU. The current abundance estimate for this MU is 102,656 (CV=0.29; 95% CI=58,932 –178,822) (estimated using data from SCANS III and ObSERVE)(IAMMWG 2021). No common dolphins were identified during the 24 months of site-specific surveys although there were several sightings of dolphins which could not be identified to species level. They have, however, been recorded in the wider study area for GyM and have been recorded by the Sea Watch Foundation in the coastal waters of North Wales, with sightings recorded year-round. The SCANS II density estimate (0.0081 dolphins/km<sup>2</sup>) is slightly higher than the more local scale density estimate of ~0.005 dolphins/km<sup>2</sup> estimated by the Sea Watch Foundation (Evans et al. 2021) and is thus considered to be a conservative estimate for the area.
- 114 A single MU is implemented for Risso's dolphins in UK waters: 'Celtic and Greater North Seas' MU. The current abundance estimate for this MU is 12,262 (95% CI: 5,227 – 28,764, CV: 0.46) (estimated using data from SCANS III and ObSERVE)(IAMMWG 2021). There have previously been no abundance estimates in UK waters for Risso's dolphins, but as this MU covers all UK waters this estimate is not representative of the potential abundance within the region surrounding the AyM site. No site-specific densities can be calculated due to the absence of Risso's dolphin sightings during the 24 months of AyM site specific surveys. However, other surveys observed Risso's dolphins around north Anglesey and Bardsey Island (Baines and Evans 2012) and north Wales (Evans et al. 2021). The Sea Watch Foundation have recorded Risso's dolphin in north Wales between April and November inclusive, though PAM conducted in the Holyhead Deeps west of Anglesey indicates that the species is present offshore all year round (G. Veneruso, pers. comm.). Therefore, it is considered to be precautionary to include this species quantitatively in the impact assessment.



- 115 Minke whale abundance is also analysed within the 'Celtic and Greater North Seas' MU and is estimated at 20,118 (95% CI: 14,061 – 28,786, CV: 0.18) (estimated using data from SCANS III and ObSERVE) (IAMMWG 2021). Data shows minke whales have patchy distribution within the Irish Sea with low sightings rates in vicinity of the AyM array area (Baines and Evans 2012), substantiated by the absence of sightings during the 24 months of AyM surveys and multiple GyM surveys conducted. However, given the presence of minke whale within the wider region recorded during SCANS III and ObSERVE survey, minke whales are expected to be present in the Irish Sea in the summer months and therefore should be included in the AyM impact assessment.
- 116 Grey seal abundance has been examined within two MUs: the OSPAR Region II: Celtic Seas MU (interim MU, proposed by NRW 2020) and the combined Wales and Northwest England seal MUs (as used in SCOS reporting). The OSPAR Region II: Celtic Seas MU has an estimated abundance of 66,100 seals. The combined Wales and Northwest England seal MUs has an estimated abundance of 5,000 seals. The large variability between these two estimates can be attributed to the differing sizes of the MUs and differing survey effort and analysis methods used. Seals were observed during both the AyM and GyM surveys. In North Wales, grey seals mainly haul-out around the coast of Anglesey (including the Skerries), around Llandudno (Angel Bay) and the Dee Estuary (Hilbre North and West Hoyle Sandbank). There are also confirmed pupping sites also around Anglesey and the Llyn Peninsula, although the majority of pup production in Welsh waters is located in Pembrokeshire, where there is an estimated 4% of the UK breeding population.

### 7.7.1 Evolution of the baseline

- 117 The Infrastructure Planning (Environmental Impact Assessment) Regulations 2017 require that “A description of the relevant aspects of the current state of the environment (baseline scenario) and an outline of the likely evolution thereof without implementation of the development as far as natural changes from the baseline scenario can be assessed with reasonable effort on the basis of the availability of environmental information and scientific knowledge” is included within the ES (EIA Regulations, Schedule 4, Paragraph 3). From the point of assessment, over the course of the development and operational lifetime of AyM (operational lifetime anticipated to be up to 25 years from first power), long-term trends mean that the condition of the baseline environment is expected to evolve. This section provides a qualitative description of the evolution of the baseline environment, on the assumption that AyM is not constructed, using available information and scientific knowledge of marine mammal ecology.
- 118 It is challenging to predict the future trajectories of marine mammal populations. Some UK marine mammal populations have undergone periods of significant change in parts of their range, with a limited understanding of the driving factors responsible. For example, there is uncertainty about whether a reduction in pup mortality or an increase in fecundity is the cause of the recent exponential growth of grey seals in the North Sea (Russell et al. 2017). Additionally, there is no appropriate monitoring at the right temporal or spatial scales to really understand the baseline dynamics of some marine mammal populations, including all cetacean species included in this assessment.

119 The results of the most recent UK assessment of favourable conservation status for each marine mammal species included in the assessment are outlined in Table 17. Grey seals are considered to have a favourable conservation status and all other species are considered to have an Unknown conservation status. It is worth noting that while the UK harbour porpoise population has been assessed as having Favourable future prospects, the most recent abundance estimate for the Celtic and Irish Sea MU is significantly lower than the previous estimate. The current estimate is 62,517 porpoise (95% CI: 48,324 – 80,887, CV 0.13) (IAMMWG 2021) which is only 60% of the previous estimate of 104,695 porpoise (95% CI: 56,774 - 193,065, CV: 0.32) (IAMMWG 2015). The updated estimates do not discuss the potential reasons behind the decline in abundance in the Celtic and Irish Sea MU.

**Table 17: Summary of the conservation status of each marine mammal species (FV = Favourable, XX = Unknown, + = Improving).**

| SPECIES            | RANGE | POPULATION | HABITAT | FUTURE PROSPECT: | CONSERVATION STATUS | OVERALL TREND | REFERENCE    |
|--------------------|-------|------------|---------|------------------|---------------------|---------------|--------------|
| Harbour porpoise   | FV    | XX         | XX      | FV               | XX                  | XX            | JNCC (2019c) |
| Bottlenose dolphin | FV    | XX         | XX      | XX               | XX                  | XX            | JNCC (2019a) |
| Common dolphin     | FV    | XX         | XX      | XX               | XX                  | XX            | JNCC (2019b) |
| Risso's dolphin    | FV    | XX         | XX      | XX               | XX                  | XX            | JNCC (2019e) |
| Minke whale        | FV    | XX         | XX      | XX               | XX                  | XX            | JNCC (2019f) |

| SPECIES   | RANGE | POPULATION | HABITAT | FUTURE PROSPECT | CONSERVATION STATUS | OVERALL TREND | REFERENCE    |
|-----------|-------|------------|---------|-----------------|---------------------|---------------|--------------|
| Grey seal | FV    | FV         | FV      | FV              | FV                  | +             | JNCC (2019d) |

120 The potential impacts of climate change on marine mammals were reviewed and synthesised by Evans and Bjørge (2013) and they concluded that this topic remains poorly understood. In the UK, changes are predicted to manifest in relation to changes in prey abundance and distribution as a result of warmer sea temperatures. The authors also conclude that species likely to be most affected in the future will be those that have relatively narrow habitat requirements and that shelf sea species like the harbour porpoise, white-beaked dolphin and minke whale may come under increased pressure with reduced available habitat, if their range shifts northwards. Although the main cause of widespread declines in UK harbour seal population is not known, the prevalence of domoic acid derived from toxic algae may be a contributory factor and could be exacerbated by increased sea temperatures (Evans and Bjørge 2013). In addition, sea level rise and an increase in storm frequency and associated wave surges could affect the availability of haul out sites for seals and increased storm frequency and associated conditions could also lead to increased pup and calf mortality (Prime 1985, Gazo et al. 2000, Lea et al. 2009).

## 7.8 Key parameters for assessment

121 Table 18 identifies the MDS in environmental terms, defined by the project design envelope. This is to establish the maximum potential impact associated with the project.

Table 18: Maximum design scenario.

| POTENTIAL EFFECT        | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                                                                                                                                                                         | JUSTIFICATION                                                                                                                                                                                                                                                                                                                        |
|-------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| CONSTRUCTION            |                                                                                                                                                                                                                                                                                                                                                                                                          |                                                                                                                                                                                                                                                                                                                                      |
| PTS from piling         | <p>Monopile WTG (Spatial MDS disturbance):</p> <ul style="list-style-type: none"> <li>Max 50 WTG</li> <li>Max 15 m pile diameter</li> <li>Max hammer energy: 5,000 kJ</li> <li>Max 2 monopiles/day = 25 piling days</li> <li>Contingency three days to install 1 monopile = 150 days</li> </ul>                                                                                                          | <p>The piling scenario with the largest PTS-onset impact ranges represents the spatial MDS for PTS.</p> <p>The piling scenario with the greatest number of piling days represents the temporal MDS for PTS.</p> <p>The maximum number of piled foundations would represent the temporal maximum design scenario for disturbance.</p> |
| Disturbance from piling | <p>Monopile Other structures:</p> <ul style="list-style-type: none"> <li>Max 2 OSP &amp; 1 met mast</li> <li>Max 2 monopiles for OSP (or total 16 smaller monopiles)</li> <li>Max 1 monopile for met mast</li> <li>Max 15 m column diameter</li> <li>Max hammer energy: 5,000 kJ</li> <li>Max 2 monopiles/day = 9 piling days</li> <li>Contingency three days to install 1 monopile = 51 days</li> </ul> | <p>The maximum predicted impact range for underwater noise for piled foundations would represent the spatial maximum design scenario for disturbance.</p>                                                                                                                                                                            |

| POTENTIAL EFFECT | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | JUSTIFICATION |
|------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
|                  | <p>Multi-leg jacket WTG: 1 piling vessel<br/>(Temporal MDS disturbance &amp; PTS):</p> <ul style="list-style-type: none"> <li>➤ Max 50 WTG</li> <li>➤ Max 4 legs per jacket</li> <li>➤ Max 200 legs in total</li> <li>➤ Max leg diameter: 3.5 m</li> <li>➤ Max hammer energy: 3,000 kJ</li> <li>➤ Max 4 legs/day = 50 piling days</li> <li>➤ Contingency two days to install 1 jacket = 100 days</li> </ul> <p>Multi-leg jacket WTG: 2 piling vessels at 1 location (Spatial MDS PTS):</p> <ul style="list-style-type: none"> <li>➤ Max 50 WTG</li> <li>➤ Max 4 legs per jacket</li> <li>➤ Max 200 legs in total</li> <li>➤ Max leg diameter: 3.5 m</li> <li>➤ Max hammer energy: 3,000 kJ</li> <li>➤ Max 4 legs/day per vessel = 25 piling days</li> </ul> |               |



| POTENTIAL EFFECT                               | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                                                                                                                                                                                                                                                        | JUSTIFICATION                                                               |
|------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------|
|                                                | <p>Multi-leg OSPs:</p> <ul style="list-style-type: none"> <li>➤ Max 2 OSP</li> <li>➤ Max 12 legs per OSP</li> <li>➤ Max 24 legs in total</li> <li>➤ Max leg diameter: 3.5 m</li> <li>➤ Max hammer energy: 3,000 kJ</li> <li>➤ Max 4 legs/day = 6 piling days</li> </ul> <p>Foundation installation: Jan-Dec 2028</p> <p>Cofferdam:</p> <ul style="list-style-type: none"> <li>➤ Max 650 Sheet piles</li> <li>➤ Max width: 750 mm</li> <li>➤ Max 8 piles/day = 81 piling days</li> </ul> |                                                                             |
| Disturbance from other construction activities | <ul style="list-style-type: none"> <li>➤ Seabed preparation: levelling and/or dredging of soft mobile sediments as well as boulder and obstacle removal.</li> <li>➤ Cable route clearance methods: mass flow excavation, dredging</li> </ul>                                                                                                                                                                                                                                            | Maximum potential for underwater noise impacts from pre-construction works. |

| POTENTIAL EFFECT            | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                      | JUSTIFICATION                                                                                                                                                                                                                                                                                                                                                                  |
|-----------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                             | <p>▲ Cable burial methods: jet-trenching, mechanical trenching, dredging, mass flow excavation, rock cutting</p> <p>Offshore construction indicative dates: Jan 2028-Mar 2030</p>                                                     |                                                                                                                                                                                                                                                                                                                                                                                |
| PTS from UXO                | Expected number of UXO requiring clearance: 10                                                                                                                                                                                        | Estimated maximum design. A detailed UXO survey will be completed prior to construction. The type, size (net explosive quantities (NEQ)) and number of possible detonations and duration of UXO clearance operations is not known at this stage. The Applicant is not seeking to license the disposal of UXO in this application, but it is included in the impact assessment. |
| Disturbance from UXO        | <p>Up to 2 clearance events every 24 hours</p> <p>Up to 10 detonations in 10 days</p> <p>MDS clearance method: high-order detonation (though low-order is more likely)</p> <p>Expected to occur prior to foundation installation.</p> |                                                                                                                                                                                                                                                                                                                                                                                |
| Collision risk from vessels | <p>Max total construction vessels: 101</p> <p>Indicative peak vessels on-site simultaneously: 35</p> <p>Offshore construction indicative dates: Jan 2028-Mar 2030</p>                                                                 | The maximum numbers of vessels and associated vessel movements represents the maximum potential for collision risk and disturbance.                                                                                                                                                                                                                                            |
| Disturbance from vessels    |                                                                                                                                                                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                |

| POTENTIAL EFFECT | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | JUSTIFICATION |
|------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
|                  | <p>Construction Vessels:</p> <ul style="list-style-type: none"> <li>▲ 4 Filter layer installation/seabed prep vessels</li> <li>▲ 2 Gravity base ballast installation vessels</li> <li>▲ 16 Foundation Installation Vessels</li> <li>▲ 6 Transition Piece Installation Vessels</li> <li>▲ 2 Scour Vessel</li> <li>▲ 15 WTG Installation Spread</li> <li>▲ 3 Commissioning Vessels</li> <li>▲ 12 inter array Cable Vessels</li> <li>▲ 12 Export Cable Vessels</li> <li>▲ 4 Substation Installation Vessels</li> <li>▲ 8 Substation Foundation Vessels</li> <li>▲ 15 Other Vessels</li> </ul> <p>Max round trips over 1.5 years:</p> <ul style="list-style-type: none"> <li>▲ Scour Layers Vessel x170</li> <li>▲ Gravity Base Foundation Ballast Vessel x315</li> </ul> |               |

| POTENTIAL EFFECT                       | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | JUSTIFICATION |
|----------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
|                                        | <ul style="list-style-type: none"> <li>Foundation Installation Spread x133</li> <li>Transition Piece Installation x24</li> <li>WTG Installation Spread x45</li> <li>Commissioning Vessels x78</li> <li>Accommodation vessels x52</li> <li>Inter array Cable Vessels x24</li> <li>Inter array Rock Berm Vessels x84</li> <li>Export Cable Vessels x23</li> <li>Export Cable Rock Berm Vessels x164</li> <li>Substation Installation Vessels Topside x8</li> <li>Substation Installation Vessels Foundation x16</li> <li>Other Vessels x2,300</li> </ul> |               |
| Change in water quality                | Maximum amount of suspended sediment released during construction activities and associated duration - see Volume 2, Chapter 2: Marine Geology, Oceanography and Physical Processes and Volume 2 Chapter 3: Marine Water and Sediment Quality.                                                                                                                                                                                                                                                                                                         |               |
| Change in fish abundance/ distribution | Assessment is based on the MDS presented in Volume 2, Chapter 6: Fish and Shellfish Ecology.                                                                                                                                                                                                                                                                                                                                                                                                                                                           |               |

| POTENTIAL EFFECT            | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | JUSTIFICATION                                                                                                                       |
|-----------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------|
| OPERATION                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                                                                                     |
| Collision risk from vessels | <p>Annual round trips:</p> <ul style="list-style-type: none"> <li>▲ Jack-up vessel: 6</li> <li>▲ Service operation vessel (SOV): 52</li> <li>▲ Small O&amp;M vessel (CTV): 1,095</li> <li>▲ Lift vessels: 6</li> <li>▲ Cable maintenance vessel: 1</li> <li>▲ Auxiliary vessel: 48</li> </ul> <p>Peak vessel quantities:</p> <ul style="list-style-type: none"> <li>▲ Jack-ups: 2</li> <li>▲ SOVs: 2</li> <li>▲ Small O&amp;M vessel (CTV): 6</li> <li>▲ Lift vessels: 2</li> <li>▲ Cable maintenance vessels: 2</li> <li>▲ Auxiliary vessels: 8</li> </ul> | The maximum numbers of vessels and associated vessel movements represents the maximum potential for collision risk and disturbance. |
| Disturbance from vessels    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                                                                                                                     |
| Barrier effects             | Maximum number of offshore structures: 50 WTG, 2 OSP, 1 met mast.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | The maximum numbers of offshore structures represent the maximum potential for a perceived barrier effect.                          |

| POTENTIAL EFFECT                          | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                                                                                                                                                     | JUSTIFICATION                                                                                                                       |
|-------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------|
| Change in water quality                   | Maximum amount of suspended sediment released during operation and associated duration - see Volume 2, Chapter 2: Marine Geology, Oceanography and Physical Processes and Volume 2 Chapter 3: Marine Water and Sediment Quality.                                                                                                                                                     |                                                                                                                                     |
| Change in fish abundance/<br>distribution | Assessment is based on the MDS presented in Volume 2, Chapter 6: Fish and Shellfish Ecology.                                                                                                                                                                                                                                                                                         |                                                                                                                                     |
| DECOMMISSIONING                           |                                                                                                                                                                                                                                                                                                                                                                                      |                                                                                                                                     |
| PTS and Disturbance                       | Maximum levels of underwater noise during decommissioning would be from underwater cutting required to remove structures. This is much less than pile driving and therefore impacts would be less than as assessed during the construction phase.<br><br>Piled solutions assumed to be cut off at or below seabed.<br><br>Three-year duration (offshore and onshore decommissioning) |                                                                                                                                     |
| Collision risk from vessels               | Assumed to be similar vessel types, numbers and movements to construction phase (or less).                                                                                                                                                                                                                                                                                           | The maximum numbers of vessels and associated vessel movements represents the maximum potential for collision risk and disturbance. |
| Disturbance from vessels                  |                                                                                                                                                                                                                                                                                                                                                                                      |                                                                                                                                     |



| POTENTIAL EFFECT                          | MAXIMUM ADVERSE SCENARIO ASSESSE                                                                                                                                                                                                                  | JUSTIFICATION |
|-------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------|
| Change in water quality                   | Maximum amount of suspended sediment released during decommissioning activities and associated duration - see Volume 2, Chapter 2: Marine Geology, Oceanography and Physical Processes and Volume 2 Chapter 3: Marine Water and Sediment Quality. |               |
| Change in fish abundance/<br>distribution | Assessment is based on the MDS presented in Volume 2, Chapter 6: Fish and Shellfish Ecology.                                                                                                                                                      |               |
| CUMULATIVE EFFECTS                        |                                                                                                                                                                                                                                                   |               |
| See Table 48.                             |                                                                                                                                                                                                                                                   |               |

## 7.9 Mitigation measures

122 Mitigation measures that were identified and have been adopted as part of the evolution of the project design (embedded into the project design) and that are relevant to marine mammals are listed in Table 19. The mitigation includes embedded measures such as design changes and applied mitigation which is subject to further study or approval of details; these include avoidance measures that will be informed by pre-construction surveys, and necessary additional consents where relevant. The composite of embedded and applied mitigation measures apply to all parts of the AyM development works, including pre-construction, construction, O&M and decommissioning.

Table 19: Mitigation measures relating to marine mammals.

| PARAMETER               | MITIGATION MEASURES                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|-------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| GENERAL                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
| Pollution prevention    | A Project Environment Management Plan (PEMP) is proposed to be produced to ensure that the potential for contaminant release is strictly controlled. The PEMP will include a Marine Pollution Contingency Plan (MPCP) and will also incorporate plans to cover accidental spills, potential contaminant release and include key emergency contact details (e.g. NRW, Maritime Coastguard Agency and the project site co-ordinator). The PEMP will be secured as a condition in the Marine Licence. |
| Vessel codes of conduct | The adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme, Scottish Marine Wildlife Watching Code or Guide to Best Practice for Watching Marine Wildlife) will minimise the potential for any impact. The final codes of conduct will be discussed and agreed with NRW and JNCC.                                                                                                                                                    |
| CONSTRUCTION            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |

| PARAMETER                                           | MITIGATION MEASURES                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|-----------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Project design                                      | <p>Inclusion of soft-start and ramp up procedures for pile driving.</p> <p>In the case of monopiles, piling will only occur at one location at a time. There is no possibility of simultaneous or concurrent piling. In the case of pin-piled multi-leg jacket foundations, pin-piles may be installed concurrently, but only on adjacent legs of the same jacket foundation. There is no possibility of simultaneous or concurrent piling at two separate foundation locations.</p>   |
| Marine Mammal Mitigation Protocol (Piling specific) | A piling Marine Mammal Mitigation Protocol will be implemented as a condition in the Marine Licence (see Volume 4, Annex 7.2: Draft Outline MMMP). The MMMP will be secured as a condition within the Marine Licence.                                                                                                                                                                                                                                                                  |
| Marine Mammal Mitigation Protocol (UXO specific).   | Implementation of a UXO Marine Mammal Mitigation Protocol subject to a separate Marine License application should UXO clearance be required.                                                                                                                                                                                                                                                                                                                                           |
| OPERATION                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| None                                                | NA                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |
| DECOMMISSIONING                                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
| Decommissioning Plan                                | A Decommissioning Programme will be developed to cover the decommissioning phase as required under Chapter 3 of the Energy Act 2004. As the decommissioning phase will be a similar process to the construction phase but in reverse (i.e., increased project vessels on-site, partially deconstructed structures) the embedded mitigation measure will be similar to those for the construction phase. The Decommissioning Plan will be secured as a condition in the Marine Licence. |

| PARAMETER                                           | MITIGATION MEASURES                                                                                                                                                      |
|-----------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Marine Mammal Mitigation Protocol (Decommissioning) | Implementation of a decommissioning Marine Mammal Mitigation Protocol subject to a separate Marine License application prior to decommissioning should this be required. |

## 7.10 Environmental assessment: construction phase

123 The potential environmental impacts arising from the construction of AyM are listed in Table 18 along with the MDS against which each construction phase impact has been assessed. A description of the potential effect on marine mammal ecology receptors caused by each identified impact is given below.

### 7.10.1 PTS from piling

124 The assessment below focuses on underwater noise from pile-driving (monopiles and pin piles) for the installation of foundations for offshore structures.

### Harbour porpoise

125 Table 20 presents the PTS-onset impact area, impact range and number of porpoise within the PTS-onset impact area. The instantaneous PTS-onset impact ranges are low (maximum 1.3 km) which equates to less than a single harbour porpoise using the JCP density estimate. For the onset of cumulative PTS, the maximum predicted impact is predicted to occur when two pin piles are installed simultaneously at the NW location, resulting in a cumulative PTS-onset range of 6.3 km, equating to 11 harbour porpoise using the JCP Tool and 83 porpoise using the SWF density estimate (averaged density estimate presented in Evans et al. (2021))<sup>iv</sup>.

<sup>iv</sup> Please see Volume 4: Annex 7.1: Marine Mammal Baseline Characterisation for details as to why this estimate is considered to be highly precautionary.

- 126 As stated in Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, Limitations and Uncertainties, these predictions assume that all animals within the PTS-onset range are impacted, which will overestimate the true number of impacted animals as only 18-19% of the animals are predicted to actually experience PTS at the PTS-onset threshold level. In addition, as stated in Volume 4, Annex 7.3, the sound is modelled as being fully impulsive irrespective of distance from the pile, which is highly precautionary and results in predictions that are unlikely to be realised (e.g. it is unlikely that the sound will be fully impulsive at >6 km from the pile). Finally, Volume 4, Annex 7.3 outlines the over-precautions built into the calculation of cumulative PTS impact, and how the resulting impact ranges are considered to be highly over-precautionary and unrealistic.
- 127 Despite the precautions inherent in the modelling, the numbers of individual harbour porpoise predicted to be at risk of PTS are low. It is also likely that the presence of vessels and associated construction activity will ensure that the vicinity of the pile is free of harbour porpoise by the time that piling begins. In the absence of any mitigation, given the very low number of animals potentially impacted, the magnitude of this impact (in the absence of any mitigation) is **negligible**, as there is not expected to be any change to the population size or trajectory.
- 128 As outlined in section 7.5.1: Sensitivity to PTS, harbour porpoise have been assessed as having a **Low** sensitivity to PTS-onset from pile driving.
- 129 The magnitude of the impact (in the absence of any mitigation) has been assessed as **negligible** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of PTS-onset from unmitigated pile driving for harbour porpoise is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

Table 20: Impact area, maximum range, number of harbour porpoise predicted to experience PTS-onset from piling.

| PILE TYPE                                                                                        | MONOPILE<br>(5,000 KJ) |      | MULTILEG<br>(3,000 KJ) |      | MULTILEG<br>2 AT 1<br>LOCATION |     |
|--------------------------------------------------------------------------------------------------|------------------------|------|------------------------|------|--------------------------------|-----|
| MODELLING LOCATION                                                                               | NW                     | SE   | NW                     | SE   | NW                             | SE  |
| INSTANTANEOUS PTS: 202 DB UNWEIGHTED SPL <sub>PEAK</sub>                                         |                        |      |                        |      |                                |     |
| Area (km <sup>2</sup> )                                                                          | 1.3                    | 0.7  | 0.9                    | 0.5  | NA                             | NA  |
| Max range (km)                                                                                   | 0.64                   | 0.50 | 0.54                   | 0.42 |                                |     |
| # Porpoise (JCP 0.13/km <sup>2</sup> )                                                           | <1                     | <1   | <1                     | <1   |                                |     |
| # Porpoise (SWF 1.0/km <sup>2</sup> )                                                            | 1                      | <1   | <1                     | <1   |                                |     |
| CUMULATIVE PTS: 155 DB VHF WEIGHTED SEL <sub>CUM</sub> (2 MONOPILES OR 4<br>PIN-PILES IN 24 HRS) |                        |      |                        |      |                                |     |
| Area (km <sup>2</sup> )                                                                          | 48                     | 13   | 28                     | 5.8  | 83                             | 25  |
| Max range (km)                                                                                   | 4.7                    | 2.9  | 3.6                    | 2.0  | 6.3                            | 4.0 |
| # Porpoise (JCP 0.13/km <sup>2</sup> )                                                           | 6                      | 2    | 4                      | 1    | 11                             | 3   |
| # Porpoise (SWF 1.0/km <sup>2</sup> )                                                            | 48                     | 13   | 28                     | 6    | 83                             | 25  |

## Bottlenose, common and Risso's dolphin

130 Table 21 presents the PTS-onset impact area and impact range for bottlenose, common and Risso's dolphins. Both the instantaneous and cumulative PTS-onset ranges are very small for all scenarios (<50 m and <100 m respectively) which results in <1 individual predicted to be impacted. Therefore, the impact of PTS-onset from piling for bottlenose, common and Risso's dolphins is assessed as having a **negligible** adverse magnitude given the negligible impact ranges.

131 As outlined in section 7.5.1: Sensitivity to PTS, bottlenose, common and Risso's dolphins have been assessed as having a **medium** sensitivity to PTS-onset from pile driving.



132 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **medium**. Therefore, the significance of the effect of PTS-onset from unmitigated pile driving for bottlenose, common and Risso's dolphins is concluded to be of **medium adverse significance**, which is not significant in terms of the EIA regulations.

Table 21: Impact area and maximum range for bottlenose, common and Risso's dolphins predicted to experience PTS-onset from piling.

| PILE TYPE                                                                                        | MONOPILE<br>(5,000 KJ) |        | MULTILEG<br>(3,000 KJ) |       | MULTILEG 2 AT<br>1 LOCATION |      |
|--------------------------------------------------------------------------------------------------|------------------------|--------|------------------------|-------|-----------------------------|------|
| MODELLING LOCATION                                                                               | NW                     | SE     | NW                     | SE    | NW                          | SE   |
| INSTANTANEOUS PTS: 230 DB UNWEIGHTED SPL <sub>PEAK</sub>                                         |                        |        |                        |       |                             |      |
| Area (km <sup>2</sup> )                                                                          | <0.1                   | <0.1   | <0.1                   | <0.1  | NA                          | NA   |
| Max range (km)                                                                                   | <0.05                  | <0. 05 | <0.05                  | <0.05 |                             |      |
| CUMULATIVE PTS: 185 DB VHF WEIGHTED SEL <sub>CUM</sub> (2 MONOPILES OR 4<br>PIN-PILES IN 24 HRS) |                        |        |                        |       |                             |      |
| Area (km <sup>2</sup> )                                                                          | <0.1                   | <0.1   | <0.1                   | <0.1  | <0.1                        | <0.1 |
| Max range (km)                                                                                   | <0.1                   | <0.1   | <0.1                   | <0.1  | <0.1                        | <0.1 |

## Minke whale

133 Table 22 presents the PTS-onset impact area, impact range and number of minke whales within the PTS-onset impact area. The instantaneous PTS-onset impact ranges are very low (50 m) across all scenarios. For the onset of cumulative PTS, the maximum predicted impact is for the simultaneous installation of two pin piles at the NW location, where impact ranges reach 10 km, however, given the low densities of minke whales predicted at the site, this equates to only three whales using the SCANS III density estimate.

- 134 As stated in Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, Limitations and Uncertainties, these predictions assume that all animals within the PTS-onset range are impacted, which will overestimate the true number of impacted animals as only 18-19% of the animals are predicted to actually experience PTS at the PTS-onset threshold level. In addition, as stated in Volume 4, Annex 7.3, the sound is modelled as being fully impulsive irrespective of distance from the pile, which is highly precautionary and results in predictions that are unlikely to be realised (e.g. it is highly unlikely that the sound will be fully impulsive at 10 km from the pile). Finally, Volume 4, Annex 7.3, outlines the over-precautions built into the calculation of cumulative PTS impact, and how the resulting impact ranges are considered to be highly over-precautionary and unrealistic.
- 135 Despite the precautions inherent in the modelling, the numbers of individual minke whales predicted to be at risk of PTS are very low (maximum three per piling day). In the absence of any mitigation, given the very low number of animals potentially impacted, the magnitude of this impact is **negligible**, as there is not expected to be any change to the population size or trajectory.
- 136 As outlined in section 7.5.1: Sensitivity to PTS, minke whales have been assessed as having a **low** sensitivity to PTS-onset from pile driving.
- 137 The magnitude of the impact (in the absence of mitigation) has been assessed as **negligible** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of PTS-onset from pile driving for minke whales is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

Table 22: Impact area, maximum range and number of minke whales predicted to experience PTS-onset from piling.

| PILE TYPE                                                                                        | MONOPILE<br>(5,000 KJ) |      | MULTILEG<br>(3,000 KJ) |      | MULTILEG 2 AT 1<br>LOCATION |     |
|--------------------------------------------------------------------------------------------------|------------------------|------|------------------------|------|-----------------------------|-----|
| MODELLING<br>LOCATION                                                                            | NW                     | SE   | NW                     | SE   | NW                          | SE  |
| INSTANTANEOUS PTS: 219 DB UNWEIGHTED SPL <sub>PEAK</sub>                                         |                        |      |                        |      |                             |     |
| Area (km <sup>2</sup> )                                                                          | <0.1                   | <0.1 | <0.1                   | <0.1 | NA                          | NA  |
| Max range (km)                                                                                   | 0.06                   | 0.05 | 0.05                   | 0.05 |                             |     |
| # whales                                                                                         | <1                     | <1   | <1                     | <1   |                             |     |
| CUMULATIVE PTS: 183 DB VHF WEIGHTED SEL <sub>CUM</sub> (2 MONOPILES OR 4<br>PIN-PILES IN 24 HRS) |                        |      |                        |      |                             |     |
| Area (km <sup>2</sup> )                                                                          | 120                    | 19   | 70                     | 5.9  | 170                         | 29  |
| Max range (km)                                                                                   | 8.5                    | 4.2  | 6.5                    | 2.6  | 10.0                        | 5.5 |
| # whales                                                                                         | 2                      | <1   | 1                      | <1   | 3                           | <1  |

## Grey seal

138 Table 23 presents the PTS-onset impact area and impact range for grey seals. Both the instantaneous and cumulative PTS-onset ranges are very small for all scenarios (60 m and <100 m respectively) which results in <1 individual predicted to be impacted. Therefore, the impact of PTS-onset from piling for grey seals is assessed as having a **negligible** adverse magnitude given the negligible impact ranges in addition to the embedded mitigation of a MMMP.

139 As outlined in section 7.5.1, grey seals have been assessed as having a **low** sensitivity to PTS-onset from pile driving.

140 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of PTS-onset from pile driving for grey seals is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

Table 23: Impact area, maximum range and number of grey seals predicted to experience PTS-onset from piling.

| PILE TYPE                                                                                        | MONOPILE<br>(5,000 KJ) |       | MULTILEG<br>(3,000 KJ) |       | MULTILEG 2 AT 1<br>LOCATION |       |
|--------------------------------------------------------------------------------------------------|------------------------|-------|------------------------|-------|-----------------------------|-------|
| MODELLING<br>LOCATION                                                                            | NW                     | SE    | NW                     | SE    | NW                          | SE    |
| INSTANTANEOUS PTS: 219 DB UNWEIGHTED SPL <sub>PEAK</sub>                                         |                        |       |                        |       |                             |       |
| Area (km²)                                                                                       | <0.1                   | <0.1  | <0.1                   | <0.1  | NA                          | NA    |
| Max range (km)                                                                                   | 0.07                   | 0.06  | 0.06                   | 0.06  |                             |       |
| # seals                                                                                          | <1                     | <1    | <1                     | <1    |                             |       |
| CUMULATIVE PTS: 183 DB VHF WEIGHTED SEL <sub>CUM</sub> (2 MONOPILES OR 4<br>PIN-PILES IN 24 HRS) |                        |       |                        |       |                             |       |
| Area (km²)                                                                                       | <0.1                   | <0.1  | <0.1                   | <0.1  | <0.1                        | <0.1  |
| Max range (km)                                                                                   | <0.01                  | <0.01 | <0.01                  | <0.01 | <0.01                       | <0.01 |
| # seals                                                                                          | <1                     | <1    | <1                     | <1    | <1                          | <1    |

## Cofferdam sheet piles

141 Table 24 presents the PTS-onset impact area and maximum impact range for all species. For all marine mammal species, both the instantaneous and cumulative PTS-onset ranges are very small (<100 m). Therefore, the impact of PTS-onset from piling of sheet piles for all marine mammal species is assessed as having a **negligible** adverse magnitude given the negligible impact ranges.

Table 24: Impact area and maximum range for PTS-onset from piling of cofferdam sheet piles.

| SPECIES                               |                         | INSTANTANEOUS PTS (8 SHEETS IN 24 HRS) |                 | CUMULATIVE PTS (8 SHEETS IN 24 HRS) |                 |
|---------------------------------------|-------------------------|----------------------------------------|-----------------|-------------------------------------|-----------------|
|                                       |                         | 8.0 M ABOVE LAT                        | 0.6 M ABOVE LAT | 8.0 M ABOVE LAT                     | 0.6 M ABOVE LAT |
| Harbour porpoise                      | Area (km <sup>2</sup> ) | <0.01                                  | <0.01           | <0.01                               | <0.01           |
|                                       | Max range (km)          | <0.05                                  | <0.05           | <0.1                                | <0.1            |
| Bottlenose, common & Risso's dolphins | Area (km <sup>2</sup> ) | <0.01                                  | <0.01           | <0.01                               | <0.01           |
|                                       | Max range (km)          | <0.05                                  | <0.05           | <0.1                                | <0.1            |
| Minke whale                           | Area (km <sup>2</sup> ) | <0.01                                  | <0.01           | <0.01                               | <0.01           |
|                                       | Max range (km)          | <0.05                                  | <0.05           | <0.1                                | <0.1            |
| Grey seal                             | Area (km <sup>2</sup> ) | <0.01                                  | <0.01           | <0.01                               | <0.01           |
|                                       | Max range (km)          | <0.05                                  | <0.05           | <0.1                                | <0.1            |

## PTS summary

142 The impact of PTS-onset from piling noise under the maximum design scenario is not considered to have a significant effect on any marine mammal species considered in this assessment (Table 25).

Table 25: Summary of the assessment for PTS-onset from pile driving for each marine mammal species.

| SPECIES            | MAGNITUDE          | SENSITIVITY | SIGNIFICANCE                    |
|--------------------|--------------------|-------------|---------------------------------|
| Harbour porpoise   | Negligible adverse | Low         | Negligible adverse significance |
| Bottlenose dolphin | Negligible adverse | Medium      | Minor adverse significance      |
| Common dolphin     | Negligible adverse | Medium      | Minor adverse significance      |
| Risso's dolphin    | Negligible adverse | Medium      | Minor adverse significance      |
| Minke whale        | Negligible adverse | Low         | Negligible adverse significance |
| Grey seal          | Negligible adverse | Low         | Negligible adverse significance |

### 7.10.2 TTS from piling

143 Full details of the underwater noise modelling and the resulting TTS-onset impact areas and ranges are detailed in Volume 4, Annex 6.2: Subsea Noise Technical Report. As outlined in Section 7.4.3: TTS Assessment there are no thresholds to determine a biologically significant effect from TTS-onset, therefore the predicted ranges and area for the onset of TTS are presented in Table 26, but no assessment of the number of animals, magnitude, sensitivity or significance of effect is given. This approach was agreed with members of Marine Mammals & Marine Ecology Expert Topic Group (21st September 2020) and follows the advice provided in the Scoping Opinion (The Planning Inspectorate, July 2020).



Table 26: TTS-onset impact area (km<sup>2</sup>) and maximum range (km) for each marine mammal hearing group.

| THRESHOLD                                                                               |     |       | MONOPILE (5,000 KJ) |       | MULTILEG (3,000 KJ) |       | MULTILEG 2 AT 1 LOCATION |
|-----------------------------------------------------------------------------------------|-----|-------|---------------------|-------|---------------------|-------|--------------------------|
|                                                                                         |     |       | NW                  | SE    | NW                  | SE    | NW                       |
| INSTANTANEOUS TTS: SPL <sub>PEAK</sub> DB RE 1μPA                                       |     |       |                     |       |                     |       |                          |
| VHF                                                                                     | 196 | Area  | 6.9                 | 3.7   | 5                   | 2.6   | NA                       |
|                                                                                         |     | Range | 1.5                 | 1.1   | 1.3                 | 0.94  |                          |
| HF                                                                                      | 230 | Area  | <0.01               | <0.01 | <0.01               | <0.01 |                          |
|                                                                                         |     | Range | <0.05               | <0.05 | <0.05               | <0.05 |                          |
| LF                                                                                      | 219 | Area  | 0.05                | 0.03  | 0.03                | 0.02  |                          |
|                                                                                         |     | Range | 0.13                | 0.11  | 0.05                | 0.09  |                          |
| PW                                                                                      | 212 | Area  | 0.07                | 0.04  | 0.05                | 0.03  |                          |
|                                                                                         |     | Range | 0.15                | 0.13  | 0.13                | 0.11  |                          |
| CUMULATIVE TTS: SEL <sub>CUM</sub> DB RE 1μPA <sup>2</sup> S (2X MONOPILE, 4X MULTILEG) |     |       |                     |       |                     |       |                          |
| VHF                                                                                     | 140 | Area  | 960                 | 470   | 820                 | 390   | 1200                     |
|                                                                                         |     | Range | 23                  | 19    | 21                  | 17    | 26                       |
| HF                                                                                      | 170 | Area  | <0.1                | <0.1  | <0.1                | <0.1  | <0.1                     |
|                                                                                         |     | Range | <0.1                | <0.1  | <0.1                | <0.1  | <0.1                     |
| LF                                                                                      | 168 | Area  | 1400                | 59    | 1100                | 460   | 1500                     |
|                                                                                         |     | Range | 30                  | 23    | 27                  | 20    | 33                       |
| PW                                                                                      | 170 | Area  | 210                 | 60    | 170                 | 44    | 330                      |
|                                                                                         |     | Range | 10                  | 6.3   | 9.2                 | 5.5   | 13                       |

Table 27: Impact area and maximum range for TTS-onset from piling of cofferdam sheet piles.

| SPECIES                               |                         | INSTANTANEOUS TTS |                 | CUMULATIVE TTS (8 SHEETS IN 24 HRS) |                 |
|---------------------------------------|-------------------------|-------------------|-----------------|-------------------------------------|-----------------|
|                                       |                         | 8.0 M ABOVE LAT   | 0.6 M ABOVE LAT | 8.0 M ABOVE LAT                     | 0.6 M ABOVE LAT |
| Harbour porpoise                      | Area (km <sup>2</sup> ) | 0.02              | <0.01           | 0.4                                 | <0.01           |
|                                       | Max range (km)          | 0.7               | <0.05           | 480                                 | <0.1            |
| Bottlenose, common & Risso's dolphins | Area (km <sup>2</sup> ) | <0.01             | <0.01           | <0.01                               | <0.01           |
|                                       | Max range (km)          | <0.05             | <0.05           | <0.1                                | <0.1            |
| Minke whale                           | Area (km <sup>2</sup> ) | <0.01             | <0.01           | 0.1                                 | <0.01           |
|                                       | Max range (km)          | <0.05             | <0.05           | 210                                 | <0.1            |
| Grey seal                             | Area (km <sup>2</sup> ) | <0.01             | <0.01           | <0.01                               | <0.01           |
|                                       | Max range (km)          | <0.05             | <0.05           | <0.1                                | <0.1            |

### 7.10.3 Disturbance from piling

#### Harbour porpoise

144 The method used to calculate the number of porpoise predicted to experience behavioural disturbance is shown in Table 29 for the installation of a monopile at the NW location, using the JCP density estimate and the Graham et al. (2017) dose-response curve.

- 145 Using the JCP density estimate, for all scenarios modelled, the number of harbour porpoise predicted to experience behavioural disturbance is low (<0.5% of the MU). The scenario with the maximum level of disturbance is the installation of a monopile foundation at the NW modelling location, which results in a predicted 275 porpoise experiencing disturbance on each day of pile driving activities using the JCP density estimate (0.13 porpoise/km<sup>2</sup>).
- 146 Given the results of the expert elicitation on the likely effects of behavioural disturbance on harbour porpoise vital rates (Booth et al. 2019) (see section 7.5.2), an absolute worst case maximum of 201 days of piling is unlikely to cause any effect on fertility rates, although there is the potential for calf survival to be affected. However, it is highly unlikely that the same mother-calf pair would repeatedly return to the area in order to receive these levels of repeated disturbance over this many days. Any potential impact on calf survival rates is likely to be temporary and is not expected to result in any changes in the population trajectory or overall size. The impact is predicted to be of local spatial extent, short term duration, intermittent and is reversible.
- 147 Using the JCP density estimate, the low number of porpoise predicted to be impacted and the low proportion of the population this represents, results in a **low** adverse magnitude, where short-term and/or intermittent and temporary behavioural effects are expected in a small proportion of the population, and any impact to vital rates of individuals occur only in the short term (over a limited number of breeding cycles, <1 in this case) and where any changes to individual vital rates are very unlikely to occur to the extent that the population trajectory would be altered.

- 148 Using the SWF density estimate (1.0 porpoise/km<sup>2</sup>, averaged across the coastal and offshore areas), the number of harbour porpoise predicted to experience behavioural disturbance is higher. The maximum level of disturbance results from a monopile foundation at the NW modelling location, which results in a predicted 2,112 porpoise experiencing disturbance on each day of pile driving activities (3.38% MU)<sup>v</sup>. Using the SWF density estimate, the number of porpoise predicted to be impacted and the proportion of the population this represents, results in a precautionary **medium** adverse magnitude, where any changes to individual vital rates are very unlikely to affect the population trajectory over a generational scale.
- 149 As outlined in section 7.5.2, disturbance as result of pile driving may temporarily affect harbour porpoise fertility and the probability of calf survival. Due to observed responsiveness to piling, and their income breeder life history, harbour porpoise are considered to have a **low** sensitivity to disturbance from pile driving.
- 150 The magnitude of the impact has been assessed as **low** adverse (using the JCP density estimate) or **medium** (using the SWF density estimate) and the sensitivity of receptor as **low**. Therefore, the significance of the effect of disturbance from pile driving on harbour porpoise is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

**Table 28: Number of harbour porpoise and percentage of the MU predicted to experience potential behavioural disturbance from piling.**



| PILE TYPE                                      | MONOPILE (5,000 KJ) |       |         | MULTILEG (3,000 KJ) |       |         |
|------------------------------------------------|---------------------|-------|---------|---------------------|-------|---------|
| MODELLING LOCATION                             | NW                  | SE    | NW & SE | NW                  | SE    | NW & SE |
| JCP DATA TOOL (0.13 PORPOISE/KM <sup>2</sup> ) |                     |       |         |                     |       |         |
| # porpoise                                     | 275                 | 158   | NA      | 244                 | 136   | NA      |
| % MU                                           | 0.44%               | 0.25% |         | 0.39%               | 0.22% |         |

<sup>v</sup> Please see Volume 4: Annex 7.1: Marine Mammal Baseline Characterisation for details as to why this estimate is considered to be highly precautionary.

| PILE TYPE                                             | MONOPILE (5,000 KJ) |       |    | MULTILEG (3,000 KJ) |       |    |
|-------------------------------------------------------|---------------------|-------|----|---------------------|-------|----|
| SWF AVERAGED ESTIMATE (1.0 PORPOISE/KM <sup>2</sup> ) |                     |       |    |                     |       |    |
| # porpoise                                            | 2,112               | 1,217 | NA | 1,878               | 1,048 | NA |
| % MU                                                  | 3.38%               | 1.95% |    | 3.00%               | 1.68% |    |

Table 29: Calculation of the number of harbour porpoise predicted to experience behavioural disturbance for the installation of a monopile at the NW location, using the JCP III density estimate and the Graham et al. (2017a) dose-response curve.

| RECEIVED LEVEL (SEL <sub>SS</sub> [RE 1 μPA <sup>2</sup> S]) | AREA (KM <sup>2</sup> ) | # PORPOISE (JCP III DENSITY) | % PORPOISE PREDICTED TO RESPOND | # PORPOISE PREDICTED TO RESPOND |
|--------------------------------------------------------------|-------------------------|------------------------------|---------------------------------|---------------------------------|
| 180+                                                         | 4.3                     | 0.6                          | 99.9                            | 0.6                             |
| 175<180                                                      | 12.8                    | 1.7                          | 99.7                            | 1.7                             |
| 170<175                                                      | 40.3                    | 5.2                          | 99.0                            | 5.2                             |
| 165<170                                                      | 106.7                   | 13.9                         | 96.8                            | 13.4                            |
| 160<165                                                      | 223.2                   | 29.0                         | 91.9                            | 26.7                            |
| 155<160                                                      | 379.1                   | 49.3                         | 82.7                            | 40.7                            |
| 150<155                                                      | 550.9                   | 71.6                         | 68.5                            | 49.1                            |
| 145<150                                                      | 732.0                   | 95.2                         | 50.9                            | 48.4                            |
| 140<145                                                      | 902.8                   | 117.4                        | 33.1                            | 38.9                            |
| 135<140                                                      | 1079.1                  | 140.3                        | 18.5                            | 26.0                            |
| 130<135                                                      | 1293.3                  | 168.1                        | 8.8                             | 14.8                            |
| 125<130                                                      | 1462.7                  | 190.1                        | 3.5                             | 6.6                             |
| 120<125                                                      | 1737.4                  | 225.9                        | 1.2                             | 2.6                             |
| TOTAL NUMBER OF HARBOUR PORPOISE IMPACTED                    |                         |                              |                                 | 275                             |



**LEGEND**

- Order Limits
- Array Area

**NW Monopile Disturbance Dose-Response Contours**

- 120 SELss dB re 1 µPa²s
- 125 SELss dB re 1 µPa²s
- 130 SELss dB re 1 µPa²s
- 135 SELss dB re 1 µPa²s
- 140 SELss dB re 1 µPa²s
- 145 SELss dB re 1 µPa²s
- 150 SELss dB re 1 µPa²s
- 155 SELss dB re 1 µPa²s
- 160 SELss dB re 1 µPa²s
- 165 SELss dB re 1 µPa²s
- 170 SELss dB re 1 µPa²s
- 175 SELss dB re 1 µPa²s
- 180 SELss dB re 1 µPa²s

Data Source:  
Subacoustech Environmental Ltd

**PROJECT TITLE:**

*AWEL Y MÔR OFFSHORE WINDFARM*

**FIGURE TITLE:**


**Harbour Porpoise  
Disturbance Contours**

| VER | DATE       | REMARKS   | Drawn | Checked |
|-----|------------|-----------|-------|---------|
| 1   | 10/03/2022 | For Issue | RRS   | RM      |
|     |            |           |       |         |

**FIGURE NUMBER:**

**Figure 18**

|        |           |            |    |        |       |             |        |
|--------|-----------|------------|----|--------|-------|-------------|--------|
| SCALE: | 1:500,000 | PLOT SIZE: | A3 | DATUM: | WGS84 | PROJECTION: | UTM30N |
|--------|-----------|------------|----|--------|-------|-------------|--------|



Esri, Garmin, GEBCO, NOAA NGDC, and other contributors




## Bottlenose dolphin

151 Table 30 outlines the number of bottlenose dolphins predicted to be disturbed by pile driving at both the NW and SE locations for both monopiles and multi-leg jacket foundations. Most of the area covered by the impact contours are located in offshore waters beyond the 20 m depth contour, where bottlenose dolphin density is expected to be low (Figure 19). This results in fairly low numbers of dolphins predicted to be disturbed on each piling day (up to 23 individuals which represents 7.9% of the MU).

**Table 30: Number of bottlenose dolphins and percentage of the MU predicted to experience potential behavioural disturbance from piling.**

|            | MONOPILE (5,000 KJ) |      |         | MULTILEG (3,000 KJ) |      |         |
|------------|---------------------|------|---------|---------------------|------|---------|
|            | NW                  | SE   | NW & SE | NW                  | SE   | NW & SE |
| # dolphins | 23                  | 16   | NA      | 20                  | 14   | NA      |
| % MU       | 7.9%                | 5.5% |         | 6.8%                | 4.8% |         |



- 152 In order to assess whether the predicted level of disturbance would be sufficient to cause a population level effect, the interim PCoD model (version 5.2) was run<sup>vi</sup>. Conservative input values were used in the model, such that 23 bottlenose dolphins were predicted to be disturbed on every piling day. The model assumed the worst-case scenario where it could take up to three days to install one monopile, equating to 201 piling days. An indicative piling schedule was not available for use, and therefore the piling days were randomly spread throughout the 12-month construction period.
- 153 The results of the modelling showed that there was some predicted impact on the MU population as a result of the piling activity at AyM (Table 31 and Figure 20). The median ratio of the impacted:un-impacted population size after 6 years of simulation (1 year of impact followed by 5 years with no impact) was 1 and the impacted mean population size after 6 years of simulation (1 year of impact followed by 5 years with no impact) was only 5 individuals smaller than the un-impacted mean population size (such that the impacted population size is expected to be 98.3% of the un-impacted population size). The population size remained the same after 12 years of simulation (1 year of impact followed by 11 years with no impact) and thus the population trajectory of both the impacted and un-impacted populations are expected to be stable in the long term.

**Table 31 Bottlenose dolphin population modelling inputs and results**

| PARAMETERS INPUT INTO IPCOD                 |            |      |
|---------------------------------------------|------------|------|
| Number of simulations run                   | nboot      | 1000 |
| Species                                     | spec       | BND  |
| Proportion of population that is female     | propfemale | 0.5  |
| Population size at the start of simulations | pmean      | 293  |
| Calf survival rate                          | Surv[1]    | 0.86 |
| Juvenile survival rate                      | Surv[7]    | 0.94 |

<sup>vi</sup> <http://www.smruconsulting.com/products-tools/pcod/ipcod/>

## PARAMETERS INPUT INTO IPCOD

|                                                                              |                |          |
|------------------------------------------------------------------------------|----------------|----------|
| Adult survival rate                                                          | Surv[13]       | 0.94     |
| Fecundity rate                                                               | Fertility      | 0.25     |
| Age at independence                                                          | age1           | 2        |
| Age at first birth                                                           | age2           | 9        |
| Number of piling years                                                       | pile_years     | 1        |
| Proportion of animals in vulnerable component                                | vulnmean       | c(1.0)   |
| Days of "residual" disturbance                                               | days           | 0        |
| Proportion of disturbed experiencing "days"                                  | prop_days_dist | 1        |
| Number of piling Operations                                                  | pilesx1        | 1        |
| Seasonal variation (1=no variation)                                          | seasons        | 1        |
| Number of animals predicted to experience disturbance during 1 day of piling | numDt[1,]      | 23       |
| Years for simulation                                                         | years          | 25       |
| Density dependence (0=no density dependence)                                 | z              | 0        |
| Piling schedule                                                              |                | 201 days |

## RESULTS

|                                                            |       |
|------------------------------------------------------------|-------|
| Un-impacted pop mean (after 1 year)                        | 292   |
| Impacted pop mean (after 1 year)                           | 289   |
| Impacted pop as % of un-impacted pop (after 1 year)        | 99.0% |
| Median impacted:un-impacted population size (after 1 year) | 1     |

## PARAMETERS INPUT INTO IPCOD

|                                                              |       |
|--------------------------------------------------------------|-------|
| Un-impacted pop mean (after 6 years)                         | 292   |
| Impacted pop mean (after 6 years)                            | 287   |
| Impacted pop as % of un-impacted pop (after 6 years)         | 98.3% |
| Median impacted:un-impacted population size (after 6 years)  | 1     |
| Un-impacted pop mean (after 12 years)                        | 293   |
| Impacted pop mean (after 12 years)                           | 288   |
| Impacted pop as % of un-impacted pop (after 12 years)        | 98.3% |
| Median impacted:un-impacted population size (after 12 years) | 1     |




Figure 20: Population trajectory for both the impacted and un-impacted bottlenose dolphin population resulting from 201 days of piling disturbance.

154 The impact is predicted to be of local spatial extent, short term duration (limited to a one-year construction window), intermittent and is reversible. However, given the number of dolphins predicted to be impacted and the proportion of the population this represents, this is conservatively considered to be a **medium** adverse magnitude, where temporary changes in behaviour and/or distribution of individuals could result in potential reductions to lifetime reproductive success to some individuals although not enough to affect the population trajectory over a generational scale (as demonstrated by the population modelling).



- 155 As outlined in section 7.5.3, disturbance as result of pile driving may result in small spatial and temporal scale disturbance to bottlenose dolphins, however direct evidence for this species is generally lacking. There is evidence that pile driving can result in temporary displacement of bottlenose dolphins, but that this displacement may be limited to small temporal and spatial scales. While there remains the potential for disturbance and displacement to affect individual behaviour and in particular calf survival rates, bottlenose dolphins do have some capability to adapt their behaviour and tolerate certain levels of temporary disturbance. Therefore, bottlenose dolphins are considered to have a **low** sensitivity to disturbance from pile driving.
- 156 The magnitude of the impact has been assessed as **medium** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of disturbance from pile driving on bottlenose dolphins is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

## Common dolphin

- 157 Table 32 outlines the number of common dolphins predicted to be disturbed by pile driving at both the NW and SE locations for both monopiles and multi-leg jacket foundations. The scenario with the maximum level of disturbance is the installation of a monopile foundation at the NW modelling location, which results in a predicted 17 common dolphins (0.02% MU) experiencing disturbance on each day of pile driving activities using the JCP density estimate.
- 158 The movement patterns of common dolphins in UK waters are poorly understood, and as such, it is not known how much repeated disturbance an individual dolphin would be expected to receive. Common dolphins are generally thought to be wide-ranging, capable of travelling large distances, based on tag and genetic data (e.g. Evans 1982, Natoli et al. 2006, Genov et al. 2012). This would suggest that it is more likely that the turn-over of common dolphins in the area is high and that each dolphin would be unlikely to be subjected to multiple repeated days of disturbance. Based on the current evidence on the effects of disturbance on dolphin species, it is not expected that exposure to a single day/low number of days of pile driving would result in any changes to vital rates.

- 159 Therefore the worst-case scenario would consist of the same animals being repeatedly exposed, thus increasing the potential for the repeated disturbance to result in changes to vital rates. However, given the low proportion of the MU predicted to be impacted repeatedly, and the short-term duration of the impact (limited to a one year construction window), this is assessed as a **Low** adverse magnitude, where short-term and/or intermittent and temporary behavioural effects are expected in a small proportion of the population, and any impact to vital rates of individuals occur only in the short term (over a limited number of breeding cycles, <1 in this case) and where any changes to individual vital rates are very unlikely to occur to the extent that the population trajectory would be altered.
- 160 As outlined in section 7.5.3, disturbance as result of pile driving may result in small spatial and temporal scale disturbance to common dolphins, however direct evidence for this species is generally lacking. Given that they are of the same hearing group, it is expected that common dolphins may respond in a similar way to bottlenose dolphins. There is evidence that pile driving can result in temporary displacement of bottlenose dolphins, but that this displacement may be limited to small temporal and spatial scales. While there remains the potential for disturbance and displacement to affect individual behaviour and in particular calf survival rates, bottlenose dolphins do have some capability to adapt their behaviour and tolerate certain levels of temporary disturbance. Therefore, using bottlenose dolphins as a proxy, common dolphins are considered to have a **low** sensitivity to disturbance from pile driving.
- 161 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of disturbance from pile driving on common dolphins is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

Table 32: Number of common dolphins predicted to experience potential behavioural disturbance from piling.

| PILE TYPE          | MONOPILE (5,000 KJ) |       |         | MULTILEG (3,000 KJ) |       |         |
|--------------------|---------------------|-------|---------|---------------------|-------|---------|
| MODELLING LOCATION | NW                  | SE    | NW & SE | NW                  | SE    | NW & SE |
| # dolphins         | 17                  | 10    | NA      | 15                  | 8     | NA      |
| % MU               | 0.02%               | 0.01% |         | 0.01%               | 0.01% |         |

## Risso's dolphin

162 Table 33 outlines the number of Risso's dolphins predicted to be disturbed by pile driving at both the NW and SE locations for both monopiles and multi-leg jacket foundations on each piling day. Given the low predicted densities of Risso's dolphins in the area (0.031 dolphins/km<sup>2</sup> using SCANS III data) this results in low numbers of individuals predicted to be disturbed on any given piling day. The maximum estimate of disturbance is 65 dolphins for the installation of a monopile at the NW location, which represents 0.53% of the MU.

163 The impact is predicted to be of local spatial extent, short term duration (within a one-year construction window), intermittent and is reversible. As outlined above, the worst-case scenario would consist of the same animals being repeatedly exposed, thus increasing the potential for the repeated disturbance to result in changes to vital rates. However, given the low number of dolphins predicted to be impacted and the low proportion of the population this represents, this is considered to be a **low** adverse magnitude, where short-term and/or intermittent and temporary behavioural effects are expected in a small proportion of the population, and any impact to vital rates of individuals occur only in the short term (over a limited number of breeding cycles, <1 in this case) and where any changes to individual vital rates are very unlikely to occur to the extent that the population trajectory would be altered.

- 164 As outlined in section 7.5.3, there is no evidence on the sensitivity of Risso's dolphins to disturbance from pile driving. Risso's dolphins are categorised as being in the high-frequency cetacean hearing group (Southall et al. 2019) along with bottlenose dolphins, therefore it is considered appropriate, given the lack of species-specific data, to use bottlenose dolphins as a proxy. There is evidence that pile driving can result in temporary displacement of bottlenose dolphins, but that this displacement may be limited to small temporal and spatial scales. While there remains the potential for disturbance and displacement to affect individual behaviour and in particular calf survival rates, bottlenose dolphins do have some capability to adapt their behaviour and tolerate certain levels of temporary disturbance. Therefore, based on the evidence available for bottlenose dolphins as a proxy, Risso's dolphins are considered to have a **low** sensitivity to disturbance from pile driving.
- 165 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of disturbance from pile driving on Risso's dolphins is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

**Table 33: Number of Risso's dolphins predicted to experience potential behavioural disturbance from piling.**

| PILE TYPE          | MONOPILE (5,000 KJ) |       |         | MULTILEG (3,000 KJ) |       |         |
|--------------------|---------------------|-------|---------|---------------------|-------|---------|
| MODELLING LOCATION | NW                  | SE    | NW & SE | NW                  | SE    | NW & SE |
| # dolphins         | 65                  | 38    | NA      | 58                  | 33    | NA      |
| % MU               | 0.53%               | 0.31% |         | 0.47%               | 0.27% |         |



## Minke whale

- 166 Table 34 outlines the number of minke whales predicted to be disturbed by pile driving at both the NW and SE locations for both monopiles and multi-leg jacket foundations. Given the low predicted densities of minke whales in the area (0.017 whales/km<sup>2</sup> using SCANS III data) this results in low numbers of individuals predicted to be disturbed on any given piling day. The maximum estimate of disturbance is 36 whales from the installation of a monopile at the NW location, which represents 0.18% of the MU. It is important to note here that minke whales are expected to only be present in the summer months, and therefore any pile driving activities that occur outside the summer months is expected to have no impact on minke whales as none are expected to be present.
- 167 The impact is predicted to be of local spatial extent, short term duration (within a one-year construction window), intermittent and is reversible. As outlined above, the worst-case scenario would consist of the same animals being repeatedly exposed, thus increasing the potential for the repeated disturbance to result in changes to vital rates. However, given the low number of whales predicted to be impacted and the low proportion of the population this represents, this is considered to be a **low** adverse magnitude, where short-term and/or intermittent and temporary behavioural effects are expected in a small proportion of the population, and any impact to vital rates of individuals occur only in the short term (over a limited number of breeding cycles, <1 in this case) and where any changes to individual vital rates are very unlikely to occur to the extent that the population trajectory would be altered.
- 168 As outlined in section 7.5.4, there is a lack of evidence of strong behavioural responses of minke whales to piling noise. Therefore, they are considered to have a **low** sensitivity to disturbance from pile driving.
- 169 147 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of disturbance from pile driving on minke whales is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

Table 34: Number of minke whales and percentage of the MU predicted to experience potential behavioural disturbance from piling.

| PILE TYPE          | MONOPILE (5,000 KJ) |       |         | MULTILEG (3,000 KJ) |       |         |
|--------------------|---------------------|-------|---------|---------------------|-------|---------|
| MODELLING LOCATION | NW                  | SE    | NW & SE | NW                  | SE    | NW & SE |
| # whales           | 36                  | 21    | NA      | 32                  | 18    | NA      |
| % MU               | 0.18%               | 0.09% |         | 0.14%               | 0.08% |         |

## Grey seal


170 Table 35 outlines the number of grey seals predicted to be disturbed by pile driving at both the NW and SE locations for both monopiles and multi-leg jacket foundations. 95% confidence intervals are provided for grey seals as there was a large amount of uncertainty in the results that informed the dose-response curve. A total of 81 grey seals (95% CI: 9-151) are predicted to experience behavioural disturbance from the piling of a monopile at the NW location, which represents 1.6% of the Wales and NW England MU (0.2-3%) or 0.1% of the Oskar region III MU (0.0-0.2%). There is little overlap between the predicted noise contours and the area of higher grey seal density in the Dee estuary or inner Liverpool Bay area (Figure 21).

Table 35: Number of grey seals and percentage of the MU predicted to experience potential behavioural disturbance from piling.

| PILE TYPE               | MONOPILE (5,000 KJ) |                |         | MULTILEG (3,000 KJ) |               |         |
|-------------------------|---------------------|----------------|---------|---------------------|---------------|---------|
| MODELLING LOCATION      | NW                  | SE             | NW & SE | NW                  | SE            | NW & SE |
| # seals (mean & 95% CI) | 81<br>9 – 151       | 72<br>11 – 128 | NA      | 70<br>8 – 130       | 62<br>9 - 112 | NA      |



| PILE TYPE                 | MONOPILE (5,000 KJ) |                   |  | MULTILEG (3,000 KJ) |                   |  |
|---------------------------|---------------------|-------------------|--|---------------------|-------------------|--|
| % MU (Wales & NW Eng Mus) | 1.6%<br>0.2-3.0     | 1.4%<br>0.2-2.6   |  | 1.4<br>0.2-2.6      | 1.2%<br>0.2-2.2   |  |
| % MU (Ospar region III)   | 0.1%<br>0.0 – 0.2   | 0.1%<br>0.0 – 0.2 |  | 0.1%<br>0.0 – 0.2   | 0.1%<br>0.0 – 0.2 |  |



- 171 In order to assess whether the predicted level of disturbance would be sufficient to cause a population level effect, the interim PCoD model (version 5.2) was run<sup>vii</sup>. Conservative input values were used in the model, such that 81 grey seals were predicted to be disturbed on every piling day and two scenarios were run, one assuming the OSPAR Region III MU (66,100 individuals) and one assuming the Wales and NW England MUs (5,000 individuals). The model assumed the absolute worst-case scenario, that there could be a total of up to 201 days on which piling might occur (where it was precautionarily assumed that it could take up to three days to install each monopile, resulting in 150 piling days for 50 WTGs, 48 piling days for the two OSPs and 3 piling days for one met mast). An indicative piling schedule was not available for use, and therefore the piling days were randomly spread throughout the 12-month construction period.
- 172 The results of the modelling showed that there was no impact on the MU population as a result of the piling activity at AyM (Table 36 and Figure 22). The median ratio of the impacted:un-impacted population size after 6 years of simulation (1 year of impact followed by 5 years with no impact) was 1 and the impacted mean population size after 6 years of simulation (1 year of impact followed by 5 years with no impact) was the same as the un-impacted mean population size.

**Table 36: Grey seal population modelling inputs and results**

| PARAMETERS INPUT INTO IPCOD             |            | OSPAR REGION MU | WALES & NE ENG MU |
|-----------------------------------------|------------|-----------------|-------------------|
| Number of simulations run               | nboot      | 1000            | 1000              |
| Species                                 | spec       | GS              | GS                |
| Proportion of population that is female | propfemale | 0.5             | 0.5               |

<sup>vii</sup> <http://www.smruconsulting.com/products-tools/pcod/ipcod/>

| PARAMETERS INPUT INTO IPCOD                            |                | OSPAR<br>REGION<br>MU | WALES &<br>NE ENG<br>MU |
|--------------------------------------------------------|----------------|-----------------------|-------------------------|
| Population size<br>at the start of<br>simulations      | pmean          | 66100                 | 5000                    |
| Pup survival<br>rate                                   | Surv[1]        | 0.222                 | 0.222                   |
| Juvenile<br>survival rate                              | Surv[7]        | 0.94                  | 0.94                    |
| Adult survival<br>rate                                 | Surv[13]       | 0.94                  | 0.94                    |
| Fecundity rate                                         | Fertility      | 0.84                  | 0.84                    |
| Age at<br>independence                                 | age1           | 1                     | 1                       |
| Age at first<br>birth                                  | age2           | 5                     | 5                       |
| Number of<br>piling years                              | pile_years     | 1                     | 1                       |
| Proportion of<br>animals in<br>vulnerable<br>component | vulnmean       | c(1.0)                | c(1.0)                  |
| Days of<br>"residual"<br>disturbance                   | days           | 0                     | 0                       |
| Proportion of<br>disturbed<br>experiencing<br>"days"   | prop_days_dist | 1                     | 1                       |

| PARAMETERS INPUT INTO IPCOD                                                                    |           | OSPAR<br>REGION<br>MU | WALES &<br>NE ENG<br>MU |
|------------------------------------------------------------------------------------------------|-----------|-----------------------|-------------------------|
| Number of<br>piling<br>Operations                                                              | pilesx1   | 1                     | 1                       |
| Seasonal<br>variation (1=no<br>variation)                                                      | seasons   | 1                     | 1                       |
| Number of<br>animals<br>predicted to<br>experience<br>disturbance<br>during 1 day<br>of piling | numDt[1,] | 81                    | 81                      |
| Years for<br>simulation                                                                        | years     | 25                    | 25                      |
| Density<br>dependence<br>(0=no density<br>dependence)                                          | z         | 0                     | 0                       |
| Piling schedule                                                                                |           | 201 days              | 201<br>days             |
| RESULTS                                                                                        |           |                       |                         |
| Un-impacted pop mean (after 1 year)                                                            |           | 66,100                | 5,038                   |
| Impacted pop mean (after 1 year)                                                               |           | 66,100                | 5,038                   |
| Impacted pop as % of un-impacted pop (after 1 year)                                            |           | 100%                  | 100%                    |
| Median impacted:un-impacted population size (after 1 year)                                     |           | 1                     | 1                       |

| PARAMETERS INPUT INTO IPCOD                                  | OSPAR<br>REGION<br>MU | WALES &<br>NE ENG<br>MU |
|--------------------------------------------------------------|-----------------------|-------------------------|
| Un-impacted pop mean (after 6 years)                         | 69,689                | 5,302                   |
| Impacted pop mean (after 6 years)                            | 69,689                | 5,302                   |
| Impacted pop as % of un-impacted pop (after 6 years)         | 100%                  | 100%                    |
| Median impacted:un-impacted population size (after 6 years)  | 1                     | 1                       |
| Un-impacted pop mean (after 12 years)                        | 73,772                | 5,633                   |
| Impacted pop mean (after 12 years)                           | 73,772                | 5,633                   |
| Impacted pop as % of un-impacted pop (after 12 years)        | 100%                  | 100%                    |
| Median impacted:un-impacted population size (after 12 years) | 1                     | 1                       |






Figure 22: Population trajectory for both the impacted and un-impacted grey seal OSPAR Region III MU (left) and the Wales & NW England's MU (right) resulting from 201 days of piling disturbance.

173 The impact is predicted to be of local spatial extent, short term duration (within a one-year construction window), intermittent and is reversible. Given their ability to store energy, and the fact that they are generalist and adaptable foragers, it is expected that grey seals would require moderate-high levels of repeated disturbance before there was any effect on fertility rates. Given the number of grey seals predicted to be impacted and the proportion of the population this represents, along with the short-term duration of the overall impact, this is considered to be a **low** adverse magnitude, where short-term and/or intermittent and temporary behavioural effects are expected in a small proportion of the population, and any impact to vital rates of individuals occur only in the short term (over a limited number of breeding cycles, <1 in this case) and where any changes to individual vital rates are very unlikely to occur to the extent that the population trajectory would be altered (as shown by the population modelling).

- 174 As outlined in section 7.5.5, there is limited information available on the behavioural responses of grey seals to pile driving. The data that are available suggests large variation in response level between individuals but that seals returned to the area once pile driving ceased (Aarts et al. 2018). Grey seals are highly adaptable to a changing environment and are capable of adjusting their metabolic rate and foraging tactics, to compensate for different periods of energy demand and supply (Beck et al. 2003, Sparling et al. 2006), consequently, they are unlikely to be particularly sensitive to displacement from foraging grounds during periods of active piling.
- 175 Based on the data presented in Aarts et al. (2018) and Hastie et al. (2021), it is possible that some grey seals may show no behavioural response at all, if they are motivated to remain in the area for foraging (if the area contains a high-quality prey patch). The quality of the AyM array area as a prey patch is unknown, and the importance of this area to grey seals specifically for foraging has not been quantitatively assessed. However, some inference can be made from movement and distribution data. Habitat preference data do not appear to indicate that the AyM array area itself is an important foraging location, though densities are higher in the Dee estuary. Given the wide-ranging behaviour of grey seals, travelling up to 448 km from a haul-out site (Carter et al. 2020), it is highly likely that any grey seals displaced from lower quality prey patches will be able to compensate by travelling to a different foraging patch, and thus it is expected that any displacement would result in minimal energetic cost. Should the seals choose to remain in the area during piling then this indicates that the energetic benefit outweighs the perceived risk from piling.
- 176 Therefore, grey seals are considered to have a **negligible** sensitivity to disturbance from pile driving.
- 177 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **negligible**. Therefore, the significance of the effect of disturbance from pile driving on grey seals is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

## Cofferdam sheet piles

- 178 Table 37 outlines the number of marine mammals of each species predicted to be disturbed per piling day by pile driving installation of sheet piles for the cofferdam. The numbers predicted to be disturbed are very low for all species (0-20 individuals) given the low hammer energies required.
- 179 For bottlenose dolphins, common dolphins and minke whales, <1 individual is predicted to be disturbed per piling day. Therefore, for these species the magnitude is assessed as **negligible** as there is no potential for any changes in the individual reproductive success or survival, and therefore no changes to the population size or trajectory. Therefore, the significance of the effect of disturbance from cofferdam sheet pile driving on bottlenose dolphins, common dolphins and minke whales is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.
- 180 Though the number of animals and proportion of the MU predicted to be impacted per day of piling is low for harbour porpoise, Risso's dolphins and grey seals, there is the potential for 81 days of cofferdam sheet piling to potentially result in short-term and/or intermittent and temporary behavioural effects are expected in a small proportion of the population where any changes to individual vital rates are very unlikely to occur to the extent that the population trajectory would be altered. Therefore, the magnitude is assessed as **low** adverse.
- 181 Both harbour porpoise and Risso's dolphins have been assessed as having a **low** sensitivity to disturbance from pile driving. Therefore, the significance of the effect of disturbance from cofferdam sheet pile driving on harbour porpoise and Risso's dolphins is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.
- 182 Grey seals have been assessed as having a **negligible** sensitivity to disturbance from pile driving. Therefore, the significance of the effect of disturbance from cofferdam sheet pile driving on grey seals is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

Table 37: Number of animals predicted to experience behavioural disturbance from piling of cofferdam sheet piles.

| SPECIES            | DISTURBANCE            | 8 M ABOVE LAT     | 0.6 M ABOVE LAT   |
|--------------------|------------------------|-------------------|-------------------|
| Harbour porpoise   | # disturbed (JCP)      | 3                 | 1                 |
|                    | % MU                   | 0.00%             | 0.00%             |
|                    | #disturbed (SWF)       | 20                | 4                 |
|                    | % MU                   | 0.03%             | 0.01%             |
| Bottlenose dolphin | # disturbed            | <1                | <1                |
|                    | % MU                   | <0.05%            | <0.05%            |
| Common dolphin     | # disturbed            | 0                 | 0                 |
|                    | % MU                   | 0.00%             | 0.00%             |
| Risso's dolphin    | # disturbed            | 1                 | 0                 |
|                    | % MU                   | 0.01%             | 0.00%             |
| Minke whale        | # disturbed            | 0                 | 0                 |
|                    | % MU                   | 0.00%             | 0.00%             |
| Grey seal          | # disturbed            | 6 (1-10)          | 3 (1-5)           |
|                    | % MU (Wales & NW Eng)  | 0.12% (0.02-0.20) | 0.06% (0.02-0.10) |
|                    | % MU (OSAR region III) | 0.01% (0.00-0.02) | 0.00% (0.00-0.01) |

## Disturbance summary

183 The impact of behavioural disturbance from piling noise under the maximum design scenario is not considered to have a significant effect on any marine mammal species considered in this assessment (Table 38).

**Table 38: Summary of the assessment of disturbance from pile driving for each marine mammal species.**

| SPECIES            | MAGNITUDE          | SENSITIVITY | SIGNIFICANCE                    |
|--------------------|--------------------|-------------|---------------------------------|
| Harbour porpoise   | Low-Medium adverse | Low         | Minor adverse significance      |
| Bottlenose dolphin | Medium adverse     | Low         | Minor adverse significance      |
| Common dolphin     | Low adverse        | Low         | Minor adverse significance      |
| Risso's dolphin    | Low adverse        | Low         | Minor adverse significance      |
| Minke whale        | Low adverse        | Low         | Minor adverse significance      |
| Grey seal          | Low adverse        | Negligible  | Negligible adverse significance |

### 7.10.4 Other construction activities

#### PTS from other construction activities

184 A simple assessment of the noise impacts from non-piling noise is presented in Volume 4, Annex 6.2: Subsea Noise Technical Report. This includes an assessment of the potential PTS and TTS-onset impact ranges for:

- ▲ Cable laying: Noise from the cable laying vessel and any other associated noise during the offshore cable installation.



- ▲ Dredging: Dredging may be required on site for seabed preparation work for certain foundation options, as well as for the export cable, array cables and interconnector cable installation. Suction dredging has been assumed as a worst-case.
- ▲ Trenching: Plough trenching may be required during offshore cable installation.
- ▲ Rock placement: Potentially required on site for installation of offshore cables (cable crossings and cable protection) and scour protection around foundation structures.
- ▲ Vessel noise: Jack-up barges for piling substructure and WTG installation. Other large and medium sized vessels to carry out other construction tasks and anchor handling. Other small vessels for crew transport and maintenance on site.

185 Using the non-impulsive weighted  $SEL_{cum}$  PTS-onset thresholds from Southall et al. (2019) resulted in estimated PTS impact ranges of <100 m for all marine mammal species for each non-piling construction activity (Table 39). These values mean that animals would have to stay within these very small ranges for 24 hours before they experienced injury, which is an extremely unlikely scenario as it is far more likely that any marine mammal within the injury zone would move away from the vicinity of the vessel and the construction activity.

186 Using the non-impulsive weighted  $SEL_{cum}$  TTS-onset thresholds from Southall et al. (2019) resulted in an estimated TTS impact ranges of <100 m for all HF and LF cetaceans and PCW for all non-piling construction activity. Estimated TTS for HF cetaceans was variable depending on the non-piling construction activity: cable laying, trenching and vessel noise (medium) also had TTS impact ranges of <100 m but suction dredging and vessel noise (large) had an increased TTS impact range of 200 m and vessel noise (large) was increased to a 1 km TTS impact range (Table 39). These values are assuming that the animal would be stationary within these small ranges for 24 hours before they experienced a TTS in hearing, which is an extremely unlikely scenario as it is far more likely that any marine mammal within the injury zone would move away from the vicinity of the vessel and the construction activity. Vessel noise (large) had the greatest estimated TTS impact range of 1 km so presents an increased potential for an animal to be within this range for 24 hours, but is still considered an unlikely scenario.



- 187 The impact of non-piling construction noise under the maximum design scenario is not considered to have a significant effect on any marine mammal species considered in this assessment. These noise sources will have a local spatial extent, short-term duration and are intermittent, meaning a marine mammals would have to remain within close proximity (<100 m) for a 24-hour period for PTS-onset to occur. Therefore, the impact of these sources will have a **negligible** adverse magnitude.
- 188 As stated in Section 7.5.1, cetaceans are assessed as having a **low** sensitivity to PTS and grey seals are assessed as having a **negligible** sensitivity.
- 189 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as low (cetaceans) or negligible (grey seals). Therefore, the significance of the effect of PTS-onset from other construction activities is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

**Table 39: Summary of the source level (SEL<sub>cum</sub> dB re 1 µPa@1m(RMS)) and impact ranges for the different construction noise sources using the non-impulsive criteria from Southall et al. (2019)**

| SOURCE                 | SOURCE LEVEL | VHF    | HF     | LF     | PCW    |
|------------------------|--------------|--------|--------|--------|--------|
| PTS-onset Impact Range |              |        |        |        |        |
| Cable laying           | 171          | <100 m | <100 m | <100 m | <100 m |
| Suction dredging       | 186          | <100 m | <100 m | <100 m | <100 m |
| Trenching              | 172          | <100 m | <100 m | <100 m | <100 m |
| Rock placement         | 172          | <100 m | <100 m | <100 m | <100 m |
| Vessel noise (large)   | 168          | <100 m | <100 m | <100 m | <100 m |
| Vessel noise (medium)  | 161          | <100 m | <100 m | <100 m | <100 m |
| TTS-onset Impact Range |              |        |        |        |        |
| Cable laying           | 171          | <100 m | <100 m | <100 m | <100 m |

| SOURCE                | SOURCE LEVEL | VHF    | HF     | LF     | PCW    |
|-----------------------|--------------|--------|--------|--------|--------|
| Suction dredging      | 186          | 200 m  | <100 m | <100 m | <100 m |
| Trenching             | 172          | <100 m | <100 m | <100 m | <100 m |
| Rock placement        | 172          | 1 km   | <100 m | <100 m | <100 m |
| Vessel noise (large)  | 168          | 200 m  | <100 m | <100 m | <100 m |
| Vessel noise (medium) | 161          | <100 m | <100 m | <100 m | <100 m |

## Disturbance from other construction activities

190 There is little evidence on the impact of disturbance of marine mammals from other construction activities such as rock placing, dredging, trenching etc.). There are some studies which have reported potential disturbance ranges from dredging activities, and these are summarised in

191 Table 40. Note: disturbance from vessels is assessed separately (section 7.10.8).

**Table 40: Summary of the potential for disturbance from dredging on marine mammal species.**

| SPECIES          | EVIDENCE                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |
|------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Harbour porpoise | Dredging at a source level of 184 dB re 1 $\mu$ Pa at 1 m would result in avoidance up to 5 km from the dredging site (Verboom 2014). Conversely, Diederichs et al. (2010) found much more localised impacts; using Passive Acoustic Monitoring there was short term avoidance (~3 hours) at distances of up to 600 m from the dredging vessel, but no significant long-term impacts. Modelling potential impacts of dredging using a case study of the Maasvlakte port expansion (assuming maximum source levels of 192 dB re 1 $\mu$ Pa) predicted a disturbance range of 400 m, while a more conservative approach predicted avoidance of harbour porpoise up to 5 km (McQueen et al. 2020). |

| SPECIES            | EVIDENCE                                                                                                                                                                                                                                                                  |
|--------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Bottlenose dolphin | Increased dredging activity at Aberdeen Harbour was associated with a reduction in bottlenose dolphin presence and, during the initial dredge operations, bottlenose dolphins were absent for five weeks (Pirotta et al. 2013).                                           |
| Common dolphin     | In northwest Ireland, construction related activity (including dredging) did not result in any evidence of a negative impact to common dolphins (Culloch et al. 2016).                                                                                                    |
| Risso's dolphin    | There is currently no information available on the impacts of dredging for Risso's dolphins.                                                                                                                                                                              |
| Minke whale        | In northwest Ireland, construction related activity (including dredging) has been linked to reduced minke whale presence (Culloch et al. 2016).                                                                                                                           |
| Grey seal          | Based on the generic threshold of behavioural avoidance of pinnipeds (140 dB re 1 $\mu$ Pa SPL)(Southall et al. 2007), acoustic modelling of dredging demonstrated that disturbance could be caused to individuals between 400 m to 5 km from site (McQueen et al. 2020). |

192 As with piling activities, there is the potential for disturbance and displacement of marine mammals from other construction sources. Animals will likely move away from the sound source before the onset of PTS or TTS, thereby exhibiting a behavioural response.

193 Given the location of the ECC and the landfall, it is not expected that any construction related activity will disturb grey seals hauled-out on land at the main haul-out sites along the north Wales coastline (the Skerries, Angel Bay, Hilbre and West Hoyle).

194 It is expected that changes will be temporary due to the short-term duration of the activities. Given the potential for other construction activities such as dredging to impact animals out to 5 km from the source, the impact is likely to be of a **low** magnitude. It has been assumed that marine mammal sensitivity to other construction activities will be similar to that of disturbance from pile driving or vessel activity (see Table 15).

195 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low** (cetaceans) or **negligible** (grey seals). Therefore, the significance of the effect of disturbance from other construction activities is concluded to be of **minor adverse significance** (for cetaceans) and **negligible adverse significance** (for grey seals), both of which is not significant in terms of the EIA regulations.

#### 7.10.5 PTS-onset from UXO

196 If found, a risk assessment will be undertaken and items of UXO are either avoided, removed or detonated in situ. Recent advancements in the available methods for UXO clearance mean that high-order detonation may be avoided. The methods of UXO clearance considered for AyM may include:

- ▲ High-order detonation;
- ▲ Low-order detonation (deflagration);
- ▲ Removal/ relocation; and
- ▲ Other less intrusive means of neutralising the UXO.

197 As the detailed pre-construction surveys have not yet been completed, it is not possible at this time to determine how many items of UXO will require clearance. As a result, a separate Marine Licence will be applied for post-consent for the clearance (where required) of any UXO identified. In order to define the design envelope for consideration of UXO within the EIA, a review of recent information has been undertaken, in conjunction with experience from nearby offshore wind farms (including GyM). It should be noted that AyM is generally in an area considered to be low risk for UXO when compared to areas closer to Liverpool and for other recent wind farm projects in the southern North Sea; indeed, the construction of GyM required the clearance of only three UXO. The Applicant commissioned a study to establish the potential for UXO presence at AyM. Based on the results of this study, the design envelope for UXO clearance is for a total of 370 UXOs expected, of which, 52 are expected to require inspection and only ten of which are expected to require clearance.



- 198 Current advice from the SNCBs (Natural England and the MMO) is that Southall et al. (2019) should be used for assessing the impacts from UXO detonation on marine mammals. However, the suitability of these criteria for UXO is under discussion due to the lack of empirical evidence from UXO detonations using these metrics, in particular the range dependent characteristics of the peak sounds, and whether current propagation models can accurately predict the range at which these thresholds are reached.
- 199 An estimation of the source level and predicted PTS-onset impact ranges were calculated for a range of expected UXO sizes. The UXO ALARP Strategy report produced by Ordtek (ref. JM5694\_UXO\_DTS\_RARMS\_V1.0) indicates that it is possible that the project may encounter German mines, large projectiles and small projectiles. The potential for any other device is unlikely or very unlikely. On this basis, the range of equivalent charge weights for the potential UXO devices that could be present at AyM have been estimated as:
- ▲ Small projectile (small artillery or rocket): 5 kg TNT NEQ
  - ▲ Large artillery projectile: 15 kg TNT NEQ
  - ▲ German mine: 164 kg TNT NEQ
- 200 The use of a donor charge represents the worst case for additional noise. Although the donor charges have yet to be specified, donor charge weights of between 5 and 25 kg have been used on similar projects. As these are the same order as the smaller UXO devices identified above, the results for the smaller projectiles can be used as a proxy for these, with an extra item for 25 kg to clear larger UXO.
- 201 Full details of the underwater noise modelling and the resulting PTS-onset impact areas and ranges are detailed in Volume 4, Annex 6.2: Subsea Noise Technical Report. The source level of each UXO charge weight was calculated in accordance with Soloway and Dahl (2014), Arons (1954) and Barrett (1996), using conservative calculation parameters that result in the upper estimate of the source level for each charge size. This is therefore considered to be an indication of the potential maximum noise output from each charge size and, as such, likely results in an overestimate of PTS-onset impact ranges, especially for larger charge sizes.

202 The impact of PTS-onset is predicted to be of local spatial extent, short term duration and intermittent, however since PTS is a permanent change in the hearing threshold, it is not recoverable. As part of any future consent for UXO removal AyM will be required to implement a UXO specific MMMP to ensure that the risk of PTS is reduced to negligible. The exact mitigation measures contained within the UXO MMMP are yet to be determined and will be agreed with NRW, however, multiple measures are available and have been implemented elsewhere for UXO clearance, such as the use of ADDs and scarer charges to displace animals to beyond the PTS-onset impact range, the use of noise abatement techniques where appropriate or the use of low-order clearamnce methods as an alternative. The magnitude of this impact is therefore considered to be **negligible** adverse.

**Table 41: PTS-onset impact range for various potential UXO charge sizes.**

| CHARGE SIZE                                             |     |                                         | 5 KG   | 25 KG  | 164 KG |
|---------------------------------------------------------|-----|-----------------------------------------|--------|--------|--------|
| PTS-ONSET SPL <sub>PEAK</sub> (DB RE 1μPA)              |     |                                         |        |        |        |
| VHF                                                     | 202 | Impact Range                            | 2.7 km | 4.6 km | 8.6 km |
|                                                         |     | # Porpoise (JCP 0.13/km <sup>2</sup> )  | 3      | 9      | 30     |
|                                                         |     | # Porpoise (SWF 1.0/km <sup>2</sup> )   | 23     | 66     | 232    |
| HF                                                      | 203 | Impact Range                            | 150 m  | 260 m  | 500 m  |
|                                                         |     | # Bottlenose (0.0178/km <sup>2</sup> )* | <1     | <1     | <1     |
|                                                         |     | # Common (0.0081/km <sup>2</sup> )      | <1     | <1     | <1     |
|                                                         |     | # Risso's (0.031/km <sup>2</sup> )      | <1     | <1     | <1     |
| LF                                                      | 219 | Impact Range                            | 470 m  | 810 m  | 1.5 km |
|                                                         |     | # Whales (0.017/km <sup>2</sup> )       | <1     | <1     | <1     |
| PCW                                                     | 218 | Impact Range                            | 530 m  | 900 m  | 1.6 km |
|                                                         |     | # Seals (0.43/km <sup>2</sup> )**       | <1     | 1      | 3      |
| PTS-ONSET SEL <sub>SS</sub> (DB RE 1μPA <sup>2</sup> S) |     |                                         |        |        |        |



| CHARGE SIZE |     |                                         | 5 KG  | 25 KG  | 164 KG |
|-------------|-----|-----------------------------------------|-------|--------|--------|
| VHF         | 155 | Impact Range                            | 300 m | 560 m  | 1 km   |
|             |     | # Porpoise (JCP 0.13/km <sup>2</sup> )  | <1    | <1     | <1     |
|             |     | # Porpoise (SWF 1.0/km <sup>2</sup> )   | <1    | 1      | 3      |
| HF          | 185 | Impact Range                            | <50 m | <50 m  | <50 m  |
|             |     | # Bottlenose (0.0178/km <sup>2</sup> )* | <1    | <1     | <1     |
|             |     | # Common (0.0081/km <sup>2</sup> )      | <1    | <1     | <1     |
|             |     | # Risso's (0.031/km <sup>2</sup> )      | <1    | <1     | <1     |
| LF          | 183 | Impact Range                            | 990 m | 2.1 km | 5.4 km |
|             |     | # Whales (0.017/km <sup>2</sup> )       | <1    | <1     | 2      |
| PCW         | 185 | Impact Range                            | 170 m | 380 m  | 960 m  |
|             |     | # Seals (0.43/km <sup>2</sup> )**       | <1    | <1     | 1      |

\* mean density within AyM + 26 km buffer

\*\* mean density within AyM + 26 km buffer from Carter et. al (2020)

## 7.10.6 Disturbance from UXO

203 In the absence of agreed thresholds to assess the potential for behaviour disturbance in marine mammals from UXO detonations, this assessment presents results for each of the following behavioural disturbance thresholds:

- 26 km EDR for high-order detonations;
- 5 km EDR for low-order detonations; and
- TTS-onset thresholds for high-order detonations.

204 Please see Volume 4, Annex 7.3: Marine Mammal Quantitative Noise Impact Assessment – Assumptions, Limitations and Uncertainties for full details on the selection of these thresholds to assess disturbance from UXO clearance.

205 The impact of UXO disturbance is predicted to be of local spatial extent, short term duration and intermittent and extremely infrequent (expected absolute maximum of 10 UXOs require clearing). As part of any future consent for UXO removal AyM will be required to implement a specific MMMP during UXO operations to minimise the risk of injury to marine mammals. As previously stated, the exact mitigation measures contained with the UXO MMMP are yet to be determined and will be agreed with NRW. However, multiple measures are available and have been implemented elsewhere for UXO clearance, such as the use of ADDs and scarer charges to displace animals to beyond the PTS impact range, the use of noise abatement techniques where appropriate and the consideration of low order clearance methods as an alternative.

## 26 km EDR – High order

206 It has been advised by JNCC that an EDR of 26 km around the source location is used to determine the impact area from UXO clearance with respect to disturbance of harbour porpoise in SACs (JNCC et al. 2020). In the absence of agreed metrics for other species, and given a lack of empirical data on the likelihood of response to explosives, this 26 km radius (area of 2,124 km<sup>2</sup>) has been applied here for all species. The resulting number of animals, proportion of the reference population and impact magnitude is detailed in Table 42. This is quantified by calculating the numbers of animals likely to be within the effective deterrence range by multiplying the area of the impact footprint by the appropriate density estimate.

**Table 42: Estimated number of marine mammals potentially at risk of disturbance during high-order UXO clearance (assuming an EDR of 26 km, resulting in a 2,123.72 km<sup>2</sup> impact area).**

| SPECIES            | DENSITY                           | # IMPACTED | % MU  |
|--------------------|-----------------------------------|------------|-------|
| Harbour porpoise   | JCP 0.13 porpoise/km <sup>2</sup> | 276        | 0.44% |
|                    | SWF 1.0 porpoise/km <sup>2</sup>  | 2,124      | 3.40% |
| Bottlenose dolphin | 0.0178 dolphins/km <sup>2</sup> * | 38         | 12.9% |
| Common dolphin     | 0.0081 dolphins/km <sup>2</sup>   | 17         | 0.02% |

| SPECIES         | DENSITY                            | # IMPACTED | % MU       |
|-----------------|------------------------------------|------------|------------|
| Risso's dolphin | 0.031 dolphins/km <sup>2</sup>     | 66         | 0.54%      |
| Minke whale     | 0.017 whales/km <sup>2</sup>       | 36         | 0.18%      |
| Grey Seal       | 0.43 grey seals/km <sup>2</sup> ** | 913***     | 1.38% **** |

\* mean density within AyM + 26 km buffer

\*\* mean density within AyM + 26 km buffer from Carter et. al (2020)

\*\*\* this is considered to be a vast overestimate since the dose-response curve predicts low levels of disturbance to grey seals

\*\*\*\* using OSPAR region III MU

207 NRW have expressed concerns with the 26 km EDR approach, and have stated that: *"NRW considers that there is still considerable uncertainty in the evidence underpinning the calculation of Effective Deterrent Range (EDR), especially in Welsh waters, and as such are not a signatory to the cited JNCC guidance for assessing the significance of noise disturbance against Conservation Objectives of harbour porpoise SACs (England & Northern Ireland)"* (NRW s42 comments).

208 The 26 km EDR was advised by JNCC for harbour porpoise only. There is no evidence that a 26 km EDR is suitable for any other species of marine mammal. Thus the 26 km EDR has been used here for illustrative purposes for other marine mammal species but should be viewed with caution as there is no evidence to support this impact range.

209 Therefore, there are limitations in the confidence levels for the number of animals predicted to experience behavioural disturbance using this approach. As such, the alternative approach of using TTS-onset as a proxy for disturbance is also presented below.

## 5 km EDR – Low order

210 It is important to note that while high-order detonation represents the very worst-case scenario for UXO clearance, it is highly likely that low-order clearance methods (deflagration) will be used instead. Current risk assessments conducted to support UXO Marine Licence Applications that are including deflagration as the preferred method, are assuming an EDR of 5 km (e.g. Sofia offshore wind farm). As a consequence, due to the absence of formal guidance, this approach has been adopted here for the assessment of disturbance from low-order detonation of UXOs at the Project.

211 There is no evidence that a 5 km EDR is suitable for any species of marine mammal. Thus the 5 km EDR has been used here for illustrative purposes but should be viewed with caution as there is no evidence to support this impact range. As such, the alternative approach of using TTS-onset as a proxy for disturbance is also presented below.

**Table 43: Estimated number of marine mammals potentially at risk of disturbance during low-order UXO clearance (assuming an EDR of 5 km, resulting in a 78.54 km<sup>2</sup> impact area).**

| SPECIES            | DENSITY                            | # IMPACTED | % MU      |
|--------------------|------------------------------------|------------|-----------|
| Harbour porpoise   | JCP 0.13 porpoise/km <sup>2</sup>  | 10         | 0.02%     |
|                    | SWF 1.0 porpoise/km <sup>2</sup>   | 79         | 0.13%     |
| Bottlenose dolphin | 0.0178 dolphins/km <sup>2</sup> *  | 1          | 0.48%     |
| Common dolphin     | 0.0081 dolphins/km <sup>2</sup>    | <1         | 0.00%     |
| Risso's dolphin    | 0.031 dolphins/km <sup>2</sup>     | 2          | 0.02%     |
| Minke whale        | 0.017 whales/km <sup>2</sup>       | 1          | 0.01%     |
| Grey Seal          | 0.43 grey seals/km <sup>2</sup> ** | 34***      | 0.05%**** |

\* mean density within AyM + 26 km buffer

\*\* mean density within AyM + 26 km buffer from Carter et. al (2020)

\*\*\* this is considered to be a vast overestimate since grey seals are known to be less responsive than harbour porpoise

\*\*\*\* using OSPAR region III MU

## Fixed noise threshold: TTS-onset

- 212 An estimation of the extent of behavioural disturbance can be based on the sound levels at which the onset of TTS is predicted to occur from impulsive sounds. As stated by Southall et al. (2007): *“Although TTS is not a behavioural effect per se, this approach is used because any compromise, even temporarily, to hearing functions has the potential to affect vital rates by interfering with essential communication and/or detection capabilities. This approach is expected to be precautionary because TTS at onset levels is unlikely to last a full diel cycle or to have serious biological consequences during the time TTS persists”*. Therefore, using TTS-onset as a proxy for disturbance for a single pulse sound source is expected to over-estimate the true behavioural response.
- 213 Full details of the underwater noise modelling and the resulting TTS-onset impact areas and ranges are detailed in Volume 4, Annex 6.2: Subsea Noise Technical Report.
- 214 Table 44 and Table 45 provide the TTS-onset impact ranges for various UXO charge sizes. Large TTS-onset impact ranges are predicted for both porpoise (16 km using  $SPL_{peak}$ ) and minke whales (65 km using  $SEL_{ss}$ ) for UXO charge size of 164 kg. These impact ranges are predicted to be highly over-precautionary as a proxy for disturbance, since a) TTS-onset is unlikely to have serious biological consequences and b) these ranges do not account for the fact that impulsive sound will lose its harmful impulsive characteristics and become non-impulsive as it propagates from the source (see Annex 7.3 for further details).



215 Despite this, even when the full TTS-onset impact ranges are considered, the number of animals predicted to experience TTS-onset is only 105 porpoise (0.17% MU) using the JCP density, or 804 porpoise (1.29% MU) using the SWF density, <1 dolphin, 226 minke whales (1.12% MU) and 195 grey seals (0.29% OSPAR Region III MU) per detonation event. Given that Southall et al. (2007) state that “*TTS at onset levels is unlikely to [...] have serious biological consequences*” it is not expected that vital rates would be significantly impacted, and therefore the sensitivity of marine mammals to TTS-onset as a proxy for disturbance is **low**. Since it is expected that only a maximum of ten UXOs might require detonation, this results in a maximum of 10 days of disturbance from detonations. Given this low level of repeated disturbance it is unlikely to result in any change in the population trajectory for any of the marine mammal species considered, and so is assessed as being of **low** magnitude.

216 The magnitude of the impact has been assessed as **low**, and the sensitivity of receptors as **low**. Therefore, the significance of the effect of disturbance from UXO clearance is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

Table 44: TTS-onset impact ranges (SPL<sub>peak</sub>) for various potential UXO charge sizes.

| CHARGE SIZE                                |     |                         | 5 KG       | 25 KG       | 164 KG      |
|--------------------------------------------|-----|-------------------------|------------|-------------|-------------|
| TTS-ONSET SPL <sub>PEAK</sub> (DB RE 1μPA) |     |                         |            |             |             |
| VHF                                        | 196 | Impact Range (km)       | 5.0        | 8.5         | 16          |
|                                            |     | Area (km <sup>2</sup> ) | 78.5       | 227.0       | 804.2       |
|                                            |     | JCP # Porpoise (%MU)    | 10 (0.02%) | 30 (0.05%)  | 105 (0.17%) |
|                                            |     | SWF # Porpoise (%MU)    | 79 (0.13%) | 227 (0.36%) | 804 (1.29%) |
| HF                                         | 224 | Impact Range (km)       | 0.28       | 0.49        | 0.92        |
|                                            |     | Area (km <sup>2</sup> ) | 0.2        | 0.8         | 2.7         |
|                                            |     | # Bottlenose            | <1         | <1          | <1          |
|                                            |     | # Common                | <1         | <1          | <1          |



| CHARGE SIZE |     |                         | 5 KG | 25 KG     | 164 KG     |
|-------------|-----|-------------------------|------|-----------|------------|
|             |     | # Risso's               | <1   | <1        | <1         |
| LF          | 213 | Impact Range (km)       | 0.88 | 1.5       | 2.8        |
|             |     | Area (km <sup>2</sup> ) | 2.4  | 7.1       | 24.6       |
|             |     | # Whales                | <1   | <1        | <1         |
| PCW         | 212 | Impact Range (km)       | 1.0  | 1.6       | 3.1        |
|             |     | Area (km <sup>2</sup> ) | 3.1  | 8.0       | 30.2       |
|             |     | # Seals (%MU)           | 1    | 3 (0.00%) | 13 (0.02%) |

Table 45 TTS-onset impact ranges (SEL<sub>SS</sub>) for various potential UXO charge sizes.

| CHARGE SIZE                                             |     |                         | 5 KG       | 25 KG      | 164 KG      |
|---------------------------------------------------------|-----|-------------------------|------------|------------|-------------|
| TTS-ONSET SEL <sub>SS</sub> (DB RE 1μPA <sup>2</sup> S) |     |                         |            |            |             |
| VHF                                                     | 140 | Impact Range (km)       | 1.7        | 2.4        | 3.3         |
|                                                         |     | Area (km <sup>2</sup> ) | 9.1        | 18.1       | 34.2        |
|                                                         |     | JCP # Porpoise (%MU)    | 1          | 2 (0.00%)  | 4 (0.01%)   |
|                                                         |     | SWF # Porpoise (%MU)    | 9          | 18         | 34          |
| HF                                                      | 170 | Impact Range (km)       | 0.08       | 0.15       | 0.34        |
|                                                         |     | Area (km <sup>2</sup> ) | <0.1       | 0.1        | 0.4         |
|                                                         |     | # Bottlenose            | <1         | <1         | <1          |
|                                                         |     | # Common                | <1         | <1         | <1          |
|                                                         |     | # Risso's               | <1         | <1         | <1          |
| LF                                                      | 168 | Impact Range (km)       | 14         | 29         | 65          |
|                                                         |     | Area (km <sup>2</sup> ) | 615.8      | 2,642.1    | 13,273.2    |
|                                                         |     | # Whales                | 10 (0.05%) | 45 (0.22%) | 226 (1.12%) |

| CHARGE SIZE |     |                         | 5 KG      | 25 KG      | 164 KG      |
|-------------|-----|-------------------------|-----------|------------|-------------|
| PCW         | 170 | Impact Range (km)       | 2.4       | 5.2        | 12          |
|             |     | Area (km <sup>2</sup> ) | 18.1      | 84.9       | 452.4       |
|             |     | # Seals (%MU)           | 8 (0.01%) | 37 (0.06%) | 195 (0.29%) |

### 7.10.7 Collision risk from construction vessels

217 The area surrounding AyM already experiences high levels of vessel traffic (Figure 23 and Figure 24) (see Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline for full details). The Shipping and Navigation Baseline study recorded an average of 58 vessels per day recorded within study area<sup>viii</sup> in the winter (busiest day was 73 vessels) (Figure 25), comprised of mainly cargo and tanker vessels as well as recreational and offshore wind farm vessels (Figure 27). Similarly, the study recorded an average of 57 vessels per day recorded within study area in the summer (busiest day was 71 vessels) (Figure 26), comprised of mainly cargo and tanker vessels as well as recreational and offshore wind farm vessels (Figure 27).

218 Therefore, the introduction of additional vessels during construction of AyM is not a novel impact for marine mammals present in the area.

<sup>viii</sup> Shipping and Navigation Technical Baseline defines the Study Area as a 10 nm buffer of the array, and 5 nm buffer of the offshore ECC.




Figure 23: Vessel Types – Winter 2020 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline).




Figure 24 Vessel Types – Summer 2021 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline).




Figure 25: Unique Vessels Per Day – Winter 2020 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline).




Figure 26: Unique Vessels Per Day – Summer 2021 Survey Period (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline).






Figure 27: Vessel Type Distribution – Winter 2020 and Summer 2021 Survey Periods combined (Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline).

219 During construction of the wind farm, a potential source of impact from increased vessel activity is physical trauma from collision with a boat or ship. These injuries include blunt trauma to the body or injuries consistent with propeller strikes. The risk of collision of marine mammals with vessels would be directly influenced by the type of vessel and the speed with which it is travelling (Laist et al. 2001) and indirectly by ambient noise levels underwater and the behaviour the marine mammal is engaged in.

220 There is currently a lack of information on the frequency of occurrence of vessel collisions as a source of marine mammal mortality, and there is little evidence from marine mammals stranded in the UK that injury from vessel collisions is an important source of mortality. The UK Cetacean Strandings Investigation Programme (CSIP) documents the annual number of reported strandings and the cause of death for those individuals examined at post-mortem. The CSIP data shows that very few strandings have been attributed to vessel collisions<sup>ix</sup>, therefore, while there is evidence that mortality from vessel collisions can and does occur, it is not considered to be a key source of mortality highlighted from post-mortem examinations.

<sup>ix</sup> (CSIP 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018)

- 221 Harbour porpoises, dolphins and seals are relatively small and highly mobile, and given observed responses to noise, are expected to detect vessels in close proximity and largely avoid collision. Predictability of vessel movement by marine mammals is known to be a key aspect in minimising the potential risks imposed by vessel traffic (Nowacek et al. 2001, Lusseau 2003, 2006). The Applicant has committed to the adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme<sup>x</sup>, Scottish Marine Wildlife Watching Code<sup>xi</sup> or Guide to Best Practice for Watching Marine Wildlife<sup>xii</sup>) during construction in order to minimise the potential for any impact. It is highly likely that a proportion of vessels will be stationary or slow moving throughout construction activities for significant periods of time. Therefore, the actual increase in vessel traffic moving around the site and to/from port to the site will occur over short periods of the offshore construction activity.
- 222 It is not expected that the level of vessel activity during construction would cause an increase in the risk of mortality from collisions. The commitment to the adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme<sup>xiii</sup>, Scottish Marine Wildlife Watching Code<sup>xiv</sup> or Guide to Best Practice for Watching Marine Wildlife<sup>xv</sup>) during construction will minimise the potential for any impact. Therefore, the risk of vessel collisions occurring is of **negligible** adverse magnitude.
- 223 All marine mammal receptors are deemed to be of low vulnerability given that vessel collision is not considered to be a key source of mortality highlighted from post-mortem examinations of stranded animals. However, should a collision event occur, this has the potential to kill the animal. As a result of the low vulnerability to a strike but the serious consequences of a strike, marine mammal receptors are considered to have a **high** sensitivity to vessel collisions.

---

<sup>x</sup> <https://www.wisescheme.org/>

<sup>xi</sup> <https://www.nature.scot/scottish-marine-wildlife-watching-code-smwwc-part-1>

<sup>xii</sup> <https://www.nature.scot/guide-best-practice-watching-marine-wildlife-smwwc-part-2>

<sup>xiii</sup> <https://www.wisescheme.org/>

<sup>xiv</sup> <https://www.nature.scot/scottish-marine-wildlife-watching-code-smwwc-part-1>

<sup>xv</sup> <https://www.nature.scot/guide-best-practice-watching-marine-wildlife-smwwc-part-2>



224 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **high**. Therefore, the significance of the effect of collisions from vessels is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

#### 7.10.8 Disturbance from construction vessels

225 As stated in 7.10.7, the area surrounding AyM already experiences high levels of vessel traffic (Figure 23 and Figure 24) (see Volume 2, Chapter 7: Shipping and Navigation for full details). Therefore, the introduction of additional vessels during construction AyM is not a novel impact for marine mammals present in the area.

226 Vessel noise levels from construction vessels will result in an increase in non-impulsive, continuous sound in the vicinity of the AyM array, typically in the range of 10 – 100 Hz (although higher frequencies may also be produced) (Sinclair et al. 2021) with an estimated source level of 161 – 168 SEL<sub>cum</sub> dB re 1 µPa@1m (RMS) for medium and large construction vessels travelling at a speed of 10 knots (Volume 4, Annex 6.2: Subsea Noise Technical Report).

227 Porpoise displacement has been observed up to 4 km from construction vessels (Benhemma-Le Gall et al. 2021). It is expected that other cetacean species will be displaced to a similar extent.

228 It is anticipated there will be a maximum of 99 construction vessels in total, of which 35 may be on site during peak periods. There are very few studies that indicate a critical level of activity in relation to risk of collisions but an analysis presented in Heinänen and Skov (2015) suggested that harbour porpoise density was significantly lower in areas with vessel transit rates of greater than 80 per day (within a 5 km<sup>2</sup> area). Even considering the existing levels of vessel traffic in the area, the addition of AyM construction traffic will still be well below this figure.

229 The commitment to the adoption of best practice vessel-handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme, Scottish Marine Wildlife Watching Code or Guide to Best Practice for Watching Marine Wildlife) during construction will minimise the potential for any impact. Therefore, the impact is expected to be of **low** adverse magnitude.

230 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low** (cetaceans) or **negligible** (grey seals). Therefore, the significance of the effect of disturbance from vessels is concluded to be of **minor adverse significance** for cetaceans and **negligible adverse significance** for grey seals, which is not significant in terms of the EIA regulations.

#### 7.10.9 Change in water quality from construction activities

231 Disturbance to water quality as a result of construction activities can have both direct and indirect impacts on marine mammals. Indirect impacts include effects on prey species (see section 7.10.10). Direct impacts include the impairment of visibility and therefore foraging ability which might be expected to reduce foraging success.

232 During construction of the project, sediment will be disturbed and released into the water column. This will give rise to suspended sediment plumes and localised changes in bed levels as material settles out of suspension. The main activities resulting in disturbance of seabed sediments are:

- Pre-lay cable trenching;
- Sandwave clearance;
- Cable installation;
- Dredge spoil disposal; and
- Drill arisings release.

233 The maximum distance (and therefore the overall spatial extent) that any local plume effects might be (temporarily) experienced can be reasonably estimated as the spring tidal excursion distance. The assessment provided in Volume 2, Chapter 2: Marine Geology, Oceanography and Physical Processes found that:

- Within 5 m of the activity, SSC might be millions of mg/l or more locally, i.e. more sediment than water in parts of the local plume. The effect is very localised and of very short duration.
- During the first half tidal cycle (~6 hours), the width of the plume increases through dispersion to 50-100 m, all non-silt sediments have settled to the seabed, and SSC consequentially reduces rapidly to 5-10 mg/l.

- 234 Marine mammals are well known to forage in tidal areas where water conditions are turbid and visibility conditions poor. For example, harbour porpoise and harbour seals in the UK have been documented foraging in areas with high tidal flows (Pierpoint 2008, Marubini et al. 2009, Hastie et al. 2016); therefore, low light levels, turbid waters and suspended sediments are unlikely to negatively impact marine mammal foraging success. It is important to note that it is hearing, not vision that is the primary sensory modality for most marine mammals. When the visual sensory systems of marine mammals are compromised, they are able to sense the environment in other ways, for example, seals can detect water movements and hydrodynamic trails with their mystacial vibrissae; while odontocetes primarily use echolocation to navigate and find food in darkness.
- 235 Any disturbance to the seabed will be localised and any resultant increase in SSC will be temporary so will be of **negligible** adverse magnitude. Short-term increased turbidity is not anticipated to impact marine mammals which rely primarily on hearing, resulting in **negligible** sensitivity to changes in water quality.
- 236 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **negligible**. Therefore, the significance of the effect of changes in water quality is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

#### 7.10.10 Change in fish abundance/distribution from construction activities

- 237 Given that marine mammals are dependent on fish prey, there is the potential for indirect effects on marine mammals as a result of impacts upon fish species or the habitats that support them. The key prey species for each marine mammal receptor are listed in Table 46.

- 238 During construction activities, there is the potential for fish mortality, PTS, TTS, behavioural impacts and auditory masking arising from low level continuous noise and vibration. The assessment of impacts upon fish species is presented in Volume 2, Chapter 6: Fish and Shellfish Ecology. The greatest impact is likely to be from UXO operations conducted as part of construction. Individual UXO detonations will have the potential to result in mortality, mortal injury, recoverable injury, TTS and disturbance to fish species, depending on the proximity of the individuals to the UXO location and the size of the UXO. Small scale mortality of fish as a result of UXO detonation are frequently recorded, with dead fish recorded floating at the surface in the immediate vicinity of the detonation. As such, this is expected to be a small-scale impact.
- 239 Direct damage and disturbance of subtidal habitat resulting from construction activities is predicted to directly impact approximately 9.49% of the total seabed area within the AyM draft Order Limits (see Volume 2, Chapter 6: Fish and Shellfish Ecology). Implementation of structures may result in habitat damage as well as direct damage to receptors e.g. crushing.
- 240 Fishing pressure may be reduced during construction at AyM due to the required safety distances around construction vessels and fishing effort may be displaced into the surrounding area. However, it would not be expected that any changes in fishing activities in this area would lead to changes in populations of these species as any increase would be very localised and any population level effects would be minimised by fisheries management measures.



Table 46: Key prey species of the marine mammal receptors (**bold** = species present at AyM).

|     | SITE     | KEY PREY SPECIES                                                                           | REFERENCE                                               |
|-----|----------|--------------------------------------------------------------------------------------------|---------------------------------------------------------|
| HP  | Scotland | Whiting, sandeel, haddock, saithe, pollock, Norway pout, poor-cod, cod, ling, blue whiting | Santos et al. (2004)                                    |
|     | Ireland  | Poor-cod, whiting, herring                                                                 | Berrow and Rogan (1995), Hernandez-Milian et al. (2011) |
| BND | Wales    | Mackerel, seabass, herring, whiting                                                        | Pesante et al. (2008), Nuuttila et al. (2017)           |
|     | Wales    | Seabass, salmon, conger eel, garfish, sandeel, small sharks                                | Evans and Hintner (2013)                                |
|     | Ireland  | Whiting, blue whiting, pollock, saithe, haddock, poor-cod                                  | Hernandez-Milian et al. (2011)                          |
|     | Scotland | Cod, saithe, whiting, salmon, haddock                                                      | Santos et al. (2001)                                    |
| CD  | UK       | Seabass, goby, cod, cephalopods, mackerel, lanternfish, blue whiting                       | Brophy et al. (2009)                                    |
| RD  | UK       | Cephalopods (octopus, cuttlefish, squid)                                                   | Clarke and Pascoe (1985)                                |
| MW  | Scotland | Sandeel, herring, sprat, mackerel, goby, Norway pout/poor cod                              | Pierce et al. (2004)                                    |
| GS  | Wales    | Cod, righteye flounders, large-tooth flounders, harbour porpoise                           | Nelms et al. (2019), Stringell et al. (2015)            |
|     | Wales    | Whiting, poor-cod, sole, herring                                                           | Evans and Hintner (2013)                                |

|  | SITE | KEY PREY SPECIES                                                  | REFERENCE   |
|--|------|-------------------------------------------------------------------|-------------|
|  | UK   | Sandeel, cod, whiting, haddock, ling, plaice, sole, flounder, dab | SCOS (2020) |



- 241 While there may be certain species that comprise the main part of their diet, all marine mammals in this assessment are considered to be generalist feeders and are thus not reliant on a single prey species (with the exception of Risso's dolphins which predominantly eat cephalopods). Therefore, they are assessed as having a **low** sensitivity to changes in prey abundance and distribution. The assessment provided in Volume 2, Chapter 6: Fish and Shellfish Ecology indicates that the overall adverse impacts to fish species from the construction of AyM will be of negligible to minor adverse significance and thus the predicted impact on marine mammals is of **negligible** adverse magnitude.
- 242 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of changes in fish abundance/distribution is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

## 7.11 Environmental assessment: operational phase

- 243 The impacts of the offshore operation and maintenance of AyM have been assessed on marine mammals. The environmental impacts arising from the operation and maintenance of Hornsea Four are listed in Table 18 along with the MDS against which each operation and maintenance phase impact has been assessed.

### 7.11.1 Barrier effects from operation

- 244 Potential barrier effects have been assessed at a number of previously constructed offshore windfarm sites. For example, at the Horns Rev and Nysted offshore wind farms in Denmark, long-term monitoring showed that both harbour porpoise and harbour seals were sighted regularly within the operational OWFs, and within two years of operation, the populations had returned to levels that were comparable with the wider area (Diederichs et al. 2008). Similarly, a monitoring programme at the Egmond aan Zee OWF in the Netherlands reported that significantly more porpoise activity was recorded within the OWF compared to the reference area during the operational phase (Scheidat et al. 2011), indicating the presence of the windfarm was not adversely affecting harbour porpoise presence. Other studies at Dutch and Danish OWFs (Lindeboom et al. 2011) also suggest that harbour porpoise may be attracted to increased foraging opportunities within operating offshore wind farms. In addition, recent tagging work by Russell et al. (2014) found that some tagged harbour and grey seals demonstrated grid-like movement patterns as these animals moved between individual WTGs, strongly suggestive of these structures being used for foraging.
- 245 Other reviews have also concluded that operational wind farm noise will have negligible effects (Madsen et al. 2006, Teilmann et al. 2006a, Teilmann et al. 2006b, CEFAS 2010, Brasseur et al. 2012). Based on results of studies conducted at other offshore windfarm locations, it is not anticipated that the AyM offshore windfarm will create a barrier to marine mammals and therefore will not prevent their access to or transit through the area.
- 246 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **negligible**. Therefore, the significance of barrier effects is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations

### 7.11.2 Collision risk from O&M vessels

- 247 As stated in 7.10.7, the area surrounding AyM already experiences a high amount of vessel traffic (Figure 23 and Figure 24) (see Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline for full details). Therefore, the introduction of additional vessels during O&M of AyM is not a novel impact for marine mammals present in the area.
- 248 Predictability of vessel movement by marine mammals is known to be a key aspect in minimising the potential risks imposed by vessel traffic (Nowacek et al. 2001, Lusseau 2003, 2006). The adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme<sup>xvi</sup>, Scottish Marine Wildlife Watching Code<sup>xvii</sup> or Guide to Best Practice for Watching Marine Wildlife<sup>xviii</sup>) will minimise the potential for any impact. Additional traffic during operations includes an increased frequency and greater variety of vessel types than in the construction phase e.g. jack-up vessels, SOV, small O&M vessels, lift vessels, cable maintenance vessels and auxiliary vehicles, and will take place over a longer period of time e.g. lifetime of AyM offshore windfarm (see Table 18 for maximum estimated annual round trips). Therefore, vessel traffic increase will be greater during this phase. However, it is still highly likely that a proportion of vessels will be stationary or slow moving throughout operations at AyM for significant periods of time.
- 249 It is not expected that the level of vessel activity during operations would cause an increase in the risk of mortality from collisions. The adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme, Scottish Marine Wildlife Watching Code or Guide to Best Practice for Watching Marine Wildlife) during O&M will minimise the potential for any impact. Therefore, the risk of vessel collisions occurring is of **negligible** adverse magnitude.

---

<sup>xvi</sup> <https://www.wisescheme.org/>

<sup>xvii</sup> <https://www.nature.scot/scottish-marine-wildlife-watching-code-smwwc-part-1>

<sup>xviii</sup> <https://www.nature.scot/guide-best-practice-watching-marine-wildlife-smwwc-part-2>

250 All marine mammal receptors are deemed to be of low vulnerability given that vessel collision is not considered to be a key source of mortality highlighted from post-mortem examinations of stranded animals. However, should a collision event occur, this has the potential to kill the animal, from which they have no ability to recover from. As a result of the low vulnerability to a strike but the serious consequences of a strike, marine mammal receptors are considered to have a **high** sensitivity to vessel collisions.

251 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **high**. Therefore, the significance of the effect of collisions from O&M vessels is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

### 7.11.3 Disturbance from O&M vessels

252 As stated in section 7.10.7, the area surrounding AyM already experiences a high amount of vessel traffic (Figure 23 and Figure 24) (see Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline for full details). Therefore, the introduction of additional vessels during O&M of AyM is not a novel impact for marine mammals present in the area.

253 Vessel noise levels from vessels during operations will result in an increase in non-impulsive, continuous sound in the vicinity of the AyM array, typically in the range of 10 – 100 Hz (although higher frequencies may also be produced) (Sinclair et al. 2021) with an estimated source level of 161 – 168 SEL<sub>cum</sub> dB re 1 µPa@1m (RMS). It is anticipated that numerous different vessel types would be conducting round trips to and from port and the AyM array area, but only two jack-up vessels and two SOVs would be present at any one time.



- 254 Heinänen and Skov (2015) suggested that harbour porpoise density was significantly lower in areas with vessel transit rates of greater than 80 per day (within a 5 km<sup>2</sup> area). Vessel traffic in the AyM area, even considering the addition of AyM O&M traffic will still be well below this figure. The adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme, Scottish Marine Wildlife Watching Code or Guide to Best Practice for Watching Marine Wildlife) during O&M will minimise the potential for any impact. Therefore, the impact is expected to be of **low** adverse magnitude.
- 255 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low** (cetaceans) or **negligible** (grey seals) (see sections 7.5.6 to 7.5.9). Therefore, the significance of the effect of disturbance from O&M vessels is concluded to be of **minor adverse significance** for cetaceans and **negligible adverse significance** for grey seals, which is not significant in terms of the EIA regulations.

#### 7.11.4 Change in water quality from operation

- 256 There are no changes to water quality indicated in Volume 2, Chapter 2: Marine Geology, Oceanography and Physical Processes or Chapter 3: Marine Water and Sediment Quality as a result of operations at AyM. Therefore, water quality is anticipated to have no impact on marine mammals during AyM operation.

#### 7.11.5 Change in fish abundance/distribution from operation

- 257 Any change in fish abundance and/or distribution as a result of AyM operations is important to assess as, given marine mammals are dependent on fish as prey species, there is the potential for indirect effect on marine mammals. The key prey species for each marine mammal receptor are listed in Table 46.

- 258 The presence of turbine infrastructure has the potential to impact on fish species by removing essential habitats (e.g. spawning, nursery and feeding habitats) (see Volume 2, Chapter 6: Fish and Shellfish Ecology). The AyM array area overlaps with sandeel spawning grounds, but comparable habitats are present and widespread within the wider area. The long-term habitat loss due to the presence of foundations, scour protection and cable protection is expected to be up to a maximum of 1.7 km<sup>2</sup>, which represents less than 0.1% of the fish and shellfish study area. The assessment provided in Volume 2, Chapter 6: Fish and Shellfish Ecology indicates that the overall adverse impacts to fish species from the operation of AyM will be of negligible to minor adverse significance and thus the predicted impact on marine mammals is of **negligible** adverse magnitude.
- 259 Fishing pressure in the AyM array area will be reduced as a result of operations due to advisory safety zones around infrastructure and the physical presence of the infrastructure preventing access to fishing vessels. Conversely, fishing pressure outside the AyM array area may be increased due to displacement. These effects will be highly localised and therefore will have a **negligible** adverse magnitude on prey availability for marine mammals.
- 260 While there may be certain species that comprise the main part of their diet, all marine mammals in this assessment are considered to be generalist feeders and are thus not reliant on a single prey species (with the exception of Risso's dolphins which predominantly eat cephalopods). Therefore, they are assessed as having a **low** sensitivity to changes in prey abundance and distribution.
- 261 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of changes in fish abundance/distribution during O&M is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.



## 7.12 Environmental assessment: decommissioning phase

262 The impacts of the offshore decommissioning of AyM have been assessed on marine mammals. The environmental impacts arising from the decommissioning of AyM are listed in Table 18 along with the MDS against which each decommissioning phase impact has been assessed. Decommissioning would involve the dismantling of structures and removal of offshore structures above the seabed, in reverse order to the construction sequence. The effects of these activities on marine mammals are considered to be similar to or less (as a result of there being no piling) than those occurring as a result of construction. Therefore, the effects of decommissioning are considered to be no greater than those described for the construction phase.

### 7.12.1 PTS and disturbance from decommissioning

263 It is envisaged that piled foundations would be cut below seabed level, and the protruding section removed. Typical current methods for cutting piles are abrasive water jet cutters or diamond wire cutting. The final method chosen shall be dependent on the technologies available at the time of decommissioning. The indicative methodology would be:

- Deployment of ROV's or divers to inspect each pile footing and reinstate lifting attachments if necessary.
- Mobilise a jack-up barge/heavy lifting vessel.
- Remove any scour protection or sediment obstructing the cutting process. It may be necessary to dig a small trench around the foundation.
- Deploy crane hooks from the decommissioning vessel and attach to the lift points.
- Cut piles at just below seabed level.
- Inspect seabed for debris and remove debris where necessary.
- Considering the current technology, the decommissioned components are likely to be transported back to shore by lifting onto a jack-up or heavy lift vessels, freighter, barge, or by buoyant tow.
- Transport all components to an onshore site where they will be processed for reuse/recycling/disposal.
- Inspect seabed and remove debris.

264 As the exact methods to be used for decommissioning are to be decided, the impact from PTS and disturbance levels of decommissioning activities cannot be accurately determined at this time. However, it is anticipated that with the implementation of embedded mitigation in the form of a Decommissioning Plan/Program and a MMMP specific to decommissioning activities (Table 19) the significance of these impacts will be reduced. The impacts of decommissioning activities will likely be similar or of a lesser extent than during piling in the construction phase and therefore will be of **negligible adverse significance** to **minor adverse significance**, which is not significant in terms of the EIA regulations.

### 7.12.2 Collision risk from decommissioning vessels

265 As stated in section 7.10.7, the area surrounding AyM already experiences a high amount of vessel traffic (Figure 23 and Figure 24) (see Volume 4, Annex 9.1: Navigational Risk Assessment Technical Baseline for full details). Therefore, the introduction of additional vessels during decommissioning of AyM is not a novel impact for marine mammals present in the area.

266 The adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme, Scottish Marine Wildlife Watching Code or Guide to Best Practice for Watching Marine Wildlife) during decommissioning will minimise the potential for any impact. It is assumed that similar vessel types and number will be present in the AyM array area as during the construction phase. Therefore, it is highly likely that a proportion of vessels will be stationary or slow moving throughout decommissioning activities for significant periods of time. Therefore, the actual increase in vessel traffic moving around the site and to/from port to the site will occur over short periods of the offshore decommissioning activity.

- 267 It is not expected that the level of vessel activity during decommissioning operations would cause an increase in the risk of mortality from collisions. The adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme<sup>xix</sup>, Scottish Marine Wildlife Watching Code<sup>xx</sup> or Guide to Best Practice for Watching Marine Wildlife<sup>xxi</sup>) will minimise the potential for any impact. Therefore, the risk of vessel collisions occurring is of **negligible** adverse magnitude.
- 268 All marine mammal receptors are deemed to be of low vulnerability given that vessel collision is not considered to be a key source of mortality highlighted from post-mortem examinations of stranded animals. However, should a collision event occur, this has the potential to kill the animal, from which they have no ability to recover from. As a result of the low vulnerability to a strike but the serious consequences of a strike, marine mammal receptors are considered to have a **high** sensitivity to vessel collisions.
- 269 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **high**. Therefore, the significance of the effect of collision risk from decommissioning vessels is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

### 7.12.3 Disturbance from decommissioning vessels

- 270 Vessel noise levels from decommissioning vessels will result in an increase in non-impulsive, continuous sound in the vicinity of the AyM array, typically in the range of 10 – 100 Hz (although higher frequencies may also be produced) (Sinclair et al. 2021) with an estimated source level of 161 – 168 SEL<sub>cum</sub> dB re 1 µPa@1m(RMS). It is anticipated that levels and types of vessel traffic during decommissioning would be similar to that during construction.

---

<sup>xix</sup> <https://www.wisescheme.org/>

<sup>xx</sup> <https://www.nature.scot/scottish-marine-wildlife-watching-code-smwwc-part-1>

<sup>xxi</sup> <https://www.nature.scot/guide-best-practice-watching-marine-wildlife-smwwc-part-2>

- 271 Heinänen and Skov (2015) suggested that harbour porpoise density was significantly lower in areas with vessel transit rates of greater than 80 per day (within a 5 km<sup>2</sup> area). Vessel traffic in the AyM area, even considering the addition of AyM decommissioning traffic will still be well below this figure. The adoption of best practice vessel handling protocols (e.g. following the Codes of Conduct provided by the WiSe Scheme, Scottish Marine Wildlife Watching Code or Guide to Best Practice for Watching Marine Wildlife) during decommissioning will minimise the potential for any impact. Therefore, the impact is expected to be of **low magnitude**.
- 272 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low** (cetaceans) or **negligible** (grey seals) (see sections 7.5.6 to 7.5.9). Therefore, the significance of the effect of disturbance from decommissioning vessels is concluded to be of **minor adverse significance** for cetaceans and **negligible adverse significance** for grey seals, which is not significant in terms of the EIA regulations.

#### 7.12.4 Change in water quality from decommissioning

- 273 During decommissioning, SSC could potentially be increased and associated deposition of material within the AyM array and the offshore ECC from the following activities:
- Removal of foundation structures;
  - Cutting off of monopiles and jacket foundation legs; and
  - (Possible) removal of cables from the intertidal zone.
- 274 Any disturbance to the seabed will be localised and any resultant increase in SSC will be temporary. The changes in SSC and resultant water quality during decommissioning are anticipated to be lesser than those associated with construction. Short-term increased turbidity is not anticipated to impact marine mammals which rely primarily on hearing, resulting in **negligible** sensitivity to changes in water quality.
- 275 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **negligible**. Therefore, the significance of the effect of changes in water quality is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.



### 7.12.5 Change in fish abundance/distribution from decommissioning

- 276 Any change in fish abundance and/or distribution as a result of AyM decommissioning is important to assess as, given marine mammals are dependent on fish as prey species, there is the potential for indirect effect on marine mammals. The key prey species for each marine mammal receptor are listed in Table 46. While there may be certain species that comprise the main part of their diet, all marine mammals in this assessment are considered to be generalist feeders and are thus not reliant on a single prey species (with the exception of Risso's dolphins which predominantly eat cephalopods). Therefore, they are assessed as having a **low** sensitivity to changes in prey abundance and distribution.
- 277 Decommissioning of offshore infrastructure for AyM may result in temporarily elevated underwater noise levels which may have effects on fish. However, the Volume 4, Annex 6.2: Subsea Noise Technical Report assesses the maximum noise levels to be far below that during pile driving during construction phase, therefore, the impacts would also be less. The assessment provided in Volume 2, Chapter 6: Fish and Shellfish Ecology indicates that the overall adverse impacts to fish species from the decommissioning of AyM will be of negligible adverse significance and thus the predicted impact on marine mammals is of **negligible** adverse magnitude.
- 278 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the effect of changes in fish abundance/distribution is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.

## 7.13 Environmental assessment: cumulative effects

- 279 Cumulative effects can be defined as effects upon a single receptor from AyM when considered alongside other proposed and reasonably foreseeable projects and developments. This includes all projects that result in a comparative effect that is not intrinsically considered as part of the existing environment and is not limited to offshore wind projects. A screening process has identified a number of reasonably foreseeable projects and developments which may act cumulatively with AyM. The full list of such projects that have been identified in relation to the offshore environment are set out in Volume 1, Annex 3.1: Cumulative Effects Assessment.
- 280 In assessing the potential cumulative impacts for AyM, it is important to bear in mind that some projects, predominantly those 'proposed' or identified in development plans, may not actually be taken forward, or fully built out as described within their MDS. There is, therefore, a need to build in some consideration of certainty (or uncertainty) with respect to the potential impacts which might arise from such proposals. For example, those projects under construction are likely to contribute to cumulative impacts (providing effect or spatial pathways exist), whereas those proposals not yet approved are less likely to contribute to such an impact, as some may not achieve approval or may not ultimately be built due to other factors.



281 With this in mind, all projects and plans considered alongside AyM have been allocated into 'tiers' reflecting their current stage within the planning and development process. This allows the cumulative impact assessment to present several future development scenarios, each with a differing potential for being ultimately built out. This approach also allows appropriate weight to be given to each scenario (tier) when considering the potential cumulative impact. The proposed tier structure is intended to ensure that there is a clear understanding of the level of confidence in the cumulative effects assessment (CEA). An explanation of each tier is included in Table 47. The proposed tier structure for marine mammals is different to that presented for other receptors. This is due to the need to take into account greater levels of uncertainty in the degree and timing of overlap of activities which will generate significant levels of underwater noise during the construction phase of projects. This is the established approach for marine mammal assessments and has been accepted by the Stakeholders and used in the most recent offshore wind farm EIAs in UK waters (for example: Hornsea Project Four PEIR Volume 2 Chapter 4, Norfolk Vanguard ES Volume 1 Chapter 12 and East Anglia Three ES Volume 1 Chapter 12).

**Table 47: Description of tiers of other developments considered within the marine mammal cumulative effect assessment.**

| TEIR   | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Tier 1 | <p>Operational and under construction projects which were not in place when baseline data was collected.</p> <p>Projects with a legally secure consent (i.e. projects which are not on hold subject to an ongoing judicial review process) that have been awarded a Contract for Difference (CFD) but have not yet been implemented.</p> <p>All Tier 1 offshore wind farm projects are due to be commissioned prior to the construction of AyM but will have an ongoing operational cumulative impact not considered part of the baseline. Therefore, there is no potential for the overlap in the construction and pile driving of these projects with the pile driving at AyM.</p> |

| TEIR   | DESCRIPTION                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |
|--------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|        | All other Tier 1 projects that were operational or ongoing at the time of the baseline data collection have been screened out of the assessment.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |
| Tier 2 | <p>Tier 2 includes all projects/plans that have a legally secure consent but have no CFD therefore there is uncertainty about the timeline for construction of these projects.</p> <p>Tier 2 offshore windfarms have the potential for cumulative operational and maintenance and decommissioning impacts. The potential for cumulative construction phase impacts have been considered where there is a reasonable chance of overlap of pile driving with AyM.</p>                                                                                                                                                                                                            |
| Tier 3 | <p>Tier 3 projects are projects for which an application has been submitted, but not yet determined. There is therefore information on which to base a quantitative assessment of cumulative impact but there is a degree of uncertainty as to the final approved design of the project and the timeline for construction.</p> <p>Tier 3 offshore wind farm projects have the potential for cumulative construction, operational and maintenance and decommissioning impacts with AyM.</p>                                                                                                                                                                                     |
| Tier 4 | <p>Tier 4 projects are relevant marine infrastructure projects that the regulatory body are expecting to be submitted for determination and for projects for which Preliminary Environmental Information Report (PEIR) has been submitted, but a full ES has not yet been submitted. There is, therefore, some information on which to base a quantitative assessment of cumulative impact but there is a large degree of uncertainty as to the final design of the project and the timeline for construction.</p> <p>Tier 4 offshore wind farm projects have the potential for cumulative construction, operational and maintenance and decommissioning impacts with AyM.</p> |
| Tier 5 | Tier 5 projects are relevant marine infrastructure projects that the regulatory body are expecting to be submitted for determination                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |

| TEIR | DESCRIPTION                                                                                                                                                                                                                                                                                                          |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
|      | <p>(e.g. projects listed under the Planning Inspectorate programme of projects). For Tier 5 projects there is a lot of uncertainty and not enough information to allow AyM to undertake an assessment.</p> <p>Projects that have low data confidence and no established timeline are screened out of assessment.</p> |

282 **Screening Projects:** The CEA methodology and long-list are described in Volume 1, Annex 3.1: Cumulative Effects Assessment. The long-list of projects, plans and activities was used to generate a list of projects initially screened into the marine mammal CEA. The long-list of projects was screened to remove all projects that have:

- ▲ no data available,
- ▲ no timeline available,
- ▲ no conceptual effect-receptor pathway,
- ▲ no physical effect-receptor overlap, and
- ▲ no temporal overlap.

283 Following this initial screening, as one or more of the above criteria applied, the following project types were all screened out of the marine mammal CEA:

- ▲ Aggregates and disposal,
- ▲ Commercial fisheries,
- ▲ Oil and gas,
- ▲ Shipping,
- ▲ Military, aviation and radar, and
- ▲ Coastal developments.

284 This resulted in only offshore energy projects being screened into the marine mammal CEA.

285 **Screening Impacts:** Certain impacts assessed for AyM alone are not considered in the marine mammal CEA due to:

- ▲ the highly localised nature of the impacts,

- management and mitigation measures in place at AyM and on other projects will reduce the risk occurring, and
- where the potential significance of the impact from AyM alone has been assessed as negligible.

286 The impacts excluded from the marine mammal CEA for these reasons are:

- Auditory injury (PTS): where PTS may result from activities such as pile driving and UXO clearance, suitable mitigation will be put in place to reduce injury risk to marine mammals to negligible levels (as a requirement of European Protected Species legislation)
- Collision with vessels: it is expected that all offshore energy projects will employ a vessel management plan or follow best practice guidance to reduce the already low risk of collisions with marine mammals
- Changes in water quality: highly localised and negligible significance
- Changes in prey availability: highly localised and negligible significance
- Barrier effects/ operational noise: highly localised and negligible significance.

287 Therefore, the impacts that are considered in the marine mammal CEA are as follows:

- The potential for disturbance from underwater noise during construction and decommissioning of offshore energy developments; and
- The potential for disturbance from vessel activity during construction, operation and decommissioning of offshore energy developments.

288 The MDS for the marine mammal CEA is described in Table 48. Projects with impacts that overlap with the AyM construction period (2026-2030 inclusive) or with impacts that are expected to occur 1 year before or after the AyM construction period are included in the assessment. This therefore limits the CEA to projects that have impact pathways predicted to occur between 2025 and 2031 inclusive.

Table 48: Cumulative MDS for marine mammals.

| POTENTIAL EFFECT | SCENARIO                                                                                                                                                                                                                                                                                                                                                      | JUSTIFICATION                                                                                                                                                                                                                                                                                                                                                 |
|------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| Disturbance      | <p>Underwater noise produced by construction (piling and UXO clearance) and decommissioning activities in combination with ongoing seismic activities.</p> <p>Included in CEA: Only projects where construction or decommissioning periods are expected to overlap with or occur <math>\pm 1</math> year either side of the construction activity at AyM.</p> | <p>Maximum potential for cumulative effects from underwater noise associated with offshore wind farm construction and decommissioning activities is considered within the relevant MU for each species. This spatial scale was chosen as a result of the spatial extent of noise related impacts as well as the high mobility of marine mammal receptors.</p> |
|                  | <p>Vessel activity during construction, O&amp;M and decommissioning.</p> <p>Included in CEA: All projects that have vessel activity between 2025-2031 that wasn't included in the baseline.</p>                                                                                                                                                               | <p>Maximum potential for cumulative effects from the increased risk of disturbance from an increase in vessel activity is considered within the relevant MU for each species. This spatial scale was chosen as a result of the high mobility of marine mammal receptors.</p>                                                                                  |

### 7.13.1 Disturbance from underwater noise

- 289 Only projects within the relevant species MU, where construction or decommissioning periods are expected to overlap with or occurring  $\pm 1$  year either side of the construction activity at AyM were screened into the CEA for disturbance from underwater noise. This therefore included all projects that are constructing or decommissioning between 2025-2031 inclusive (Table 50, Figure 28, and Table 51).
- 290 While the construction period for AyM covers a five-year period (Table 49), Year 1 (2026) is expected to be onshore construction activity only. Offshore construction work is not expected to commence until Year 2 (2027), and foundation installation activities (including UXO clearance and piling) could occur any time between 2027 and 2029 inclusive, but only for a 12-month period within that three-year window (expected indicative date is 2028). Therefore, the underwater noise impact from UXO and piling for AyM is limited to 2027-2029 inclusive (Table 49 and Table 51).
- 291 It has been conservatively assumed that pile driving and decommissioning activities can occur at any time during the construction or decommissioning phase identified for each Project.
- 292 Different OWF EIAs have assessed disturbance using a variety of thresholds and methods, including effective deterrence ranges, fixed noise thresholds and dose-response curves. This means that the predicted number of animals disturbed is not comparable between projects. In order to standardise the CEA approach, the assessment of disturbance from construction and decommissioning activities at OWF sites follows the advice provided in JNCC et al. (2020) where unabated pile driving of a monopile and clearance of a UXO is predicted to have an effective deterrence range of 26 km for harbour porpoise. It is assumed that the impact of decommissioning is the same or lower than that of construction, and therefore in the absence of a recommended EDR for decommissioning activities, the 26 km EDR has also been assumed. In the absence of recommended EDRs for other species, this has been applied to all marine mammals.



- 293 In order to quantify the number of animals predicted to experience disturbance at each OWF project, the SCANS III density (Hammond et al. 2017) for the corresponding survey block has been applied for each cetacean species. For grey seals, the average at-sea density (Carter et al. 2020) within the corresponding OWF Project (+ 26 km buffer) has been used.
- 294 The potential number of seismic surveys that could be undertaken is unknown. Therefore, it has been assumed that one seismic survey is conducted in the Irish Sea at any one time, and four seismic surveys are conducted within the North Sea at any one time (to account for concurrent surveys in the northern and southern North Sea in both UK waters and those of neighbouring North Sea nations). It has been assumed that the EDR for seismic surveys is 12 km as per the advice provided in JNCC et al. (2020). It is considered that this approach is sufficiently precautionary (i.e. it is unlikely that this number of seismic surveys will be occurring concurrently, less so concurrently with AyM construction) to also account for any behavioural disturbance resulting from high-resolution geophysical site surveys (HRGS) within relevant regions (e.g. to support wind farm development). While the potential for behavioural disturbance from HRGS is poorly understood, it is acknowledged to be of a considerably lower magnitude than that of seismic survey (e.g. precautionary 5 km EDR suggested in JNCC et al. 2020).
- 295 To quantify the number of minke whales predicted to experience disturbance from seismic surveys in the Irish Sea, SCANS III block E density estimate was used (0.017 whales/km<sup>2</sup>). To estimate the number of whales predicted to be disturbed from seismic surveys in the North Sea, the average density across the North Sea was calculated<sup>xxii</sup>.
- 296 To quantify the number of grey seals predicted to be disturbed by seismic surveys in the Irish Sea, the average at-sea density (Carter et al. 2020) for the Irish Sea was calculated.

---

<sup>xxii</sup> SCANS III estimate of 8,900 minke whales in the North Sea / 575,000 km<sup>2</sup> = 0.015 whales/km<sup>2</sup>

Table 49: Indicative construction schedule for AyM.

|                                                    | 2026 |   |   |   | 2027 |   |   |   | 2028 |   |   |   | 2029 |   |   |   | 2030 |   |   |   |
|----------------------------------------------------|------|---|---|---|------|---|---|---|------|---|---|---|------|---|---|---|------|---|---|---|
| ACTIVITY                                           | 1    | 2 | 3 | 4 | 1    | 2 | 3 | 4 | 1    | 2 | 3 | 4 | 1    | 2 | 3 | 4 | 1    | 2 | 3 | 4 |
| Onshore construction                               |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| Offshore substation installation & commissioning   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| Offshore export cable installation                 |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| Foundation installation                            |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| Array cable installation                           |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| Wind turbine installation                          |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| First generation                                   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| Offshore wind turbine and foundation commissioning |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |
| Commercial Operations                              |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |      |   |   |   |


grey = potential date range for activity, aqua = indicative duration, dark teal = indicative date

Table 50: Projects considered within the marine mammal CEA for disturbance from underwater noise, including relevant species (according to Management Units).

| TYPE | PROJECT               | STATUS                | DATA | TIER | IMPACT                | HP | BD | GS | RD, CD & MW |
|------|-----------------------|-----------------------|------|------|-----------------------|----|----|----|-------------|
| OWF  | North Hoyle           | Operational           | High | 1    | Decommissioning noise | Y  | Y  | Y  | Y           |
| OWF  | Blyth                 | Operational           | High | 1    | Decommissioning noise | N  | N  | N  | Y           |
| OWF  | Hornsea Project Four  | Application submitted | High | 3    | Construction noise    | N  | N  | N  | Y           |
| OWF  | Scroby Sands          | Operational           | High | 1    | Decommissioning noise | N  | N  | N  | Y           |
| OWF  | Hornsea Project Three | Consented             | High | 2    | Construction noise    | N  | N  | N  | Y           |
| OWF  | Sofia                 | Consented             | High | 1    | Construction noise    | N  | N  | N  | Y           |
| OWF  | Norfolk Vanguard West | Consented             | High | 2    | Construction noise    | N  | N  | N  | Y           |
| OWF  | East Anglia Two       | Application submitted | High | 3    | Construction noise    | N  | N  | N  | Y           |
| OWF  | East Anglia One North | Application submitted | High | 3    | Construction noise    | N  | N  | N  | Y           |
| OWF  | Norfolk Boreas        | Consented             | High | 2    | Construction noise    | N  | N  | N  | Y           |

| TYPE | PROJECT                  | STATUS                | DATA | TIER | IMPACT             | HP | BD | GS | RD, CD & MW |
|------|--------------------------|-----------------------|------|------|--------------------|----|----|----|-------------|
| OWF  | Norfolk Vanguard East    | Consented             | High | 2    | Construction noise | N  | N  | N  | Y           |
| OWF  | Dogger Bank C            | Consented             | High | 1    | Construction noise | N  | N  | N  | Y           |
| OWF  | Dublin Array             | In-planning           | Med  | 5    | Construction noise | Y  | Y  | Y  | Y           |
| OWF  | Erebus (floating)        | Application submitted | High | 3    | Construction noise | Y  | N  | Y  | Y           |
| SS   | Seismic survey Irish sea | Ongoing               | Low  | 5    | Survey noise       | Y  | Y  | Y  | Y           |
| SS   | Seismic survey North Sea | Ongoing               | Low  | 5    | Survey noise       | N  | N  | N  | Y           |





LEGEND

- Order Limits
- OWF Projects Considered

Data Source:  
Subacoustech Enviromental Ltd

PROJECT TITLE:

*AWEL Y MÔR OFFSHORE WINDFARM*

FIGURE TITLE: **Marine Mammal CEA  
Underwater Noise Disturbance**

| VER | DATE       | REMARKS   | Drawn | Checked |
|-----|------------|-----------|-------|---------|
| 1   | 10/03/2022 | For Issue | RRS   | RM      |
|     |            |           |       |         |

FIGURE NUMBER:

**Figure 28**

|                    |               |              |                    |
|--------------------|---------------|--------------|--------------------|
| SCALE: 1:2,500,000 | PLOT SIZE: A3 | DATUM: WGS84 | PROJECTION: UTM30N |
|--------------------|---------------|--------------|--------------------|

Fferm Wynt Alltraeth  
**AWEL Y MÔR**  
Offshore Wind Farm

Table 51: OWF projects constructing or decommissioning at the same time as AyM is constructing ( $\pm 1$  year), in addition to seismic surveys in the Irish Sea and the North Sea.

|           | AYM | NORTH HOYLE | BLYTH | HORNSEA 4 | SCROBY SANDS | HORNSEA 3 | SOFIA | NORFOLK VANGUARD W | NORFOLK VANGUARD E | EAST ANGLIA 2 | EAST ANGLIA 1N | NORFOLK BOREAS | DOGGER BANK C | DUBLIN ARRAY | EREBUS | SEISMIC (IRISH SEA) | SEISMIC (NORTH SEA) |
|-----------|-----|-------------|-------|-----------|--------------|-----------|-------|--------------------|--------------------|---------------|----------------|----------------|---------------|--------------|--------|---------------------|---------------------|
| Tier      |     | 1           | 1     | 3         | 1            | 2         | 1     | 2                  | 2                  | 3             | 3              | 2              | 1             | 5            | 3      | 5                   |                     |
| SCANS III | F   | F           | R     | O         | L            | O         | O/N   | O/L                | L                  | L             | L              | O/L            | O             | E            | D      | -                   |                     |
| 2025      |     |             |       | Of        |              | Of        | Of    | Of                 | Of                 | Of            | Of             | Of             | Of            | Of           |        | x1                  | x4                  |
| 2026      | On  |             | De    | Of        |              | Of        | Of    | Of                 | Of                 |               | Of             |                | Of            |              | Of     | x1                  | x4                  |
| 2027      | Of  |             | De    | Of        |              | Of        |       | Of                 | Of                 |               | Of             |                |               |              |        | x1                  | x4                  |
| 2028      | Of  |             |       | Of        |              | Of        |       | Of                 | Of                 |               |                |                |               |              |        | x1                  | x4                  |
| 2029      | Of  | De          |       | Of        |              | Of        |       |                    |                    |               |                |                |               |              |        | x1                  | x4                  |
| 2030      | Cm  | De          |       |           | De           | Of        |       |                    |                    |               |                |                |               |              |        | x1                  | x4                  |



|                                                                                                                       | AYM | NORTH HOYLE | BLYTH | HORNSEA 4 | SCROBY SANDS | HORNSEA 3 | SOFIA | NORFOLK VANGUARD W | NORFOLK VANGUARD E | EAST ANGLIA 2 | EAST ANGLIA 1N | NORFOLK BOREAS | DOGGER BANK C | DUBLIN ARRAY | EREBUS | SEISMIC (IRISH SEA) | SEISMIC (NORTH SEA) |
|-----------------------------------------------------------------------------------------------------------------------|-----|-------------|-------|-----------|--------------|-----------|-------|--------------------|--------------------|---------------|----------------|----------------|---------------|--------------|--------|---------------------|---------------------|
| 2031                                                                                                                  |     |             |       |           | De           | Of        |       |                    |                    |               |                |                |               |              |        | x1                  | x4                  |
| On = onshore construction, Of= offshore construction, De = decommissioning, Cm = turbine and foundation commissioning |     |             |       |           |              |           |       |                    |                    |               |                |                |               |              |        |                     |                     |

## Harbour porpoise

- 297 The only OWF projects in the Celtic and Irish Seas MU that are predicted to have a cumulative effect on harbour porpoise alongside AyM are decommissioning activities at North Hoyle, and construction activities at Dublin Array, alongside ongoing seismic surveys in the Irish Sea. The JCP Data Tool density estimate of 0.13 porpoise/km<sup>2</sup> was used to quantify the number of porpoise potentially disturbed at AyM and North Hoyle (as this was the higher than the SCANS III density estimate for the relevant survey block), while the SCANS III density estimate of 0.239 porpoise/km<sup>2</sup> was used to quantify the number of porpoise potentially disturbed at Dublin Array (different SCANS III survey block) and by ongoing seismic surveys in the Irish Sea (conservative to use higher density estimate of the two SCANS III survey blocks in the Irish Sea). The maximum number of animals predicted to be disturbed on any one day occurs when construction activities at AyM overlap with decommissioning activities at North Hoyle and ongoing seismic activity in the Irish Sea, resulting in up to 659 porpoise potentially disturbed (1.1% MU) (Table 52). Given the low number of porpoise predicted to be impacted, this is considered to be a **low** adverse magnitude.
- 298 As outlined in section 7.5.2, disturbance may temporarily affect harbour porpoise fertility and the probability of calf survival. Due to observed responsiveness to underwater noise, harbour porpoise are considered to have a **low** sensitivity to disturbance from low-frequency impulsive underwater noise.
- 299 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the CEA for disturbance from underwater noise to harbour porpoise is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

Table 52: Number of harbour porpoise disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing ( $\pm 1$  year).

|         | AYM               | NORTH HOYLE       | DUBLIN ARRAY | EREBUS | SEISMIC (IRISH SEA X1) | TOTAL | %MU  |
|---------|-------------------|-------------------|--------------|--------|------------------------|-------|------|
| DENSITY | 0.13 <sup>‡</sup> | 0.13 <sup>‡</sup> | 0.239*       | 0.118* | 0.239*                 |       |      |
| 2025    |                   |                   | 508          |        | 108                    | 616   | 1.0% |
| 2026    |                   |                   |              | 251    | 108                    | 359   | 0.6% |
| 2027    | 275               |                   |              |        | 108                    | 383   | 0.6% |
| 2028    | 275               |                   |              |        | 108                    | 383   | 0.6% |
| 2029    | 275               | 276               |              |        | 108                    | 659   | 1.1% |
| 2030    |                   | 276               |              |        | 108                    | 384   | 0.6% |
| 2031    |                   |                   |              |        | 108                    | 108   | 0.2% |

<sup>‡</sup> JCP Data Tool density estimate

\* SCANS III

## Bottlenose dolphin

- 300 The only OWF projects in the Irish Sea MU that are predicted to have a cumulative effect on bottlenose dolphins alongside AyM are decommissioning of North Hoyle, and construction of Dublin Array, alongside ongoing seismic surveys in the Irish Sea. The SCANS III density estimate of 0.008 dolphins/km<sup>2</sup> was used to quantify the number of bottlenose dolphins potentially disturbed. In terms of the number of animals disturbed, this simple EDR approach was considered to be comparable to the more complex assessment for AyM alone (paragraph 151 et. seq.): the assumption of 100% disturbance within the EDR of 26 km resulted in a similar number of animals predicted to be disturbed (n=17) as was predicted to experience behavioural disturbance from the AyM assessment of pile driving using a dose-response curve and the assumed dolphin density surface (n=23 for the installation of a monopile at the NW location).
- 301 The maximum number of animals predicted to be disturbed on any one day occurs when construction activities at AyM overlap with decommissioning activities at North Hoyle and ongoing seismic activity in the Irish Sea, resulting in up to 44 dolphins potentially disturbed (14.9% MU) (Table 53). Given the number of dolphins predicted to be impacted, this is assessed as a high magnitude. However, this is considered to be an overestimate as it is highly unlikely that pile driving activities at AyM would actually overlap temporally with decommissioning activities at North Hoyle.

- 302 While the CEA has conservatively assumed AyM construction activities between 2027 to 2019, in reality the piling of foundations is expected to occur in a 12-month period (likely in 2028) with UXO clearance sometime in the year prior to piling, and thus is likely that the piling activities will be complete before the decommissioning activities at North Hoyle commence. In addition, the assumption of an EDR of 26 km from decommissioning activities is highly precautionary. It is expected that most decommissioning work would involve cutting techniques such as diamond wire cutting, which is highly unlikely to disturb any species of marine mammal (Panjerc et al. 2016). Furthermore, an EDR of 26 km relates to guidance for harbour porpoise (JNCC et al. 2020), which are known to show a greater extent of behavioural disturbance to impulsive underwater noise than bottlenose dolphins. Taking these overestimates and precautions into account, it is more likely that the cumulative impact is of **medium** adverse magnitude.
- 303 As outlined in section 7.5.3, disturbance from underwater noise may result in disturbance to bottlenose dolphins at a small spatial and temporal scale, and as such, they are considered to have a **low** sensitivity to disturbance from low-frequency impulsive underwater noise.
- 304 The magnitude of the impact has been assessed as **medium** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the CEA for disturbance from underwater noise to bottlenose dolphins is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

Table 53: Number of bottlenose dolphins disturbed (per day of impact) for OWF projects under construction or decommissioning and ongoing seismic surveys at the same time as AyM is under construction ( $\pm 1$  year).

|         | AYM | NORTH HOYLE | DUBLIN ARRAY | SEISMIC (IRISH SEA X1) | TOTAL | % MU  |
|---------|-----|-------------|--------------|------------------------|-------|-------|
| DENSITY |     | 0.008*      | 0.008*       | 0.008*                 |       |       |
| 2025    |     |             | 17           | 4                      | 21    | 7.0%  |
| 2026    |     |             |              | 4                      | 4     | 1.2%  |
| 2027    | 23  |             |              | 4                      | 27    | 9.1%  |
| 2028    | 23  |             |              | 4                      | 27    | 9.1%  |
| 2029    | 23  | 17          |              | 4                      | 44    | 14.9% |
| 2030    |     | 17          |              | 4                      | 21    | 7.0%  |
| 2031    |     |             |              | 4                      | 4     | 1.2%  |

\* No bottlenose dolphin density for SCANS III Block F. Used adjacent Block E.

## Risso's dolphin

305 Most of the OWF projects screened into the CEA for Risso's dolphins are in the North Sea, where the SCANS III density estimate was 0.0 dolphins/km<sup>2</sup> (blocks R, O, L and N). Therefore, even though these North Sea projects are screened in, as they are within the Celtic and Greater North Sea MU, they are predicted to have no cumulative impact on the Risso's dolphin MU. Therefore, the only OWF projects that are predicted to have a cumulative effect alongside AyM are decommissioning of North Hoyle and construction of Dublin Array, alongside ongoing seismic surveys in the Irish Sea. The maximum number of animals predicted to be disturbed on any one day occurs when construction activities at AyM overlap with decommissioning activities at North Hoyle and ongoing seismic activity in the Irish Sea, resulting in up to 145 dolphins potentially disturbed (1.2% MU) (Table 54). Given the number of dolphins predicted to be impacted, this is considered to be a **medium** adverse magnitude.



306 As outlined in section 7.5.3, there is no evidence on the sensitivity of Risso's dolphins to disturbance from underwater noise. Risso's dolphins are categorised as being in the high-frequency cetacean hearing group (Southall et al. 2019) along with bottlenose dolphins; therefore, it is considered appropriate, given the lack of species-specific data, to use bottlenose dolphins as a proxy. Therefore, Risso's dolphins are considered to have a **low** sensitivity to disturbance from low-frequency impulsive underwater noise.

307 The magnitude of the impact has been assessed as **medium** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the CEA for disturbance from underwater noise to Risso's dolphins is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

## Common dolphin

308 Most of the OWF projects screened into the CEA for common dolphins are in the North Sea, where the SCANS III density estimate was 0.0 dolphins/km<sup>2</sup> (blocks R, O, L and N). Therefore, even though these North Sea projects are screened in, as they are within the Celtic and Greater North Sea MU, they are predicted to have no cumulative impact on the common dolphin MU. Therefore, the only OWF projects that are predicted to have a cumulative effect alongside AyM are decommissioning of North Hoyle and construction of Dublin Array and Erebus, alongside ongoing seismic surveys in the Irish Sea. The maximum number of animals predicted to be disturbed on any one day occurs prior to the construction of AyM, when construction activities at Erebus overlaps with seismic surveys in the the Irish Sea, resulting in predicted impact to 799 common dolphins (1.2% MU) (Table 55). Given the number of dolphins predicted to be impacted, this is considered to be a **low** adverse magnitude.

## Minke whale

- 309 The maximum number of animals predicted to be disturbed on any one day occurs when construction activities at Hornsea Project Four, Hornsea Project Three, Sofia, Norfolk Vanguard West, Dogger Bank C, Erebus, ongoing seismic surveys in both the Irish Sea and the North Sea and decommissioning activities at Blyth, resulting in up to 269 minke whales potentially disturbed (1.3% MU) (Table 56). Given the number of whales predicted to be impacted, this is considered to be a **medium** adverse magnitude. However, it is worth noting that this is considered to be an overestimate since it is extremely unlikely that all of these activities would occur on the same day.
- 310 As outlined in section 7.5.4, there is a lack of evidence of strong behavioural responses of minke whales to piling noise. Given the limited data that is available on minke whale responses to vessel and sonar signals, they are considered to have a **low** sensitivity to disturbance from low-frequency impulsive underwater noise.
- 311 The magnitude of the impact has been assessed as **medium** adverse and the sensitivity of receptors as **low**. Therefore, the significance of the CEA for disturbance from underwater noise to minke whales is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

Table 54: Number of Risso's dolphins disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing (± 1 year).

|         | AYM    | NORTH HOYLE | BLYTH | HORNSEA 4 | SCROBY SANDS | HORNSEA 3 | SOFIA | NVG W | NVG E | EAST ANGLIA 2 | EAST ANGLIA 1N | NORFOLK BOREAS | DOGGER BANK C | DUBLIN ARRAY | EREBUS | SS (IRISH SEA X1) | SS (NORTH SEA X4) | TOTAL PER DAY | % MU |
|---------|--------|-------------|-------|-----------|--------------|-----------|-------|-------|-------|---------------|----------------|----------------|---------------|--------------|--------|-------------------|-------------------|---------------|------|
| Density | 0.031* | 0.031*      | 0.00  | 0.00      | 0.00         | 0.00      | 0.00  | 0.00  | 0.00  | 0.00          | 0.00           | 0.00           | 0.00          | 0.031        | 0.00   | 0.031             | 0.00              |               |      |
| 2025    |        |             |       | 0         |              | 0         | 0     | 0     | 0     | 0             | 0              | 0              | 0             | 66           |        | 14                | 0                 | 80            | 0.7% |
| 2026    |        |             | 0     | 0         |              | 0         | 0     | 0     | 0     |               | 0              |                | 0             |              | 0      | 14                | 0                 | 14            | 0.1% |
| 2027    | 65     |             | 0     | 0         |              | 0         |       | 0     | 0     |               | 0              |                |               |              |        | 14                | 0                 | 79            | 0.6% |
| 2028    | 65     |             |       | 0         |              | 0         |       | 0     | 0     |               |                |                |               |              |        | 14                | 0                 | 79            | 0.6% |
| 2029    | 65     | 66          |       | 0         |              | 0         |       |       |       |               |                |                |               |              |        | 14                | 0                 | 145           | 1.2% |
| 2030    |        | 66          |       |           | 0            | 0         |       |       |       |               |                |                |               |              |        | 14                | 0                 | 80            | 0.7% |
| 2031    |        |             |       |           | 0            | 0         |       |       |       |               |                |                |               |              |        | 14                | 0                 | 14            | 0.1% |

\* No Risso's dolphin density for SCANS III Block F. Used adjacent Block E density as per AyM assessment

Table 55: Number of common dolphins disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing (± 1 year).

|         | AYM    | NORTH HOYLE | BLYTH | HORNSEA 4 | SCROBY SANDS | HORNSEA 3 | SOFIA | NVG W | NVG E | EAST ANGLIA 2 | EAST ANGLIA 1N | NORFOLK BOREAS | DOGGER BANK C | DUBLIN ARRAY | EREBUS | SS (IRISH SEA X1) | SS (NORTH SEA X4) | TOTAL PER DAY | % MU |
|---------|--------|-------------|-------|-----------|--------------|-----------|-------|-------|-------|---------------|----------------|----------------|---------------|--------------|--------|-------------------|-------------------|---------------|------|
| Density | 0.0081 | 0.0081      | 0.00  | 0.00      | 0.00         | 0.00      | 0.00  | 0.00  | 0.00  | 0.00          | 0.00           | 0.00           | 0.00          | 0.0081       | 0.3743 | 0.0081            | 0.00              |               |      |
| 2025    |        |             |       | 0         |              | 0         | 0     | 0     | 0     | 0             | 0              | 0              | 0             | 17           |        | 4                 | 0                 | 21            | 0.0% |

|      | AYM | NORTH HOYLE | BLYTH | HORNSEA 4 | SCROBY SANDS | HORNSEA 3 | SOFIA | NVG W | NVG E | EAST ANGLIA 2 | EAST ANGLIA 1N | NORFOLK BOREAS | DOGGER BANK C | DUBLIN ARRAY | EREBUS | SS (IRISH SEA X1) | SS (NORTH SEA X4) | TOTAL PER DAY | % MU |
|------|-----|-------------|-------|-----------|--------------|-----------|-------|-------|-------|---------------|----------------|----------------|---------------|--------------|--------|-------------------|-------------------|---------------|------|
| 2026 |     |             | 0     | 0         |              | 0         | 0     | 0     | 0     |               | 0              |                | 0             |              | 795    | 4                 | 0                 | 799           | 1.2% |
| 2027 | 17  |             | 0     | 0         |              | 0         |       | 0     | 0     |               | 0              |                |               |              |        | 4                 | 0                 | 21            | 0.0% |
| 2028 | 17  |             |       | 0         |              | 0         |       | 0     | 0     |               |                |                |               |              |        | 4                 | 0                 | 21            | 0.0% |
| 2029 | 17  | 17          |       | 0         |              | 0         |       |       |       |               |                |                |               |              |        | 4                 | 0                 | 38            | 0.1% |
| 2030 |     | 17          |       |           | 0            | 0         |       |       |       |               |                |                |               |              |        | 4                 | 0                 | 21            | 0.0% |
| 2031 |     |             |       |           | 0            | 0         |       |       |       |               |                |                |               |              |        | 4                 | 0                 | 4             | 0.0% |

Table 56: Number of minke whales disturbed (per day of impact) for OWF projects constructing or decommissioning and ongoing seismic surveys at the same time as AyM is constructing ( $\pm 1$  year).

|         | AYM    | NORTH HOYLE | BLYTH | HORNSEA 4 | SCROBY SANDS | HORNSEA 3 | SOFIA | NVG W | NVGE | EAST ANGLIA 2 | EAST ANGLIA 1N | NORFOLK BOREAS | DOGGER BANK C | DUBLIN ARRAY | EREBUS | SS (IRISH SEA X1) | SS NORTH SEA X4)   | TOTAL PER DAY | % MU |
|---------|--------|-------------|-------|-----------|--------------|-----------|-------|-------|------|---------------|----------------|----------------|---------------|--------------|--------|-------------------|--------------------|---------------|------|
| Density | 0.017* | 0.017*      | 0.039 | 0.01      | 0.00         | 0.01      | 0.02  | 0.01  | 0.00 | 0.00          | 0.00           | 0.01           | 0.01          | 0.017        | 0.0112 | 0.017             | 0.015 <sup>x</sup> |               |      |
| 2025    |        |             |       | 21        |              | 21        | 42    | 21    | 0    | 0             | 0              | 21             | 21            | 36           |        | 8                 | 27                 | 220           | 1.1% |
| 2026    |        |             | 83    | 21        |              | 21        | 42    | 21    | 0    |               | 0              |                | 21            |              | 24     | 8                 | 27                 | 269           | 1.3% |
| 2027    | 36     |             | 83    | 21        |              | 21        |       | 21    | 0    |               | 0              |                |               |              |        | 8                 | 27                 | 217           | 1.1% |
| 2028    | 36     |             |       | 21        |              | 21        |       | 21    | 0    |               |                |                |               |              |        | 8                 | 27                 | 135           | 0.7% |
| 2029    | 36     | 36          |       | 21        |              | 21        |       |       |      |               |                |                |               |              |        | 8                 | 27                 | 150           | 0.7% |

|                                                                                            | AYM | NORTH HOYLE | BLYTH | HORNSEA 4 | SCROBY SANDS | HORNSEA 3 | SOFIA | NVG W | NVGE | EAST ANGLIA 2 | EAST ANGLIA 1N | NORFOLK BOREAS | DOGGER BANK C | DUBLIN ARRAY | EREBUS | SS (IRISH SEA X1) | SS NORTH SEA X4) | TOTAL PER DAY | % MU |
|--------------------------------------------------------------------------------------------|-----|-------------|-------|-----------|--------------|-----------|-------|-------|------|---------------|----------------|----------------|---------------|--------------|--------|-------------------|------------------|---------------|------|
| 2030                                                                                       |     | 36          |       |           | 0            | 21        |       |       |      |               |                |                |               |              |        | 8                 | 27               | 128           | 0.6% |
| 2031                                                                                       |     |             |       |           | 0            | 21        |       |       |      |               |                |                |               |              |        | 8                 | 27               | 56            | 0.3% |
| * No minke whale density for SCANS III Block F. Used adjacent Block E density.             |     |             |       |           |              |           |       |       |      |               |                |                |               |              |        |                   |                  |               |      |
| * Average minke whale density in the North Sea (SCANS III estimate of 8,900 / 575,000 km2) |     |             |       |           |              |           |       |       |      |               |                |                |               |              |        |                   |                  |               |      |

## Grey seal

- 312 The only OWF projects in the MU that are predicted to have a cumulative effect on grey seals alongside AyM are decommissioning activities at North Hoyle, and construction activities at Dublin Array and Erebus, alongside ongoing seismic surveys in the Irish Sea. The maximum number of animals predicted to be disturbed on any one day occurs when construction activities at AyM overlap with decommissioning activities at North Hoyle and ongoing seismic activities in the Irish Sea, resulting in up to 1,593 grey seals potentially disturbed (2.4% MU) (Table 57).
- 313 However, as outlined above for bottlenose dolphins, this is considered to be an overestimate as it is highly unlikely that pile driving activities at AyM would actually overlap temporally with decommissioning activities at North Hoyle. In addition, the assumption of an EDR of 26 km from decommissioning activities is highly precautionary. The EDR of 26 km was recommended for harbour porpoise, which is considerably more sensitive to underwater noise and disturbance than grey seals (Booth et al. 2019). Using the seal dose-response curve to estimate the number of grey seals potentially disturbed by piling activities at AyM, only 81 grey seals are predicted to be impacted, which is considerably less than the estimate obtained using the EDR approach (913). Therefore, it is realistic to assume that the number of grey seals predicted to be disturbed at North Hoyle is also a vast overestimate using the 26 km EDR method. Given the proximity of North Hoyle to AyM it is expected that the number of grey seals predicted to be disturbed by decommissioning activities at North Hoyle would be similar to the number predicted for construction activities at AyM, and thus in reality it is more likely that <100 grey seals would be impacted by decommissioning activities at North Hoyle. This more realistic assumption of impact is considered to be of **medium** adverse magnitude.
- 314 As outlined in section 7.5.5, grey seals are considered to have a **negligible** sensitivity to disturbance from underwater noise.
- 315 The magnitude of the impact has been assessed as **medium** adverse and the sensitivity of receptors as **negligible**. Therefore, the significance of the CEA for disturbance from underwater noise to grey seals is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.



Table 57: Number of grey seals disturbed (per day of impact) for OWF projects under construction or decommissioning and ongoing seismic surveys at the same time as AyM is under construction ( $\pm 1$  year).

|         | AYM | NORTH HOYLE | DUBLIN ARRAY | EREBUS | SS IRISH SEA X1 | TOTAL | % MU |
|---------|-----|-------------|--------------|--------|-----------------|-------|------|
| Density |     | 0.68        | 0.26         |        | 0.15            |       |      |
| 2025    |     |             | 552          |        | 68              | 620   | 0.9% |
| 2026    |     |             |              | 87     | 68              | 155   | 0.2% |
| 2027    | 81  |             |              |        | 68              | 149   | 0.2% |
| 2028    | 81  |             |              |        | 68              | 149   | 0.2% |
| 2029    | 81  | 1444        |              |        | 68              | 1593  | 2.4% |
| 2030    |     | 1444        |              |        | 68              | 1512  | 2.3% |
| 2031    |     |             |              |        | 68              | 68    | 0.1% |

316 In conclusion, the CEA for disturbance from underwater noise to all marine mammal receptors is to be of **negligible adverse significance** to **minor adverse significance**, which is not significant in terms of the EIA regulations.

### 7.13.2 Disturbance from vessel activity

317 This CEA considers the effects of increased vessel noise causing disturbance to marine mammals, due to the potential increase in vessel movements from the construction of AyM alongside expected vessel activity for other planned or existing projects, plans and activities.

318 Most projects were screened out of assessment of disturbance from vessels for the following reasons:

- ▲ Project was operational during the baseline,

- ▲ Project was under construction during the baseline (assumed that vessel levels would be lower during the O&M phase and as such the worst case had been included already), and
- ▲ No timeline data available for the project.

- 319 **Bottlenose dolphin:** The list of projects screened into the assessment of disturbance from vessels are almost all located in the North Sea, and therefore are not within the relevant MU for bottlenose dolphins (Table 58). Most of the projects that are relevant for these species (Dublin Array, Arklow Bank phase 2 and WestWave demo) are Tier 5 projects that have submitted a Scoping Report but where no other data are available upon which to base a quantitative assessment. Therefore, it is not possible to conduct a quantitative cumulative impact for these species from vessel disturbance at these projects.
- 320 **Harbour porpoise & grey seal:** The list of projects screened into the assessment of disturbance from vessels are almost all located in the North Sea, and therefore are not within the relevant MUs for harbour porpoise or grey seals (Table 58). Most of the projects that are relevant for these species (Dublin Array, Arklow Bank phase 2 and WestWave demo) are Tier 5 projects that have submitted a Scoping Report but where no other data are available upon which to base a quantitative assessment. Therefore, it is not possible to conduct a quantitative cumulative impact for these species from vessel disturbance at these projects. Project Erebus is the only development for which vessel information is available, and vessel activity at this project is expected to be low (maximum of 6 vessels on site at any one time during construction). The magnitude of the impact has been assessed as **negligible** adverse.
- 321 **Risso's dolphin, common dolphin & minke whale:** The list of projects included in the assessment of disturbance from vessels are almost all located in the North Sea, however, given that the relevant MUs for Risso's dolphins, common dolphins and minke whales is the Celtic and Greater North Seas, these Projects are screened in for these two species (Table 58). Table 59 presents the quantitative information that is available for all projects screened into the CEA for vessel disturbance, covering the construction and/or O&M phase vessel types, numbers and movements expected for each project.

- 322 It is extremely difficult to quantify reliably the level of increased noise-related disturbance to marine mammals resulting from increased vessel activity on a cumulative basis given the large degree of temporal and spatial variation in vessel movements between projects and regions, coupled with the spatial and temporal variation in marine mammal movements across the region. Vessel routes to and from offshore windfarms and other projects will use existing vessel routes where marine mammals will be accustomed to, and potentially habituated to regular vessel movements and therefore the additional risk is confined mainly to construction sites. Vessel movements within construction areas are likely to be limited and relatively slow. In addition, most projects are likely to adopt vessel management plans or follow best practice guidance in order to minimise any potential effects on marine mammals. Therefore, increases in underwater noise from vessels from offshore energy projects are likely to be small in relation to current and ongoing levels of shipping.
- 323 **Risso's dolphin:** The cumulative impact of increased underwater noise from vessels is predicted to be of local spatial extent, long term duration (vessel presence expected throughout the lifespan of a windfarm), intermittent (vessel activity will not be constant) and reversible (disturbance effects are temporary). However, given that the projects included quantitatively here are all located in the North Sea, where Risso's dolphins are expected to be virtually absent, the impact is predicted to be of **negligible** adverse magnitude.
- 324 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **low** (section 7.5.7). Therefore, the significance of the CEA for disturbance from vessel noise to Risso's dolphins is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.
- 325 **Common dolphin:** The cumulative impact of increased underwater noise from vessels is predicted to be of local spatial extent, long term duration (vessel presence expected throughout the lifespan of a windfarm), intermittent (vessel activity will not be constant) and reversible (disturbance effects are temporary). However, given that the projects included quantitatively here are all located in the North Sea, where common dolphins are expected to be virtually absent, the impact is predicted to be of **negligible** adverse magnitude.

- 326 The magnitude of the impact has been assessed as **negligible** adverse and the sensitivity of receptors as **low** (section 7.5.7). Therefore, the significance of the CEA for disturbance from vessel noise to common dolphins is concluded to be of **negligible adverse significance**, which is not significant in terms of the EIA regulations.
- 327 **Minke whale:** The cumulative impact of increased underwater noise from vessels is predicted to be of local spatial extent, long term duration (vessel presence expected throughout the lifespan of a windfarm), intermittent (vessel activity will not be constant) and reversible (disturbance effects are temporary). The low level of predicted additional disturbance is not expected to have a significant effect on the trajectory of the minke whale population. It is therefore predicted that the impact will be of **low** adverse magnitude.
- 328 The magnitude of the impact has been assessed as **low** adverse and the sensitivity of receptors as **low** (section 7.5.8). Therefore, the significance of the CEA for disturbance from vessel noise to minke whales is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.

Table 58: Projects considered within the marine mammal CEA for disturbance from vessel activity.

| TYPE | PROJECT               | STATUS                | DATA | TIER | VESSEL IMPACT      | HP | BD | GS | RD, CD & MW |
|------|-----------------------|-----------------------|------|------|--------------------|----|----|----|-------------|
| OWF  | Hornsea Project Four  | Application submitted | High | 3    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | Dogger Bank B         | Consented             | High | 1    | O&M                | N  | N  | N  | Y           |
| OWF  | Dogger Bank A         | Consented             | High | 1    | O&M                | N  | N  | N  | Y           |
| OWF  | Hornsea Project Three | Consented             | High | 2    | Construction       | N  | N  | N  | Y           |
| OWF  | Sofia                 | Consented             | High | 1    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | Norfolk Vanguard West | Consented             | High | 2    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | East Anglia Two       | Application submitted | High | 3    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | East Anglia One North | Application submitted | High | 3    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | Norfolk Boreas        | Consented             | High | 2    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | Norfolk Vanguard East | Consented             | High | 2    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | East Anglia Three     | Consented             | High | 1    | O&M                | N  | N  | N  | Y           |



| TYPE | PROJECT             | STATUS                | DATA | TIER | VESSEL IMPACT      | HP | BD | GS | RD, CD & MW |
|------|---------------------|-----------------------|------|------|--------------------|----|----|----|-------------|
| OWF  | Dogger Bank C       | Consented             | High | 1    | Construction & O&M | N  | N  | N  | Y           |
| OWF  | Dublin Array        | In-planning           | Low  | 5    | Construction & O&M | Y  | Y  | Y  | Y           |
| OWF  | Erebus              | Application submitted | High | 3    | Construction & O&M | Y  | N  | Y  | Y           |
| OWF  | Arklow Bank Phase 2 | In-planning           | Low  | 5    | O&M                | Y  | Y  | Y  | Y           |
| OWF  | WestWave Demo       | In development        | Med  | 2    | O&M                | Y  | N  | Y  | Y           |

OWF = offshore windfarm, O&M = operational and maintenance, HP = harbour porpoise, BD = bottlenose dolphin, GS = grey seal, RD = Risso's dolphin, MW = minke whale, Y/N denotes whether a project is within the species MU

Table 59: Level of vessel activity anticipated for each project included in the marine mammal CEA.

| PROJECT              | CONSTRUCTION VESSELS |    |             | O&M VESSELS                                                                                                                |     |                              | NOTES                                                    |
|----------------------|----------------------|----|-------------|----------------------------------------------------------------------------------------------------------------------------|-----|------------------------------|----------------------------------------------------------|
|                      | TYPE                 | #  | ROUND TRIPS | TYPE                                                                                                                       | #   | ROUND TRIPS                  |                                                          |
| Hornsea Project Four | Installation         | 10 | 240         | Supply vessels & other vessels for visits to wind turbine, turbine foundations, platform visits, jack-up and crew transfer | N/S | 2580 for WTG                 | Turbine Foundation - 12 months                           |
|                      | Support              | 79 | 2122        |                                                                                                                            |     | 780 for foundation           | Turbine - 24 months<br>Substation foundation - 12 months |
|                      | Transport/feeder     | 72 | 1020        |                                                                                                                            |     | 65 for platform - Structural | Substation - 12 months                                   |



| PROJECT               | CONSTRUCTION VESSELS                                         |     |             | O&M VESSELS       |    |                               | NOTES                                                 |
|-----------------------|--------------------------------------------------------------|-----|-------------|-------------------|----|-------------------------------|-------------------------------------------------------|
|                       | TYPE                                                         | #   | ROUND TRIPS | TYPE              | #  | ROUND TRIPS                   |                                                       |
|                       | Main laying                                                  | 6   | 300         |                   |    | 100 for platform - Electrical | IAC & OIC - 24 months<br>OEC - 24 months              |
|                       | Main burying                                                 | 6   | 300         |                   |    | 260 crew shift transfer       |                                                       |
|                       | Main jointing                                                | 3   | 72          |                   |    | 124 jack-up visits            |                                                       |
|                       | TOTAL                                                        | 176 | 4054        |                   |    | 3909                          |                                                       |
| Dogger Bank B         | Construction screened out                                    |     |             | Large O&M         | 3  | 50                            | Max. 28 vessels on site at any time                   |
|                       |                                                              |     |             | Small O&M         | 13 | 440                           |                                                       |
|                       |                                                              |     |             | Lift              | 2  | 40                            |                                                       |
|                       |                                                              |     |             | Cable maintenance | 2  | 3                             |                                                       |
|                       |                                                              |     |             | Auxiliary         | 8  | 150                           |                                                       |
|                       |                                                              |     |             | TOTAL             | 28 | 683                           |                                                       |
| Dogger Bank A         | Construction screened out                                    |     |             | Large O&M         | 3  | 50                            | Max. 28 vessels on site at any time                   |
|                       |                                                              |     |             | Small O&M         | 13 | 440                           |                                                       |
|                       |                                                              |     |             | Lift              | 2  | 40                            |                                                       |
|                       |                                                              |     |             | Cable maintenance | 2  | 3                             |                                                       |
|                       |                                                              |     |             | Auxiliary         | 8  | 150                           |                                                       |
|                       |                                                              |     |             | TOTAL             | 28 | 683                           |                                                       |
| Hornsea Project Three | Installation                                                 | 9   | 638         | O&M screened out  |    |                               | Up to 8 vessels in 5 km <sup>2</sup> area at any time |
|                       | Support (crew boats, SOVs, service, diver & PLGR & dredging) | 79  | 6888        |                   |    |                               |                                                       |
|                       | Transport                                                    | 20  | 2138        |                   |    |                               |                                                       |
|                       | Main laying (barge & tug)                                    | 7   | 495         |                   |    |                               |                                                       |
|                       | Main burying                                                 | 7   | 495         |                   |    |                               |                                                       |
|                       | Main jointing                                                | 4   | 120         |                   |    |                               |                                                       |
|                       | TOTAL                                                        | 126 | 10,774      |                   |    |                               |                                                       |
| Sofia                 |                                                              |     |             | Large O&M         | 3  | 40                            |                                                       |

| PROJECT       | CONSTRUCTION VESSELS                                                                                                                                                                                                                                                                                       |     |                                                                         | O&M VESSELS       |    |             | NOTES                                                                                                                         |
|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|-------------------------------------------------------------------------|-------------------|----|-------------|-------------------------------------------------------------------------------------------------------------------------------|
|               | TYPE                                                                                                                                                                                                                                                                                                       | #   | ROUND TRIPS                                                             | TYPE              | #  | ROUND TRIPS |                                                                                                                               |
|               | Large & medium crane; Floating & dynamic positioning & jack up; Transport & feeder; Tugs & anchor handling; Hotel & accommodation; Personnel transfer; Dredging; Seabed preparation & aggregate handling; Diving support; General offshore & subsea construction; Cable installation & maintenance; Survey | 396 | Construction vessel: 5150                                               | Small O&M         | 11 | 430         | Max 66 vessels offshore during construction per project (peak in year 2)<br><br>Max 26 vessels on site at any time during O&M |
|               |                                                                                                                                                                                                                                                                                                            |     | Materials transport vessel: 660<br><br>For the full construction period | Lift              | 2  | 40          |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Cable maintenance | 2  | 10          |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Auxiliary         | 8  | 210         |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Service           | 2  | 52          |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Support           | 11 | 4015        |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         |                   |    |             |                                                                                                                               |
|               | TOTAL                                                                                                                                                                                                                                                                                                      |     | 5810                                                                    | TOTAL             | 39 | 4015        |                                                                                                                               |
| Dogger Bank C | Large & medium crane; Floating & dynamic positioning & jack up; Transport & feeder; Tugs & anchor handling; Hotel & accommodation; Personnel transfer; Dredging; Seabed preparation & aggregate handling; Diving support; General offshore & subsea construction; Cable installation & maintenance; Survey | 396 | Construction vessel: 5150                                               | Large O&M         | 3  | 40          | Max 66 vessels offshore during construction per project (peak in year 2)<br><br>Max 26 vessels on site at any time during O&M |
|               |                                                                                                                                                                                                                                                                                                            |     | Materials transport vessel: 660<br><br>For the full construction period | Small O&M         | 11 | 430         |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Lift              | 2  | 40          |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Cable maintenance | 2  | 10          |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Auxiliary         | 8  | 210         |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Service           | 2  | 52          |                                                                                                                               |
|               |                                                                                                                                                                                                                                                                                                            |     |                                                                         | Support           | 11 | 4015        |                                                                                                                               |
|               | TOTAL                                                                                                                                                                                                                                                                                                      |     |                                                                         | TOTAL             | 39 | 4015        |                                                                                                                               |

| PROJECT               | CONSTRUCTION VESSELS                                                                                                                                                                                                                                                                            |   |                                         | O&M VESSELS                                     |    |             | NOTES                                                                                                                                                        |
|-----------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|-----------------------------------------|-------------------------------------------------|----|-------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|
|                       | TYPE                                                                                                                                                                                                                                                                                            | # | ROUND TRIPS                             | TYPE                                            | #  | ROUND TRIPS |                                                                                                                                                              |
| East Anglia Two       | Dredging; Tugs & storage barges; Jack-up; Dynamic Position (DP) Heavy Lift (HLV); Support; Platform installation; Accommodation; Windfarm service; Supply; Inter-array cable laying; Export cable laying; Export cable support; Pre-trenching / backfilling; Cable jetting & survey; Workboats. |   | average 1632 per year and 136 per month | Assumed similar or less than construction phase |    |             | Max. 74 vessels on site at any one time (including max 3 IAC vessels and 5 EC vessels)                                                                       |
|                       | TOTAL                                                                                                                                                                                                                                                                                           |   | 3672                                    | TOTAL                                           |    |             | No total for overall vessels given<br><br>Approx. 27-month construction period                                                                               |
| East Anglia One North | Dredging; Tugs & storage barges; Jack-up; Dynamic Position (DP) Heavy Lift (HLV); Support; Platform installation; Accommodation; Windfarm service; Supply; Inter-array cable laying; Export cable laying; Export cable support; Pre-trenching / backfilling; Cable jetting & survey; Workboats. |   | average 1488 per year, 124 per month    | Support                                         | NS | 687         | Max. 74 vessels on site at any one time (including max 3 IAC vessels and 5 EC vessels)                                                                       |
|                       | TOTAL                                                                                                                                                                                                                                                                                           |   | 3335                                    | TOTAL                                           |    |             | No total for overall vessels given<br><br>Approx. 27-month construction period                                                                               |
| Norfolk Boreas        | Seabed preparation, including dredging, Tugs and barges, Jack-up, Dynamic Position Heavy Lift Vessel, Scour, Substation / collector station installation, Array cable laying, Export cable laying, Landfall cable installation, Pre-trenching / backfilling, Cable jetting and                  |   |                                         | Support                                         | NS | 687         | Max 57 vessel on site at any time;<br><br>Approx. 36 vessels per month during the 36-month construction period for single phase development or approximately |

| PROJECT                      | CONSTRUCTION VESSELS                                                                                                                                                                                                                                                |   |                      | O&M VESSELS                                                                           |    |             | NOTES                                                                               |
|------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---|----------------------|---------------------------------------------------------------------------------------|----|-------------|-------------------------------------------------------------------------------------|
|                              | TYPE                                                                                                                                                                                                                                                                | # | ROUND TRIPS          | TYPE                                                                                  | #  | ROUND TRIPS |                                                                                     |
|                              | survey, Filter layer, Commissioning, Crew transfer, Support and service, Accommodation, WTG installation, Other.                                                                                                                                                    |   |                      |                                                                                       |    |             | 33 vessels per month during 39-month construction period for two phase development. |
|                              | TOTAL                                                                                                                                                                                                                                                               |   | 1296                 | TOTAL                                                                                 |    | 445         |                                                                                     |
| Norfolk Vanguard East & West | Seabed preparation; Transition piece installation; Scour Installation; Foundations; WTG installation; Commissioning; Accommodation; Inter-array cable laying; Export cable laying; Landfall cable installation; Substation / collector station installation; Other. |   |                      | Support                                                                               | NS | 440         |                                                                                     |
|                              | TOTAL                                                                                                                                                                                                                                                               |   | 1180 (590 x 2 phase) | TOTAL                                                                                 |    | 440         |                                                                                     |
| East Anglia Three            | Construction screened out                                                                                                                                                                                                                                           |   |                      | Service                                                                               | 2  | 52          |                                                                                     |
|                              |                                                                                                                                                                                                                                                                     |   |                      | WTG support                                                                           | 11 | 4015        |                                                                                     |
|                              |                                                                                                                                                                                                                                                                     |   |                      | TOTAL                                                                                 | 13 | 4067        |                                                                                     |
| Erebus                       | Max 6 vessels offshore at any one time                                                                                                                                                                                                                              |   |                      | Min 2 vessel visits per turbine per year<br>Max 12 vessel visits per turbine per year |    |             |                                                                                     |
|                              |                                                                                                                                                                                                                                                                     |   |                      |                                                                                       |    |             |                                                                                     |
| Dublin Array                 | No data available                                                                                                                                                                                                                                                   |   |                      |                                                                                       |    |             |                                                                                     |
| Arklow Bank Phase 2          | No data available                                                                                                                                                                                                                                                   |   |                      |                                                                                       |    |             |                                                                                     |
| West Wave Demo               | No data available                                                                                                                                                                                                                                                   |   |                      |                                                                                       |    |             |                                                                                     |

## 7.14 Inter-relationships

329 Inter-relationships are considered to be the impacts and associated effects of different aspects of the proposal on the same receptor. These are considered to be:

- ▲ Project lifetime effects: Assessment of the scope for effects that occur throughout more than one phase of the project (construction, O&M and decommissioning); to interact to potentially create a more significant effect on a receptor than if just assessed in isolation in these three key project stages (e.g. subsea noise effects from piling, operational WTGs, vessels and decommissioning); and
- ▲ Receptor led effects: Assessment of the scope for all effects to interact, spatially and temporally, to create inter-related effects on a receptor. As an example, all effects on benthic ecology such as direct habitat loss or disturbance, sediment plumes, scour, jack up vessel use etc., may interact to produce a different, or greater effect on this receptor than when the effects are considered in isolation. Receptor-led effects might be short-term, temporary or transient effects, or incorporate longer term effects.

330 A description of the likely inter-related effects arising from AyM on marine mammal ecology provided in Volume 2, Chapter 14: Inter-relationships, with a summary of assessed inter-relationships provided below:

- ▲ Collision risk from vessel activity in the area (sections 7.11.2 and 7.12.2);
- ▲ Disturbance from vessel activity (sections 7.10.8, 7.11.3 and 7.12.3);
- ▲ Changes to water quality (sections 7.10.9, 7.11.4 and 7.12.4); and
- ▲ Changes to marine mammal prey species (sections 7.10.10, 7.11.5 and 7.12.5).

331 The impact of inter-relationships between marine mammals and vessel disturbance has been assessed as **negligible adverse significance** to **minor adverse significance**. The impact of inter-relationships between marine mammals and collision risk, changes to water quality and prey species has been assessed as not significant. Overall, no inter-relationships have been identified where an accumulation of residual impacts on marine mammals and the relationship between those impacts gives rise to a need for additional mitigation beyond the embedded mitigation already considered.

## 7.15 Transboundary effects

- 332 Transboundary effects are defined as those effects upon the receiving environment of other European Economic Area (EEA) states, whether occurring from AyM alone, or cumulatively with other projects in the wider area.
- 333 There may be behavioural disturbance or displacement of marine mammals from the AyM site as a result of underwater noise. Behavioural disturbance resulting from underwater noise during construction could occur over large ranges (tens of kilometres) and therefore there is the potential for transboundary effects to occur where subsea noise arising from AyM could extend into waters of other EEA states. AyM OWF is located in close proximity to other states (e.g. Irish waters and Manx waters) and therefore there is the potential for transit of certain species between areas.
- 334 The mobile nature of marine mammals also results in the potential for transboundary effects to occur. Whilst each species has been assessed within the relevant MU for the AyM array, the MUs under which each species has been assessed varies greatly in the area covered, with the MUs for Risso's dolphin and minke whale covering the 'Celtic and Greater North Sea' area. Furthermore, the respective MUs do not represent closed populations. This means that impacts, whilst localised, could potentially affect other MUs if mixing between the assessed populations occurs.
- 335 Any transboundary impacts that do occur as a result of AyM are predicted to be short-term and intermittent, with the recovery of marine mammal populations to affected areas following the completion of construction activities.
- 336 The magnitude of the impact has been assessed as **negligible** adverse to **low** adverse and the sensitivity of receptors as **negligible** to **low**. Therefore, the significance of behavioural disturbance leading to transboundary effects is concluded to be of **minor adverse significance**, which is not significant in terms of the EIA regulations.



## 7.16 Summary of effects

- 337 This chapter has assessed the potential effects on marine mammal receptors arising from AyM. The impacts considered include direct impacts (e.g. disturbance from piling), as well as indirect impacts (e.g. change in prey species abundance), alongside cumulative impacts (e.g. underwater noise from various offshore energy developments within the species MU). Potential impacts considered in this chapter, alongside any mitigation and residual effects are summarised in Table 60.
- 338 Throughout the construction, operation and decommissioning phases of AyM, all impacts assessed were found to have either negligible, or minor effects on all marine mammal receptors and thus no impact pathway was considered to be significant in regard of the EIA Regulations.
- 339 The assessment of cumulative impacts from AyM and other developments and activities concluded that the effects of any cumulative impacts would be of minor significance at the most, and thus no cumulative impact pathway was considered to be significant in regard of the EIA Regulations.

Table 60: Summary of effects (HP = harbour porpoise, BND = bottlenose dolphin, CD = common dolphin, RD = Risso's dolphin, MW = minke whale, GS = grey seal).

| IMPACT                                         | SPECIES | MAGNITUDE  | SENSITIVITY | MITIGATION                                    | RESIDUAL                        |
|------------------------------------------------|---------|------------|-------------|-----------------------------------------------|---------------------------------|
| Construction                                   |         |            |             |                                               |                                 |
| PTS from piling                                | HP      | Negligible | Low         | None beyond embedded mitigation (piling MMMP) | Negligible adverse significance |
|                                                | BND     | Negligible | Medium      |                                               | Minor adverse significance      |
|                                                | CD      | Negligible | Medium      |                                               | Minor adverse significance      |
|                                                | RD      | Negligible | Medium      |                                               | Minor adverse significance      |
|                                                | MW      | Negligible | Low         |                                               | Negligible adverse significance |
|                                                | GS      | Negligible | Low         |                                               | Negligible adverse significance |
| Disturbance from piling                        | HP      | Low-Medium | Low         | None beyond embedded mitigation (piling MMMP) | Minor adverse significance      |
|                                                | BND     | Medium     | Low         |                                               | Minor adverse significance      |
|                                                | CD      | Low        | Low         |                                               | Minor adverse significance      |
|                                                | RD      | Low        | Low         |                                               | Minor adverse significance      |
|                                                | MW      | Low        | Low         |                                               | Minor adverse significance      |
|                                                | GS      | Low        | Negligible  |                                               | Negligible adverse significance |
| Disturbance from other construction activities | HP      | Low        | Low         | None                                          | Minor adverse significance      |
|                                                | BND     | Low        | Low         |                                               | Minor adverse significance      |
|                                                | CD      | Low        | Low         |                                               | Minor adverse significance      |
|                                                | RD      | Low        | Low         |                                               | Minor adverse significance      |
|                                                | MW      | Low        | Low         |                                               | Minor adverse significance      |
|                                                | GS      | Low        | Negligible  |                                               | Negligible adverse significance |
| PTS from UXO                                   | HP      | Negligible | Low         | None beyond embedded mitigation (UXO MMMP)    | Negligible adverse significance |
|                                                | BND     | Negligible | Medium      |                                               | Minor adverse significance      |
|                                                | CD      | Negligible | Medium      |                                               | Minor adverse significance      |
|                                                | RD      | Negligible | Medium      |                                               | Minor adverse significance      |
|                                                | MW      | Negligible | Low         |                                               | Negligible adverse significance |
|                                                | GS      | Negligible | Low         |                                               | Negligible adverse significance |

| IMPACT                                 | SPECIES | MAGNITUDE  | SENSITIVITY | MITIGATION                                                | RESIDUAL                        |
|----------------------------------------|---------|------------|-------------|-----------------------------------------------------------|---------------------------------|
| Disturbance from UXO                   | HP      | Low        | Low         | None beyond embedded mitigation (UXO MMMP)                | Minor adverse significance      |
|                                        | BND     | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | CD      | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | RD      | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | MW      | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | GS      | Low        | Negligible  |                                                           | Negligible adverse significance |
| Collision risk from vessels            | All     | Negligible | High        | None beyond embedded mitigation (vessel codes of conduct) | Minor adverse significance      |
| Disturbance from vessels               | HP      | Low        | Low         | None beyond embedded mitigation (vessel codes of conduct) | Minor adverse significance      |
|                                        | BND     | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | CD      | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | RD      | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | MW      | Low        | Low         |                                                           | Minor adverse significance      |
|                                        | GS      | Low        | Negligible  |                                                           | Negligible adverse significance |
| Change in water quality                | All     | Negligible | Negligible  | None                                                      | Negligible adverse significance |
| Change in fish abundance/ distribution | All     | Negligible | Low         | None                                                      | Negligible adverse significance |
| <b>Operation</b>                       |         |            |             |                                                           |                                 |
| Barrier effects                        | All     | Negligible | Negligible  | None                                                      | Negligible adverse significance |
| Collision risk from vessels            | All     | Negligible | High        | None beyond embedded mitigation (vessel codes of conduct) | Minor adverse significance      |
|                                        | HP      | Low        | Low         |                                                           | Minor adverse significance      |

| IMPACT                                 | SPECIES | MAGNITUDE                                    | SENSITIVITY | MITIGATION                                                | RESIDUAL                        |
|----------------------------------------|---------|----------------------------------------------|-------------|-----------------------------------------------------------|---------------------------------|
| Disturbance from vessels               | BND     | Low                                          | Low         | None beyond embedded mitigation (vessel codes of conduct) | Minor adverse significance      |
|                                        | CD      | Low                                          | Low         |                                                           | Minor adverse significance      |
|                                        | RD      | Low                                          | Low         |                                                           | Minor adverse significance      |
|                                        | MW      | Low                                          | Low         |                                                           | Minor adverse significance      |
|                                        | GS      | Low                                          | Negligible  |                                                           | Negligible adverse significance |
| Change in water quality                | All     | No impact pathway                            |             |                                                           |                                 |
| Change in fish abundance/ distribution | All     | Negligible                                   | Low         | None                                                      | Negligible adverse significance |
| Decommissioning                        |         |                                              |             |                                                           |                                 |
| PTS & disturbance                      | All     | Assumed similar or lesser extent than piling |             |                                                           |                                 |
| Collision risk from vessels            | All     | Negligible                                   | High        | None beyond embedded mitigation (vessel codes of conduct) | Minor adverse significance      |
| Disturbance from vessels               | HP      | Low                                          | Low         | None beyond embedded mitigation (vessel codes of conduct) | Minor adverse significance      |
|                                        | BND     | Low                                          | Low         |                                                           | Minor adverse significance      |
|                                        | CD      | Low                                          | Low         |                                                           | Minor adverse significance      |
|                                        | RD      | Low                                          | Low         |                                                           | Minor adverse significance      |
|                                        | MW      | Low                                          | Low         |                                                           | Minor adverse significance      |
|                                        | GS      | Low                                          | Negligible  |                                                           | Negligible adverse significance |
| Change in water quality                | All     | Negligible                                   | Negligible  | None                                                      | Negligible adverse significance |
| Change in fish abundance/ distribution | All     | Negligible                                   | Low         | None                                                      | Negligible adverse significance |
| Cumulative effects                     |         |                                              |             |                                                           |                                 |
|                                        | HP      | Low                                          | Low         |                                                           | Minor adverse significance      |

| IMPACT                            | SPECIES | MAGNITUDE    | SENSITIVITY | MITIGATION                                                | RESIDUAL                        |
|-----------------------------------|---------|--------------|-------------|-----------------------------------------------------------|---------------------------------|
| Disturbance from underwater noise | BND     | Medium       | Low         | None beyond embedded mitigation (piling MMMP)             | Minor adverse significance      |
|                                   | CD      | Medium       | Low         |                                                           | Minor adverse significance      |
|                                   | RD      | Low          | Low         |                                                           | Minor adverse significance      |
|                                   | MW      | Medium       | Low         |                                                           | Minor adverse significance      |
|                                   | GS      | Medium       | Neg         |                                                           | Negligible adverse significance |
| Disturbance from vessels          | HP      | Negligible   | Low         | None beyond embedded mitigation (vessel codes of conduct) | Negligible adverse significance |
|                                   | BND     | Screened out |             |                                                           | Screened out                    |
|                                   | CD      | Negligible   | Low         |                                                           | Negligible adverse significance |
|                                   | RD      | Negligible   | Low         |                                                           | Negligible adverse significance |
|                                   | MW      | Low          | Low         |                                                           | Minor adverse significance      |
|                                   | GS      | Negligible   | Low         |                                                           | Negligible adverse significance |

## 7.17 References

- Aarts, G., S. Brasseur, and R. Kirkwood. 2018. Behavioural response of grey seals to pile-driving. Wageningen Marine Research report C006/18.
- Adams, J. 2017. Manx Whale and Dolphin Watch land-based surveyor network report 2016.
- Angel Bay Seal Volunteer Group. 2021. Angel Bay Seal Data Summary 2020/2021.
- Arons, A. 1954. Underwater explosion shock wave parameters at large distances from the charge. *The Journal of the Acoustical Society of America* 26:343-346.
- Baines, M. E., and P. G. H. Evans. 2012. *Atlas of the Marine Mammals of Wales*. Countryside Council for Wales.
- Barett, R. 1996. Guidelines for the safe use of explosives underwater. MTD Publication 96:101.
- Beck, C. A., W. D. Bowen, and S. J. Iverson. 2003. Sex differences in the seasonal patterns of energy storage and expenditure in a phocid seal. *Journal of Animal Ecology* 72:280-291.
- Benhemma-Le Gall, A., I. Graham, N. Merchant, and P. Thompson. 2021. Broad-scale responses of harbor porpoises to pile-driving and vessel activities during offshore windfarm construction. *Frontiers in Marine Science* 8.
- Benhemma-Le Gall, A., P. Thompson, I. Graham, and N. Merchant. 2020. Lessons learned: harbour porpoises respond to vessel activities during offshore windfarm construction. *in* *Environmental Interactions of Marine Renewables 2020*, Online.
- Berrow, S. D., and E. Rogan. 1995. Stomach contents of harbour porpoises and dolphins in Irish waters. *European Research on Cetaceans* 9:179-181.
- Blix, A., and L. Folkow. 1995. Daily energy expenditure in free living minke whales. *Acta Physiologica Scandinavica* 153:61-66.
- Booth, C., and F. Heinis. 2018. Updating the Interim PCoD Model: Workshop Report - New transfer functions for the effects of permanent threshold shifts on vital rates in marine mammal species. Report Code SMRUC-UOA-2018-006, submitted to the University of Aberdeen and



Department for Business, Energy and Industrial Strategy (BEIS), June 2018 (unpublished).

- Booth, C. G., F. Heinis, and H. J. 2019. Updating the Interim PCoD Model: Workshop Report - New transfer functions for the effects of disturbance on vital rates in marine mammal species. Report Code SMRUC-BEI-2018-011, submitted to the Department for Business, Energy and Industrial Strategy (BEIS), February 2019 (unpublished).
- Brandt, M. J., A. Diederichs, K. Betke, and G. Nehls. 2011. Responses of harbour porpoises to pile driving at the Horns Rev II offshore wind farm in the Danish North Sea. *Marine Ecology Progress Series* 421:205-216.
- Brandt, M. J., A.-C. Dragon, A. Diederichs, M. A. Bellmann, V. Wahl, W. Piper, J. Nabe-Nielsen, and G. Nehls. 2018. Disturbance of harbour porpoises during construction of the first seven offshore wind farms in Germany. *Marine Ecology Progress Series* 596:213-232.
- Brandt, M. J., A. Dragon, A. Diederichs, A. Schubert, V. Kosarev, G. Nehls, V. Wahl, A. Michalik, A. Braasch, C. Hinz, C. Katzer, D. Todeskino, M. Gauger, M. Laczny, and W. Piper. 2016. Effects of offshore pile driving on harbour porpoise abundance in the German Bight.
- Brandt, M. J., C. Hoeschle, A. Diederichs, K. Betke, R. Matuschek, S. Witte, and G. Nehls. 2013. Far-reaching effects of a seal scarer on harbour porpoises, *Phocoena phocoena*. *Aquatic Conservation-Marine and Freshwater Ecosystems* 23:222-232.
- Brasseur, S., G. Aarts, E. Meesters, T. van Polanen Petel, E. Dijkman, J. Cremer, and P. Reijnders. 2012. Habitat preference of harbour seals in the Dutch coastal area: analysis and estimate of effects of offshore wind farms.
- Brophy, J., S. Murphy, and E. Rogan. 2009. The diet and feeding ecology of the short-beaked common dolphin (*Delphinus delphis*) in the northeast Atlantic. IWC Scientific Committee Document SC/61/SM 14.
- Burt, M., D. Borchers, and F. I. Samarra. 2006. SCANS II Appendix D3.3 Aerial survey abundance estimates for minke whale and dolphins.
- Carter, M., L. Boehme, C. Duck, W. Grecian, G. Hastie, B. McConnell, D. Miller, C. Morris, S. Moss, D. Thompson, P. Thompson, and D. Russell. 2020. Habitat-based predictions of at-sea distribution for grey and harbour

- seals in the British Isles. Sea Mammal Research Unit, University of St Andrews, Report to BEIS, OESEA-16-76/OESEA-17-78.
- CEFAS. 2010. Strategic review of offshore wind farm monitoring data associated with FEPA licence conditions – annex 4: underwater noise., Cefas report ME1117.
- Christiansen, F., M. Rasmussen, and D. Lusseau. 2013. Whale watching disrupts feeding activities of minke whales on a feeding ground. *Marine Ecology Progress Series* 478:239-+.
- Clarke, M. R., and P. Pascoe. 1985. The stomach contents of a Risso's dolphin (*Grampus griseus*) stranded at Thurlestone, South Devon. *Journal of the Marine Biological Association of the United Kingdom* 65:663-665.
- CMACS Ltd. 2005. Gwynt y Môr Offshore Wind Farm Marine Ecology Technical Report. Report number: J3004/2005, Report to: npower renewables.
- CMACS Ltd. 2011. Gwynt y Môr Offshore Wind Farm Marine Mammal Monitoring Baseline Report.
- CMACS Ltd. 2013. Gwynt Y Môr (GYM) Offshore Wind Farm Marine Mammal Mitigation First Year Construction Mitigation Report v1.
- Cranford, T. W., and P. Krysl. 2015. Fin whale sound reception mechanisms: skull vibration enables low-frequency hearing. *PLoS ONE* 10:e0116222.
- CSIP. 2011. Final Report for the period 1st January 2005 – 31st December 2010 (Covering contract numbers CR0346 and CR0364). Compiled by R. Deaville and P.D. Jepson (ZSL). Contributing authors: Brownlow, A & Reid, RJ (SAC) Smith, B; Duffell, EL & Sabin, RC (NHM) Penrose, R (MEM) & Perkins, M (ZSL).
- CSIP. 2012. Annual Report for the period 1st January – 31st December 2011 (Covering contract numbers MB0111 and CR0364). Compiled by R. Deaville (ZSL). Contributing Authors: P.D. Jepson and M. Perkins (ZSL) A. Brownlow and R.J. Reid (SAC) B. Smith, E. L. Duffell and R.C. Sabin (NHM) R. Penrose (MEM).
- CSIP. 2013. Annual Report for the period 1st January – 31st December 2012 (Contract number MB0111). Compiled by R. Deaville (ZSL). Contributing Authors: A. Brownlow, N. Davison and B. McGovern (SRUC), B. Smith, E. L. Duffell, M. Clery and R.C. Sabin (NHM), R. Penrose (MEM), P.D. Jepson and M. Perkins (ZSL).

- CSIP. 2014. Annual Report for the period 1st January – 31st December 2013 (Contract number MB0111). Compiled by R. Deaville (ZSL).  
Contributing Authors: A. Brownlow and N. Davison (SRUC), B. Smith, M. Clery and R.C. Sabin (NHM), R. Penrose (MEM), P.D. Jepson and M. Perkins (ZSL).
- CSIP. 2015. Annual Report for the period 1st January – 31st December 2014 (Contract number MB0111). Compiled by R. Deaville (ZSL).  
Contributing Authors: P.D. Jepson and M. Perkins (ZSL) A. Brownlow, N. Davison and M. ten Doeschate (SRUC) B. Smith, R. Lyal and R.C. Sabin (NHM) R. Penrose (MEM).
- CSIP. 2016. Annual Report for the period 1st January – 31st December 2015 (Contract number MB0111). Compiled by R. Deaville (ZSL).  
Contributing Authors: P.D. Jepson and M. Perkins (ZSL) A. Brownlow, N. Davison and M. ten Doeschate (SRUC) B. Smith, R. Lyal, L. Allan and R.C. Sabin (NHM) R. Penrose (MEM).
- CSIP. 2017. Annual Report for the period 1st January – 31st December 2016 (Contract number MB0111). Compiled by R. Deaville (ZSL).  
Contributing authors: P.D. Jepson and M. Perkins (ZSL), A. Brownlow, N. Davison and M. ten Doeschate (SRUC), B. Smith, L. Allan and R.C. Sabin (NHM), R. Penrose (MEM), J.E.F. Barnett, N. Clear, A. Crosby and R. Williams (CWTMSN/UoE).
- CSIP. 2018. Annual Report for the period 1st January – 31st December 2017 (Contract numbers MB0111 and ME6008). Compiled by R. Deaville (ZSL). Contributing Authors: P.D. Jepson and M. Perkins (ZSL), A. Brownlow, N. Davison and M. ten Doeschate (SRUC), B. Smith, L. Allan, S. Wilson, K. Swindells and R.C. Sabin (NHM), R. Penrose (MEM), J.E.F. Barnett, K. Astley, N. Clear, A. Crosby and R. Williams (UoE/CWTMSN).
- Culloch, R. M., P. Anderwald, A. Brandecker, D. Haberlin, B. McGovern, R. Pinfield, F. Visser, M. Jessopp, and M. Cronin. 2016. Effect of construction-related activities and vessel traffic on marine mammals. *Marine Ecology Progress Series* 549:231-242.
- Dähne, M., A. Gilles, K. Lucke, V. Peschko, S. Adler, K. Krugel, J. Sundermeyer, and U. Siebert. 2013. Effects of pile-driving on harbour porpoises (*Phocoena phocoena*) at the first offshore wind farm in Germany. *Environmental Research Letters* 8.

- DECC. 2011a. National Policy Statement for Renewable Energy Infrastructure (EN-3). Presented to Parliament pursuant to section 5(9) of the Planning Act 2008. Department of Energy and Climate Change, July 2011.
- DECC. 2011b. Overarching National Policy Statement for Energy (EN-1). Presented to Parliament pursuant to Section 5(9) of the Planning Act 2008. Department of Energy and Climate Change, July 2011.
- Deecke, V. B., P. J. Slater, and J. K. Ford. 2002. Selective habituation shapes acoustic predator recognition in harbour seals. *Nature* 420:171-173.
- Dehnhardt, G., B. Mauck, W. Hanke, and H. Bleckmann. 2001. Hydrodynamic trail-following in harbor seals (*Phoca vitulina*). *Science* 293:102-104.
- Diederichs, A., G. Nehls, and M. J. Brandt. 2010. Does sand extraction near Sylt affect harbour porpoises? Wadden Sea Ecosystem No. 26 edition. Common Wadden Sea Secretariat, Wilhelmshaven, Germany.
- Diederichs, A., G. Nehls, M. Dähne, S. Adler, S. Koschinski, and U. Verfuß. 2008. Methodologies for measuring and assessing potential changes in marine mammal behaviour, abundance or distribution arising from the construction, operation and decommissioning of offshore windfarms.
- Duckett, A. 2018. Cardigan Bay bottlenose dolphin (*Tursiops truncatus*) connectivity within and beyond marine protected areas. Bangor University.
- Dunlop, R. A., M. J. Noad, R. D. McCauley, L. Scott-Hayward, E. Kniest, R. Slade, D. Paton, and D. H. Cato. 2017. Determining the behavioural dose-response relationship of marine mammals to air gun noise and source proximity. *Journal of Experimental Biology* 220:2878-2886.
- Dyndo, M., D. M. Wiśniewska, L. Rojano-Doñate, and P. T. Madsen. 2015. Harbour porpoises react to low levels of high frequency vessel noise. *Scientific Reports* 5:11083.
- Edds-Walton, P. L. 2000. Vocalizations Of Minke Whales *Balaenoptera Acutorostrata* In The St. Lawrence Estuary. *Bioacoustics* 11:31-50.
- Evans, P., C. Giulia Bertulli, and J. Waggitt. 2021. CETACEANS OFF THE NORTH WALES COAST.
- Evans, P., and K. Hintner. 2013. Review of the direct and indirect impacts of fishing activities on Marine Mammals in Welsh Waters.

- Evans, P., G. Pierce, G. Veneruso, C. Weir, D. Gibas, P. Anderwald, and M. Begoña Santos. 2015. Analysis of long-term effort-related land-based observations to identify whether coastal areas of harbour porpoise and bottlenose dolphin have persistent high occurrence and abundance (revised June 2015). JNCC Report No. 543, JNCC, Peterborough, ISSN 0963-8091.
- Evans, P. G., and A. Bjørge. 2013. Impacts of climate change on marine mammals. MCCIP Science Review 2013:134-148.
- Evans, W. 1982. Distribution and differentiation of stock of *Delphinus delphis* Linnaeus in the northeastern Pacific. Mammals in the sea 4: small cetaceans, seals, sirenians, and otters. FAO Fisheries series 5:45-66.
- Feingold, D., and P. G. Evans. 2014. Bottlenose dolphin and harbour porpoise monitoring in Cardigan Bay and Pen Llŷn a'r Sarnau Special Areas of Conservation 2011-2013. NRW Evidence Report Series Report No: 4, 120 pp, Natural Resources Wales, Bangor.
- Felce, T. 2014. Cetacean research in Manx waters 2007-2014.
- Felce, T. 2015. Cetacean research in Manx waters 2015.
- Fernandez-Betelu, O., I. M. Graham, K. L. Brookes, B. J. Cheney, T. R. Barton, and P. M. Thompson. 2021. Far-Field Effects of Impulsive Noise on Coastal Bottlenose Dolphins. *Frontiers in Marine Science* 8.
- Finneran, J. J. 2015. Noise-induced hearing loss in marine mammals: A review of temporary threshold shift studies from 1996 to 2015. *The Journal of the Acoustical Society of America* 138:1702-1726.
- Finneran, J. J. 2016. Auditory weighting functions and TTS/PTS exposure functions for marine mammals exposed to underwater noise. SSC Pacific, San Diego, CA 92152-5001.
- Gazo, M., F. Aparicio, M. A. Cedenilla, J. F. Layna, and L. M. González. 2000. Pup survival in the Mediterranean monk seal (*Monachus monachus*) colony at Cabo Blanco Peninsula (Western Sahara-Mauritania). *Marine Mammal Science* 16:158-168.
- Gedamke, J., D. P. Costa, and A. Dunstan. 2001. Localization and visual verification of a complex minke whale vocalization. *The Journal of the Acoustical Society of America* 109:3038-3047.

- Genov, T., G. Bearzi, S. Bonizzoni, and M. Tempesta. 2012. Long-distance movement of a lone short-beaked common dolphin *Delphinus delphis* in the central Mediterranean Sea. *Marine Biodiversity Records* 5:e9.
- Goddard, B., S. McGovern, M. Rehfish, R. Buisson, L. Jervis, and S. Warford. 2018. Gwynt y Môr Offshore Wind Farm Post-construction Aerial Surveys Annual Report 2017/2018. APEM Ref P00001859 September 2018.
- Goddard, B., S. McGovern, S. Warford, D. Scott, R. Sheehy, M. Rehfish, and R. Buisson. 2017. Gwynt y Môr Offshore Wind Farm Post-construction Aerial Surveys Annual Report 2016/2017. APEM Ref P00000577 July 2017.
- Goold, J. C. 1996. Acoustic assessment of populations of common dolphin *Delphinus delphis* in conjunction with seismic surveying. *JOURNAL-MARINE BIOLOGICAL ASSOCIATION OF THE UNITED KINGDOM* 76:811-820.
- Gordon, J., D. Thompson, R. Leaper, D. Gillespie, C. Pierpoint, S. Calderan, V, J. Macaulay, and T. Gordon. 2011. Assessment of Risk to Marine Mammals from Underwater Marine Renewable Devices in Welsh waters Phase 2 - Studies of Marine Mammals in Welsh High Tidal Waters.
- Goulding, A., L. Jervis, N. Dominguez Alvarez, and S. McGovern. 2019. Gwynt y Môr Offshore Wind Farm Post-construction Aerial Surveys Annual Report 2018/2019. APEM Ref P00002798 June 2019.
- Graham, I. M., A. Farcas, N. D. Merchant, and P. Thompson. 2017a. Beatrice Offshore Wind Farm: An interim estimate of the probability of porpoise displacement at different unweighted single-pulse sound exposure levels. Prepared by the University of Aberdeen for Beatrice Offshore Windfarm Ltd.
- Graham, I. M., N. D. Merchant, A. Farcas, T. R. C. Barton, B. Cheney, S. Bono, and P. M. Thompson. 2019. Harbour porpoise responses to pile-driving diminish over time. *Royal Society Open Science* 6:190335.
- Graham, I. M., E. Pirotta, N. D. Merchant, A. Farcas, T. R. Barton, B. Cheney, G. D. Hastie, and P. M. Thompson. 2017b. Responses of bottlenose dolphins and harbor porpoises to impact and vibration piling noise during harbor construction. *Ecosphere* 8.



- Hammond, P., C. Lacey, A. Gilles, S. Viquerat, P. Börjesson, H. Herr, K. Macleod, V. Ridoux, M. Santos, M. Scheidat, J. Teilmann, J. Vingada, and N. Øie. 2021. Estimates of cetacean abundance in European Atlantic waters in summer 2016 from the SCANS-III aerial and shipboard surveys - revised June 2021.
- Hammond, P., C. Lacey, A. Gilles, S. Viquerat, P. Börjesson, H. Herr, K. Macleod, V. Ridoux, M. Santos, M. Scheidat, J. Teilmann, J. Vingada, and N. Øien. 2017. Estimates of cetacean abundance in European Atlantic waters in summer 2016 from the SCANS-III aerial and shipboard surveys.
- Hammond, P., K. McLeod, and M. Scheidat. 2006. Small Cetaceans in the European Atlantic and North Sea (SCANS-II). Final Report. Saint Andrews.
- Harwood, J., S. King, R. Schick, C. Donovan, and C. Booth. 2014. A protocol for Implementing the Interim Population Consequences of Disturbance (PCoD) approach: Quantifying and assessing the effects of UK offshore renewable energy developments on marine mammal populations. Report Number SMRUL-TCE-2013-014. Scottish Marine And Freshwater Science, 5(2).
- Hastie, G. D., P. Lepper, J. C. McKnight, R. Milne, D. J. F. Russell, and D. Thompson. 2021. Acoustic risk balancing by marine mammals: anthropogenic noise can influence the foraging decisions by seals. *Journal of Applied Ecology* n/a.
- Hastie, G. D., D. J. Russell, S. Benjamins, S. Moss, B. Wilson, and D. Thompson. 2016. Dynamic habitat corridors for marine predators; intensive use of a coastal channel by harbour seals is modulated by tidal currents. *Behavioral Ecology and Sociobiology*:1-14.
- Hastie, G. D., D. J. F. Russell, B. McConnell, S. Moss, D. Thompson, and V. M. Janik. 2015. Sound exposure in harbour seals during the installation of an offshore wind farm: predictions of auditory damage. *Journal of Applied Ecology* 52:631-640.
- Heinänen, S., and H. Skov. 2015. The identification of discrete and persistent areas of relatively high harbour porpoise density in the wider UK marine area. JNCC Report No. 544, JNCC, Peterborough.
- Hermanssen, L., K. Beedholm, J. Tougaard, and P. T. Madsen. 2014. High frequency components of ship noise in shallow water with a discussion

- of implications for harbor porpoises (*Phocoena phocoena*). The Journal of the Acoustical Society of America 136:1640-1653.
- Hernandez-Milian, G., M. Santos, and E. Rogan. 2011. Harbour porpoise and bottlenose dolphin in Ireland: diet and interactions with fisheries.
- Hin, V., J. Harwood, and A. M. de Roos. 2019. Bio-energetic modeling of medium-sized cetaceans shows high sensitivity to disturbance in seasons of low resource supply. Ecological Applications:e01903.
- HM Government. 2011. UK Marine Policy Statement. HM Government, Northern Ireland Executive, Scottish Government, Welsh Assembly Government.
- Hoekendijk, J., J. Spitz, A. J. Read, M. F. Leopold, and M. C. Fontaine. 2018. Resilience of harbor porpoises to anthropogenic disturbance: Must they really feed continuously? Marine Mammal Science 34:258-264.
- Houser, D. S., W. Yost, R. Burkard, J. J. Finneran, C. Reichmuth, and J. Mulsow. 2017. A review of the history, development and application of auditory weighting functions in humans and marine mammals. The Journal of the Acoustical Society of America 141:1371-1413.
- Howe, L. 2018. Marine Mammals-Cetaceans. In; Manx Marine Environmental Assessment (1.1 Edition - partial update).
- IAMMWG. 2015. Management Units for cetaceans in UK waters (January 2015). JNCC Report No: 547.
- IAMMWG. 2021. Updated abundance estimates for cetacean Management Units in UK waters. JNCC Report No. 680, JNCC Peterborough, ISSN 0963-8091.
- Jacobs. 2018. Wylfa Newydd Project 6.4.88 ES Volume D - WNDA Development App D13-6 - Marine Mammal Baseline Review. PINS Reference Number: EN010007. Application Reference Number: 6.4.88.
- JNCC. 2019a. European Community Directive on the Conservation of Natural Habitats and of Wild Fauna and Flora (92/43/EEC) Fourth Report by the United Kingdom under Article 17 on the implementation of the Directive from January 2013 to December 2018 Conservation status assessment for the species: S1349 - Bottlenose dolphin (*Tursiops truncatus*) UNITED KINGDOM.
- JNCC. 2019b. European Community Directive on the Conservation of Natural Habitats and of Wild Fauna and Flora (92/43/EEC) Fourth Report by

the United Kingdom under Article 17 on the implementation of the Directive from January 2013 to December 2018 Conservation status assessment for the species: S1350 - Common dolphin (*Delphinus delphis*) UNITED KINGDOM.

JNCC. 2019c. European Community Directive on the Conservation of Natural Habitats and of Wild Fauna and Flora (92/43/EEC) Fourth Report by the United Kingdom under Article 17 on the implementation of the Directive from January 2013 to December 2018 Conservation status assessment for the species: S1351 - Harbour porpoise (*Phocoena phocoena*) UNITED KINGDOM.

JNCC. 2019d. European Community Directive on the Conservation of Natural Habitats and of Wild Fauna and Flora (92/43/EEC) Fourth Report by the United Kingdom under Article 17 on the implementation of the Directive from January 2013 to December 2018 Conservation status assessment for the species: S1364 - Grey seal (*Halichoerus grypus*) UNITED KINGDOM.

JNCC. 2019e. European Community Directive on the Conservation of Natural Habitats and of Wild Fauna and Flora (92/43/EEC) Fourth Report by the United Kingdom under Article 17 on the implementation of the Directive from January 2013 to December 2018 Conservation status assessment for the species: S2030 - Risso's dolphin (*Grampus griseus*) UNITED KINGDOM.

JNCC. 2019f. European Community Directive on the Conservation of Natural Habitats and of Wild Fauna and Flora (92/43/EEC) Fourth Report by the United Kingdom under Article 17 on the implementation of the Directive from January 2013 to December 2018 Conservation status assessment for the species: S2618 - Minke whale (*Balaenoptera acutorostrata*) UNITED KINGDOM.

JNCC, Natural England, and DAERA. 2020. Guidance for assessing the significance of noise disturbance against Conservation Objectives of harbour porpoise SACs (England, Wales & Northern Ireland). Report No. 654, JNCC, Peterborough.

Jones, E., G. Hastie, S. Smout, J. Onoufriou, N. D. Merchant, K. Brookes, and D. thompson. 2017. Seals and shipping: quantifying population risk and individual exposure to vessel noise. *Journal of Applied Ecology* 54:1930-1940.

- Kastelein, R., N. Jennings, W. Verboom, D. De Haan, and N. Schooneman. 2006. Differences in the response of a striped dolphin (*Stenella coeruleoalba*) and a harbour porpoise (*Phocoena phocoena*) to an acoustic alarm. *Marine Environmental Research* 61:363-378.
- Kastelein, R. A., R. Gransier, L. Hoek, and C. A. de Jong. 2012a. The hearing threshold of a harbor porpoise (*Phocoena phocoena*) for impulsive sounds (L). *Journal of the Acoustical Society of America* 132:607-610.
- Kastelein, R. A., R. Gransier, L. Hoek, A. Macleod, and J. M. Terhune. 2012b. Hearing threshold shifts and recovery in harbor seals (*Phoca vitulina*) after octave-band noise exposure at 4 kHz. *Journal of the Acoustical Society of America* 132:2745-2761.
- Kastelein, R. A., R. Gransier, L. Hoek, and J. Olthuis. 2012c. Temporary threshold shifts and recovery in a harbor porpoise (*Phocoena phocoena*) after octave-band noise at 4kHz. *Journal of the Acoustical Society of America* 132:3525-3537.
- Kastelein, R. A., R. Gransier, L. Hoek, and M. Rambags. 2013. Hearing frequency thresholds of a harbor porpoise (*Phocoena phocoena*) temporarily affected by a continuous 1.5 kHz tone. *Journal of the Acoustical Society of America* 134:2286-2292.
- Kastelein, R. A., R. Gransier, M. A. T. Marijt, and L. Hoek. 2015. Hearing frequency thresholds of harbor porpoises (*Phocoena phocoena*) temporarily affected by played back offshore pile driving sounds. *The Journal of the Acoustical Society of America* 137:556-564.
- Kastelein, R. A., L. Helder-Hoek, J. Covi, and R. Gransier. 2016. Pile driving playback sounds and temporary threshold shift in harbor porpoises (*Phocoena phocoena*): Effect of exposure duration. *The Journal of the Acoustical Society of America* 139:2842-2851.
- Kastelein, R. A., L. Helder-Hoek, S. Van de Voorde, A. M. von Benda-Beckmann, F.-P. A. Lam, E. Jansen, C. A. de Jong, and M. A. Ainslie. 2017. Temporary hearing threshold shift in a harbor porpoise (*Phocoena phocoena*) after exposure to multiple airgun sounds. *The Journal of the Acoustical Society of America* 142:2430-2442.
- Kastelein, R. A., S. Van de Voorde, and N. Jennings. 2018. Swimming Speed of a Harbor Porpoise (*Phocoena phocoena*) During Playbacks of Offshore Pile Driving Sounds. *Aquatic Mammals* 44:92-99.

- Kavanagh, A. S., M. Nykänen, W. Hunt, N. Richardson, and M. J. Jessopp. 2019. Seismic surveys reduce cetacean sightings across a large marine ecosystem. *Scientific Reports* 9:19164.
- Laist, D. W., A. R. Knowlton, J. G. Mead, A. S. Collet, and M. Podesta. 2001. Collisions between ships and whales. *Marine Mammal Science* 17:35-75.
- Langley, I., T. Rosas da Costa Oliver, L. Hiby, C. W. Morris, T. B. Stringell, and P. Pomeroy. 2018. EIRPHOT: A critical assessment of Wales' grey seal (*Halichoerus grypus*) photo-identification database., NRW Evidence Report Series Report No: 280, 94pp, Natural Resources Wales, Bangor.
- Lea, M.-A., D. Johnson, R. Ream, J. Sterling, S. Melin, and T. Gelatt. 2009. Extreme weather events influence dispersal of naive northern fur seals. *Biology Letters* 5:252-257.
- Lindeboom, H. J., H. J. Kouwenhoven, M. J. N. Bergman, S. Bouma, S. Brasseur, R. Daan, R. C. Fijn, D. de Haan, S. Dirksen, R. van Hal, R. Hille Ris Lambers, R. ter Hofstede, K. L. Krijgsveld, M. Leopold, and M. Scheidat. 2011. Short-term ecological effects of an offshore wind farm in the Dutch coastal zone; a compilation. *Environmental Research Letters* 6:1-13.
- Lohrengel, K., P. Evans, C. Lindenbaum, C. Morris, and T. Stringell. 2018. Bottlenose Dolphin Monitoring in Cardigan Bay 2014-2016. Natural Resources Wales, Bangor.
- Lusseau, D. 2003. Male and female bottlenose dolphins *Tursiops* spp. have different strategies to avoid interactions with tour boats in Doubtful Sound, New Zealand. *Marine Ecology Progress Series* 257:267-274.
- Lusseau, D. 2006. The short-term behavioral reactions of bottlenose dolphins to interactions with boats in Doubtful Sound, New Zealand. *Marine Mammal Science* 22:802-818.
- Lusseau, D., L. New, C. Donovan, B. Cheney, P. Thompson, G. Hastie, and J. Harwood. 2011. The development of a framework to understand and predict the population consequences of disturbances for the Moray Firth bottlenose dolphin population. Scottish Natural Heritage Commissioned Report (98pp).
- Madsen, P. T., M. Wahlberg, J. Tougaard, K. Lucke, and P. Tyack. 2006. Wind turbine underwater noise and marine mammals: implications of

- current knowledge and data needs. *Marine Ecology Progress Series* 309:279-295.
- Marubini, F., A. Gimona, P. G. Evans, P. J. Wright, and G. J. Pierce. 2009. Habitat preferences and interannual variability in occurrence of the harbour porpoise *Phocoena phocoena* off northwest Scotland. *Marine Ecology Progress Series* 381:297-310.
- McGarry, T., O. Boisseau, S. Stephenson, and R. Compton. 2017. Understanding the Effectiveness of Acoustic Deterrent Devices (ADDs) on Minke Whale (*Balaenoptera acutorostrata*), a Low Frequency Cetacean. Report for the Offshore Renewables Joint Industry Programme (ORJIP) Project 4, Phase 2. Prepared on behalf of the Carbon Trust.
- McQueen, A. D., B. C. Suedel, C. de Jong, and F. Thomsen. 2020. Ecological risk assessment of underwater sounds from dredging operations. *Integrated environmental assessment and management* 16:481-493.
- Mellinger, D. K., C. D. Carson, and C. W. Clark. 2000. Characteristics of minke whale (*Balaenoptera acutorostrata*) pulse trains recorded near Puerto Rico. *Marine Mammal Science* 16:739-756.
- Morgan, L. H., C. W. Morris, and T. B. Stringell. 2018. Grey Seal Pupping Phenology on Ynys Dewi/Ramsey Island, Pembrokeshire. *Natural Resources Wales*.
- Natoli, A., A. Cañadas, V. Peddemors, A. Aguilar, C. Vaquero, P. Fernandez-Piqueras, and A. Hoelzel. 2006. Phylogeography and alpha taxonomy of the common dolphin (*Delphinus* sp.). *Journal of Evolutionary Biology* 19:943-954.
- Nelms, S. E., H. E. Parry, K. A. Bennett, T. S. Galloway, B. J. Godley, D. Santillo, and P. K. Lindeque. 2019. What goes in, must come out: Combining scat-based molecular diet analysis and quantification of ingested microplastics in a marine top predator. *Methods in Ecology and Evolution* 10:1712-1722.
- New, L. F., J. Harwood, L. Thomas, C. Donovan, J. S. Clark, G. Hastie, P. M. Thompson, B. Cheney, L. Scott-Hayward, and D. Lusseau. 2013. Modelling the biological significance of behavioural change in coastal bottlenose dolphins in response to disturbance. *Functional Ecology* 27:314-322.



- NMFS. 2016. Technical Guidance for Assessing the Effects of Anthropogenic Sound on Marine Mammal Hearing: Underwater Acoustic Thresholds for Onset of Permanent and Temporary Threshold Shifts. Page 189. U.S. Department of Commerce, Silver Spring.
- Nowacek, S. M., R. S. Wells, and A. R. Solow. 2001. Short-term effects of boat traffic on bottlenose dolphins, *Tursiops truncatus*, in Sarasota Bay, Florida. *Marine Mammal Science* 17:673-688.
- NRW. 2020. NRW's position on the use of Marine Mammal Management Units for screening and assessment in Habitats Regulations Assessments for Special Areas of Conservation with marine mammal features.
- Nuuttila, H. K., W. Courteney-Jones, S. Baulch, M. Simon, and P. G. H. Evans. 2017. Don't forget the porpoise: acoustic monitoring reveals fine scale temporal variation between bottlenose dolphin and harbour porpoise in Cardigan Bay SAC. *Marine Biology* 164:50.
- Oakley, J. A., A. T. Williams, and T. Thomas. 2017. Reactions of harbour porpoise (*Phocoena phocoena*) to vessel traffic in the coastal waters of South West Wales, UK. *Ocean & Coastal Management* 138:158-169.
- Otani, S., Y. Naito, A. Kato, and A. Kawamura. 2000. Diving behavior and swimming speed of a free-ranging harbor porpoise, *Phocoena phocoena*. *Marine Mammal Science* 16:811-814.
- Panjerc, T., S. Robinson, P. Theobald, and L. Galley. 2016. Underwater sound measurement data during diamond wire cutting: first description of radiated noise. *in* The Effect of Noise on Aquatic Life, Dublin.
- Paxton, C., L. Scott-Hayward, M. Mackenzie, E. Rexstad, and L. Thomas. 2016. Revised Phase III Data Analysis of Joint Cetacean Protocol Data Resources.
- Pesante, G., P. G. H. Evans, M. E. Baines, and M. McMath. 2008. Abundance and Life History Parameters of Bottlenose Dolphin in Cardigan Bay: Monitoring 2005-2007. CCW Marine Monitoring Report No: 61. 81pp.
- Pierce, G., M. Santos, R. Reid, I. Patterson, and H. Ross. 2004. Diet of minke whales *Balaenoptera acutorostrata* in Scottish (UK) waters with notes on strandings of this species in Scotland 1992–2002. *Journal of the Marine Biological Association of the UK* 84:1241-1244.

- Pierpoint, C. 2008. Harbour porpoise (*Phocoena phocoena*) foraging strategy at a high energy, near-shore site in south-west Wales, UK. *Journal of the Marine Biological Association of the UK* 88:1167-1173.
- Pirotta, E., B. E. Laesser, A. Hardaker, N. Riddoch, M. Marcoux, and D. Lusseau. 2013. Dredging displaces bottlenose dolphins from an urbanised foraging patch. *Marine Pollution Bulletin* 74:396-402.
- Pirotta, E., N. D. Merchant, P. M. Thompson, T. R. Barton, and D. Lusseau. 2015. Quantifying the effect of boat disturbance on bottlenose dolphin foraging activity. *Biological Conservation* 181:82-89.
- Prime, J. 1985. The current status of the grey seal *Halichoerus grypus* in Cornwall, England. *Biological Conservation* 33:81-87.
- Risch, D., C. W. Clark, P. J. Dugan, M. Popescu, U. Siebert, and S. M. Van Parijs. 2013. Minke whale acoustic behavior and multi-year seasonal and diel vocalization patterns in Massachusetts Bay, USA. *Marine Ecology Progress Series* 489:279-295.
- Risch, D., U. Siebert, and S. M. Van Parijs. 2014. Individual calling behaviour and movements of North Atlantic minke whales (*Balaenoptera acutorostrata*). *Behaviour* 151:1335-1360.
- Rogan, E., P. Breen, M. Mackey, A. Cañadas, M. Scheidat, S. Geelhoed, and M. Jessopp. 2018. Aerial surveys of cetaceans and seabirds in Irish waters: Occurrence, distribution and abundance in 2015-2017. Department of Communications, Climate Action & Environment and National Parks and Wildlife Service (NPWS), Department of Culture, Heritage and the Gaeltacht, Dublin, Ireland. 297pp.
- Rojano-Doñate, L., B. I. McDonald, D. M. Wisniewska, M. Johnson, J. Teilmann, M. Wahlberg, J. Højer-Kristensen, and P. T. Madsen. 2018. High field metabolic rates of wild harbour porpoises. *Journal of Experimental Biology* 221:jeb185827.
- Royal Haskoning DHV. 2019. Morlais Project Environmental Statement: Chapter 12: Marine Mammals Vol.1. Applicant: Menter Môn Morlais Limited. Document Reference: PB5034-ES-012. Version F3.0.
- Russell, D., and G. Hastie. 2017. Associating predictions of change in distribution with predicted received levels during piling. Report produced for SMRU Consulting.

- Russell, D., E. Jones, and C. Morris. 2017. Updated Seal Usage Maps: The Estimated at-sea Distribution of Grey and Harbour Seals. Scottish Marine and Freshwater Science Vol 8, No 25.
- Russell, D. J., S. M. Brasseur, D. Thompson, G. D. Hastie, V. M. Janik, G. Aarts, B. T. McClintock, J. Matthiopoulos, S. E. Moss, and B. McConnell. 2014. Marine mammals trace anthropogenic structures at sea. *Current Biology* 24:R638-R639.
- Russell, D. J., G. D. Hastie, D. Thompson, V. M. Janik, P. S. Hammond, L. A. Scott-Hayward, J. Matthiopoulos, E. L. Jones, and B. J. McConnell. 2016a. Avoidance of wind farms by harbour seals is limited to pile driving activities. *Journal of Applied Ecology* 53:1642-1652.
- Russell, D. J. F., G. D. Hastie, D. Thompson, V. M. Janik, P. S. Hammond, L. A. S. Scott-Hayward, J. Matthiopoulos, E. L. Jones, and B. J. McConnell. 2016b. Avoidance of wind farms by harbour seals is limited to pile driving activities. Pages 1642-1652 *Journal of Applied Ecology*.
- Russell, D. J. F., B. McConnell, D. Thompson, C. Duck, C. Morris, J. Harwood, and J. Matthiopoulos. 2013. Uncovering the links between foraging and breeding regions in a highly mobile mammal. *Journal of Applied Ecology* 50:499-509.
- Santos, M., G. Pierce, R. Reid, I. Patterson, H. Ross, and E. Mente. 2001. Stomach contents of bottlenose dolphins (*Tursiops truncatus*) in Scottish waters. *Journal of the Marine Biological Association of the United Kingdom* 81:873-878.
- Santos, M., G. J. Pierce, J. A. Learmonth, R. Reid, H. Ross, I. Patterson, D. Reid, and D. Beare. 2004. Variability in the diet of harbor porpoises (*Phocoena phocoena*) in Scottish waters 1992–2003. *Marine Mammal Science* 20:1-27.
- Sarnocinska, J., J. Teilmann, J. B. Dalgaard, F. v. Beest, M. Delefosse, and J. Tougaard. 2019. Harbour porpoise (*Phocoena phocoena*) reaction to a 3D seismic airgun survey in the North Sea. *Frontiers in Marine Science* 6:824.
- Scheidat, M., J. Tougaard, S. Brasseur, J. Carstensen, T. van Polanen Petel, J. Teilmann, and P. Reijnders. 2011. Harbour porpoises (*Phocoena phocoena*) and wind farms: a case study in the Dutch North Sea. *Environmental Research Letters* 6:1-10.

- SCOS. 2020. Scientific Advice on Matters Related to the Management of Seal Populations: 2019.
- SCOS. 2021. Scientific Advice on Matters Related to the Management of Seal Populations: 2020.
- Scottish Natural Heritage. 2016. Assessing collision risk between underwater turbines and marine wildlife. Scottish Natural Heritage Guidance Note.
- Shucksmith, R., N. H. Jones, G. W. Stoye, A. Davies, and E. F. Dicks. 2009. Abundance and distribution of the harbour porpoise (*Phocoena phocoena*) on the north coast of Anglesey, Wales, UK. *Journal of the Marine Biological Association of the United Kingdom* 89:1051-1058.
- Sinclair, R., S. Kazer, M. Ryder, P. New, and U. Verfuss. 2021. Review and recommendations on assessment of noise disturbance for marine mammals. NRW Evidence Report No. 529.
- Sini, M., S. J. Canning, K. Stockin, and G. J. Pierce. 2005. Bottlenose dolphins around Aberdeen harbour, north-east Scotland: a short study of habitat utilization and the potential effects of boat traffic. *Marine Biological Association of the United Kingdom. Journal of the Marine Biological Association of the United Kingdom* 85:1547.
- Sivle, L. D., P. H. Kvadsheim, C. Curé, S. Isojunno, P. J. Wensveen, F.-P. A. Lam, F. Visser, L. Kleivane, P. L. Tyack, and C. M. Harris. 2015. Severity of expert-identified behavioural responses of humpback whale, minke whale, and northern bottlenose whale to naval sonar. *Aquatic Mammals* 41:469.
- Soloway, A. G., and P. H. Dahl. 2014. Peak sound pressure and sound exposure level from underwater explosions in shallow water. *The Journal of the Acoustical Society of America* 136:EL218-EL223.
- Southall, B., J. J. Finneran, C. Reichmuth, P. E. Nachtigall, D. R. Ketten, A. E. Bowles, W. T. Ellison, D. Nowacek, and P. Tyack. 2019. Marine Mammal Noise Exposure Criteria: Updated Scientific Recommendations for Residual Hearing Effects. *Aquatic Mammals* 45:125-232.
- Southall, B. L., A. E. Bowles, W. T. Ellison, J. J. Finneran, R. L. Gentry, C. R. J. Greene, D. Kastak, D. R. Ketten, J. H. Miller, P. E. Nachtigall, W. J. Richardson, J. A. Thomas, and P. L. Tyack. 2007. Marine mammal noise exposure criteria: initial scientific recommendations. *Aquatic Mammals* 33:411-414.

- Sparling, C. E., J. R. Speakman, and M. A. Fedak. 2006. Seasonal variation in the metabolic rate and body composition of female grey seals: fat conservation prior to high-cost reproduction in a capital breeder? *Journal of Comparative Physiology B* 176:505-512.
- Stone, C. J., K. Hall, S. Mendes, and M. L. Tasker. 2017. The effects of seismic operations in UK waters: analysis of Marine Mammal Observer data. *Journal of Cetacean Research and Management* 16:71-85.
- Stringell, T., D. Hill, D. Rees, F. Rees, P. Rees, G. Morgan, L. Morgan, and C. Morris. 2015. Predation of harbour porpoises (*Phocoena phocoena*) by grey seals (*Halichoerus grypus*) in Wales. *Aquatic Mammals* 41:188.
- Stringell, T. B., C. P. Millar, W. G. Sanderson, S. M. Westcott, and M. J. McMath. 2014. When aerial surveys will not do: grey seal pup production in cryptic habitats of Wales. *Journal of the Marine Biological Association of the United Kingdom*:1-5.
- Strong, P., and S. Morris. 2010. Grey seal (*Halichoerus grypus*) disturbance, ecotourism and the Pembrokeshire Marine Code around Ramsey Island. *Journal of Ecotourism* 9.
- Teilmann, J., J. Carstensen, R. Dietz, S. M. C. Edrén, and S. M. Andersen. 2006a. Final report on aerial monitoring of seals near Nysted Offshore Wind Farm.
- Teilmann, J., J. Tougaard, and J. Carstensen. 2006b. Summary on harbour porpoise monitoring 1999-2006 around Nysted and Horns Rev Offshore Wind Farms.
- Thompson, D. 2015. Parameters for collision risk models. Report by Sea Mammal Research Unit, University of St Andrews, for Scottish Natural Heritage.
- Thompson, P. M., K. L. Brookes, I. M. Graham, T. R. Barton, K. Needham, G. Bradbury, and N. D. Merchant. 2013. Short-term disturbance by a commercial two-dimensional seismic survey does not lead to long-term displacement of harbour porpoises. *Proceedings of the Royal Society B-Biological Sciences* 280:1-8.
- Thompson, P. M., I. M. Graham, B. Cheney, T. R. Barton, A. Farcas, and N. D. Merchant. 2020. Balancing risks of injury and disturbance to marine mammals when pile driving at offshore windfarms. *Ecological Solutions and Evidence* 1.

- Thomsen, F., K. Lüdemann, R. Kafemann, and W. Piper. 2006. Effects of offshore wind farm noise on marine mammals and fish. Biola, Hamburg, Germany on behalf of COWRIE Ltd 62.
- Tougaard, J., S. Buckland, S. Robinson, and B. Southall. 2013. An analysis of potential broad-scale impacts on harbour porpoise from proposed pile driving activities in the North Sea. Report of an expert group convened under the Habitats and Wild Birds Directive - Marine Evidence Group MB0138. 38pp.
- Tubelli, A. A., A. Zosuls, D. R. Ketten, M. Yamato, and D. C. Mountain. 2012. A prediction of the minke whale (*Balaenoptera acutorostrata*) middle-ear transfer function. Journal of the Acoustical Society of America 132:3263-3272.
- Tyack, P., and L. Thomas. 2019. Using dose–response functions to improve calculations of the impact of anthropogenic noise. Aquatic Conservation Marine and Freshwater Ecosystems. 29(S1):242-253.
- Tyack, P. L. 2009. Acoustic playback experiments to study behavioral responses of free-ranging marine animals to anthropogenic sound.
- van Beest, F. M., J. Teilmann, L. Hermannsen, A. Galatius, L. Mikkelsen, S. Sveegaard, J. D. Balle, R. Dietz, and J. Nabe-Nielsen. 2018. Fine-scale movement responses of free-ranging harbour porpoises to capture, tagging and short-term noise pulses from a single airgun. Royal Society Open Science 5:170110.
- Veneruso, G., and P. G. Evans. 2012. Bottlenose Dolphin and Harbour Porpoise Monitoring in Cardigan Bay and Pen Llŷn a'r Sarnau Special Areas of Conservation. CCW Monit Rep 95:65-165.
- Verboom, W. 2014. Preliminary information on dredging and harbour porpoises. JunoBioacoustics.
- Welsh Government. 2019. Welsh National Marine Plan.
- Westgate, A. J., A. J. Head, P. Berggren, H. N. Koopman, and D. E. Gaskin. 1995. Diving behaviour of harbour porpoises, *Phocoena phocoena*. Canadian Journal of Fisheries and Aquatic Sciences 52:1064-1073.
- Whyte, K., D. Russell, C. Sparling, B. Binnerts, and G. Hastie. 2020. Estimating the effects of pile driving sounds on seals: Pitfalls and possibilities. The Effects of Noise on Aquatic Life 14:3948-3958.



- Williams, T. M. 2009. Swimming. *in* W. F. Perrin, Würsig, B. and Thewissen, J.G.M, editor. Encyclopedia of marine mammals.
- Wisniewska, D. M., M. Johnson, J. Teilmann, L. Rojas-Doñate, J. Shearer, S. Sveegaard, L. A. Miller, U. Siebert, and P. T. Madsen. 2016. Ultra-high foraging rates of harbor porpoises make them vulnerable to anthropogenic disturbance. *Current Biology* 26:1441-1446.
- Wisniewska, D. M., M. Johnson, J. Teilmann, U. Siebert, A. Galatius, R. Dietz, and P. T. Madsen. 2018. High rates of vessel noise disrupt foraging in wild harbour porpoises (*Phocoena phocoena*). *Proceedings of the Royal Society B: Biological Sciences* 285:20172314.



RWE Renewables UK Swindon Limited

Windmill Hill Business Park  
Whitehill Way  
Swindon  
Wiltshire SN5 6PB  
T +44 (0)8456 720 090  
[www.rwe.com](http://www.rwe.com)

Registered office:  
RWE Renewables UK Swindon Limited  
Windmill Hill Business Park  
Whitehill Way  
Swindon